### OOD NOTE

THE ACCURACY OF ANY FLOOD HAZARD DATA SHOWN ON THESE PLANS IS SUBJECT TO MAP SCALE UNCERTAINTY AND TO ANY OTHER UNCERTAINTY IN LOCATION OR ELEVATION ON THE REFERENCED FLOOD INSURANCE RATE MAP. THE WITHIN DESCRIBED TRACT OF LAND LIES OUTSIDE OF A FLOOD HAZARD ZONE AS SAID TRACT PLOTS BY SCALE ON COMMUNITY PANEL NUMBER 1804220175C DATED 02/15/1985 FOR THE FLOOD INSURANCE RATE MAPS FOR KNOX COUNTY, INDIANA.

### DISCLAIMER:

CONTRACTOR TO FIELD VERIFY LOCATION AND SIZES OF ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION AND CONTACT ENGINEER AND OWNER IF DISCREPANCIES OCCUR.

REVISIONS:		
REVISION #	REVISION DESCRIPTION	DATE

### CONSTRUCTION PLANS FOR:

### WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS

DIVISION I - WASTEWATER TREATMENT PLANT AND REGIONAL LIFT STATION

WHEATLAND, KNOX COUNTY, INDIANA

### PLANS PREPARED FOR:

TOWN OF WHEATLAND
121 IN-550
WHEATLAND, INDIANA 47597
TELEPHONE: (812) 321-2340
CONTACT PERSON: BRETT DAWSON,
TOWN COUNCIL PRESIDENT
BDAWSON@TOWNOFWHEATLAND.IN



### SITE VICINITY MAP

NOT TO SCALE

NOT TO SCALE

### **OPERATING AUTHORITIES**

ELECTRIC
DUKE ENERGY
1000 E. MAIN ST.
PLAINFIELD, IN 46168
(800) 521-2232

CONTACT: CINDY ROWLAND

ELECTRIC
WIN ENERGY REMC
3981 US-41
VINCENNES, IN 47591
(800) 882-5140
CONTACT: GREGORY WOLVEN

COMMUNICATIONS
NEW WAVE COMMUNICATIONS
102 NORTH FIFTH STREET
VINCENNES, IN 47591
(812) 895-7676
CONTACT: DAVID McCALL

NATURAL GAS
MIDWESTERN GAS TRANSMISSION
1275 N C.R. 550 E
WINSLOW, IN 47598
(812) 354-6620
CONTACT: BRIAN DOBBS

COMMUNICATIONS
FRONTIER COMMUNICATIONS
3401 US-41
TERRE HAUTE, IN 47802
(812) 235-3520
CONTACT: JOE SARLL

COMMUNICATIONS
SPARKLIGHT
102 N. 5TH STREET
VINCENNES, IN 47591
(844) 546-3278
CONTACT: MORGAN FOSTER

NATURAL GAS
CENTERPOINT ENERGY
1 VECTREN SQUARE
EVANSVILLE, IN 47708
(800) 227-1376
CONTACT: N/A

SEWER & WATER
WHEATLAND WATER DEPARTMENT
121 IN-550
WHEATLAND, IN 47597
(812) 321-2340
CONTACT: ERIKA GOBLE (WATER
OFFICE)



BENCH MARK: 1000 B.M. "GEODETIC" STAMPED: US COAST GEODETIC SURVEY BM G314 1965 NORTHING 1244387.030 EASTING 2886880.520

ELEV. = 486.18'

SITE LOCATION MAP

RQ/W
INTENTIONAL INNOVATION

ATLAND WASTEWATER SYSTEM IMPROVEMENTS
ON I - WASTEWATER TREATMEI

Revision Date

Project #: 21-400-194-1
Designed By: WMW
Drawn By: RLH

Date:01/04/2023

Checked By: ALC



TITLE SHEET

G001

### GENERAL NOTES

- 1. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS FOR THIS PROJECT. ADDITIONS, DELETIONS, AND/OR REVISIONS SHALL NOT BE MADE WITHOUT PRIOR APPROVAL BY THE ENGINEER. KEEP AND MAINTAIN IN GOOD CONDITION A COMPLETE SET OF THE CONTRACT DOCUMENTS ON THE JOB SITE AT ALL TIMES.
- 2. ALL WORK SHALL COMPLY WITH LOCAL, STATE, AND FEDERAL CODES, ORDINANCES, RULES, REGULATIONS, ORDERS, AND OTHER LEGAL REQUIREMENTS OF AUTHORITIES HAVING JURISDICTION.
- IN THE EVENT THAT THE CONTRACTOR DISCOVERS A DISCREPANCY IN THE CONTRACT DOCUMENTS OR POTENTIAL UTILITY CONFLICT, NOTIFY THE ENGINEER IMMEDIATELY FOR CLARIFICATION PRIOR TO PROCEEDING WITH THE CONSTRUCTION OF THE PORTION OF THE WORK IN QUESTION. FIELD LOCATE ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION. VERTICAL AND HORIZONTAL LOCATIONS TO BE CONFIRMED. ANY NECESSARY PIPE MODIFICATIONS SHALL BE MADE BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.
- 4. CONSTRUCTION SHALL NOT COMMENCE UNTIL ALL LOCAL NECESSARY PERMITS HAVE BEEN OBTAINED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING, OR VERIFYING, THAT ALL PERMITS AND APPROVALS ARE OBTAINED FROM THE RESPECTIVE CITY, COUNTY, AND STATE AGENCIES PRIOR TO STARTING CONSTRUCTION
- 5. ALL RIGHT-OF-WAY AND PROPERTY LINES AND EASEMENTS ARE APPARENT AND WERE DETERMINED BASED UPON AVAILABLE INFORMATION. VERIFY ALL RIGHT-OF-WAY AND PROPERTY LINES. STAKE ALL RIGHT-OF-WAY, PROPERTY, AND EASEMENT LINES THROUGHOUT THE DURATION OF CONSTRUCTION.
- PROTECT ALL EXISTING UTILITIES FROM DAMAGE, IN A MANNER APPROVED BY THE UTILITY COMPANIES AND THE ENGINEER. COORDINATE WITH UTILITY COMPANIES AS NECESSARY TO COMPLETE THE WORK. PROTECT BENCH MARKS, SURVEY CONTROL POINTS, AND EXISTING STRUCTURES FROM UNNECESSARY DAMAGE OR DISPLACEMENT.
- 7. PROVIDE ALL AUTOMOBILE AND PEDESTRIAN TRAFFIC CONTROL DEVICES REQUIRED BY FEDERAL, STATE, OR LOCAL AGENCIES. THE AMOUNT, LOCATION, AND SIZE SHALL BE AS REQUIRED IN ACCORDANCE WITH MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.
- 8. DURING CONSTRUCTION IT MAY BE NECESSARY TO TRIM OR REMOVE A TREE WITHIN THE RIGHT-OF-WAY OR AN EASEMENT. NOTIFY THE ENGINEER, OWNER, AND ANY AFFECTED PROPERTY OWNER PRIOR TO ANY REQUIRED TREE REMOVAL. TREE TRIMMING AS REQUIRED WITHIN THE RIGHT-OF-WAY OR EASEMENT SHALL BE MINIMIZED. NO ADDITIONAL COMPENSATION WILL BE PROVIDED FOR TREE REMOVAL OR TRIMMING.
- 9. ALL DISTURBED AREAS, INCLUDING, BUT NOT LIMITED TO, STREETS, DRIVES, WALKS, LAWNS, FENCES, RETAINING WALLS, ETC. SHALL BE RESTORED TO ORIGINAL OR BETTER CONDITION.
- 10. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO REMOVE ALL MUD, DIRT, GRAVEL, AND ANY OTHER MATERIALS TRACKED ONTO ANY PUBLIC OR PRIVATE STREETS, PARKING LOTS, OR WALKS. THIS MATERIAL REMOVAL OR SWEEPING OF THE STREETS SHALL BE DONE AS FREQUENTLY AS NECESSARY TO MAINTAIN AREAS REASONABLY CLEAN. AIRBORNE DUST SHALL BE KEPT TO A MINIMUM BY USING WATER OR OTHER METHODS AS NECESSARY.
- 11. PROVIDE TEMPORARY GRASS SEED WITHIN 7-DAYS OF ALL EARTH DISTURBING ACTIVITIES.
- 12. PROVIDE AND MAINTAIN ALL NECESSARY STRAW BALES, FILTER FENCE, INLET PROTECTION ETC. IN EXISTING AND PROPOSED DITCHES, CULVERTS, STORM PIPES, AND DRAINAGE STRUCTURES TO PREVENT DAMAGE. BIO-DEGRADABLE EROSION CONTROL DEVICES SHOULD BE PLACED IN ALL DISTURBED DRAINAGE DITCHES WITH DEPTHS GREATER THAN 12".
- 13. REGRADE AREAS AS NECESSARY WITHIN THE CONSTRUCTION LIMITS TO ALLOW PROPER DRAINAGE TO EXISTING STORM SEWER STRUCTURES.
- 14. MAINTAIN 10'-0" HORIZONTAL AND 1'-6" VERTICAL SEPARATION FROM STORM AND WATER MAIN, UNLESS SPECIFICALLY NOTED IN THE PLANS.
- 15. PROVIDE FILL AROUND PROPOSED AND EXISTING PIPING AT ALL OPEN-CUT UTILITY CROSSINGS TO ADEQUATELY SUPPORT AND PROTECT EACH CONDUIT.
- 16. PRESERVE EXISTING RIGHT-OF-WAY MARKERS. IF RIGHT-OF-WAY MARKERS ARE DISTURBED, RESET MARKERS AT NO ADDITIONAL COST TO THE OWNER.
- 17. CALL LOCAL UTILITY LINE INFORMATION SERVICE NOT LESS THAN THREE WORKING DAYS BEFORE PERFORMING WORK. REQUEST UNDERGROUND UTILITIES TO BE LOCATED AND MARKED WITHIN AND SURROUNDING CONSTRUCTION AREAS. IDENTIFY REQUIRED LINES, LEVELS, CONTOURS, AND DATUM
- 18. ESTABLISH TEMPORARY TRAFFIC CONTROL LAND DETOURS WHEN TRENCHING IS PERFORMED IN PUBLIC RIGHT-OF-WAY. RELOCATE CONTROLS AND REROUTE TRAFFIC AS REQUIRED DURING PROGRESS OF WORK.
- 19. DO NOT LEAVE MORE THAN 50 FEET OF TRENCH OPEN AT END OF WORKING DAY. PROTECT OPEN TRENCH TO PREVENT DANGER TO THE PUBLIC.
- 20. STOCKPILE EXCAVATED AND FILL MATERIALS ON SITE AT LOCATIONS APPROVED BY OWNER. STOCKPILE IN SUFFICIENT QUANTITIES TO MEET PROJECT SCHEDULE AND REQUIREMENTS. SEPARATE DIFFERENT AGGREGATE MATERIALS WITH DIVIDERS OR STOCKPILE QUANTITIES TO MEET PROJECT SCHEDULE AND REQUIREMENTS, SEPARATE DIFFERENT AGGREGATE MATERIALS WITH DIVIDERS OR STOCKPILE INDIVIDUALLY TO PREVENT MIXING. DIRECT SURFACE WATER AWAY FROM STOCKPILE SITE TO PREVENT EROSION OR DETERIORATION OF MATERIALS. STOCKPILE CLEANUP: REMOVE STOCKPILE, AND LEAVE AREA IN CLEAN AND NEAT CONDITION. GRADE SITE SURFACE TO PREVENT FREE STANDING SURFACE WATER.
- 21. SOIL STOCKPILE SHALL BE LOCATED WITHIN THE TEMPORARY EASEMENTS ALONG THE PROJECT.
- 22. FINAL CONTOURS: PERFORM FINISH GRADING AND BLEND INTO CONFIRMATION WITH REMAINING NATURAL GROUND SURFACES. LEAVE ALL FINISHED GRADING SURFACES SMOOTH AND FIRM TO DRAIN. FINISH GRADES TO ELEVATIONS WITHIN PLUS OR MINUS 0.10 FOOT OF EXISTING OR CONTOUR SHOWN.
- 23. ALL ELEVATIONS AT CONSTRUCTION LIMITS SHALL MATCH EXISTING GRADE. CONTRACTOR SHALL BE RESPONSIBLE FOR ENSURING THAT STACKED GRADES MATCH DESIGN ELEVATIONS AND POSITIVE DRAINAGE TO STORMWATER MANAGEMENT SYSTEM IS ACHIEVED. CONTACT ENGINEER IF DESIGN ELEVATIONS DO NOT PROVIDE POSITIVE DRAINAGE.

CIVIL/PRO	DCESS LEGEND
LINE TYPE	CIVIL TYPE
	CONTRUCTION LIMITS
XX'_SETBACK	SET BACK
	RIGHT OF WAY
SF SF	SILT FENCE
= = = = = = =	HAY BALE CHECK DAM
	EASEMENT
	PROPERTY LINE
	EXISTING INDEX CONTOURS
	EXISTING INTERMEDIATE CONTOURS
UFO UFO	UNDERGROUND FIBER OPTIC
SS	EXISTING SANITARY SEWER
ST	EXISTING STORM SEWER
W W	EXISTING WATER MAIN
OHE OHE	OVERHEAD ELECTRIC
UGE UGE	UNDERGROUND ELECTRIC
UGT UGT	UNDERGROUND TELEPHONE
GAS GAS	GAS LINE
XX	EXISTING FENCE
	TREE LINE
SS -	PROPOSED SANITARY SEWER
ST -	PROPOSED STORM SEWER
w w	PROPOSED WATER MAIN
870	PROPOSED INDEX CONTOURS
870	PROPOSED INTERMEDIATE CONTOURS
EE	ELECTRICAL CONDUIT
COM COM	COMMUNICATIONS CABLE
LINE TYPE	PROCESS TYPE
SBD SBD ————————————————————————————————	SLUDGE BLOWDOWN
RW RW	RAW WATER
FW FW	FINISHED WATER
BWS BWS	BACKWASH SUPPLY
FWW FWW	FILTERED WASTEWATER

	ABBREV	'IATIONS	
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION
AFF	ABOVE FINISHED FLOOR	FCO	FLOOR CLEANOUT
ATR	ALL THREAD ROD	GV	GATE VALVE
AS	AQUASTAT	GLV	GLOBE VALVE
AAV	AIR ADMITTANCE VALVE	HSP	HIGH SERVICE PUMP
AC	AIR COMPRESSOR	НВ	HOSE BIBB
ARV	AIR RELEASE VALVE	HWRP	HOT WATER RETURN PUMP
AP	ACCESS PANEL	MV	MANUAL AIR VENT
AD	AREA DRAIN	M	MOTOR - OPERATED VALVE
AV	ANGLE VALVE	ORD	OVERFLOW ROOF DRAIN
AV	AUTOMATIC AIR VENT	PTU	PACKAGED TREATMENT UNIT
BV	BALL VALVE	PV	PLUG VALVE
BFV	BUTTERFLY VALVE	PA	PIPE ANCHOR
BFPA	BACKFLOW PREVENTER ASSEMBLY	PG	PIPE GUIDE
BS	BASKET STRAINER	PS	PIPE SLEEVE
CTLV	CONTROL VALVE, 2-WAY	PRV	PRESSURE RELIEF VALVE
CV	CHECK VALVE	PIV	POST INDICATOR VALVE
CR	CONCENTRIC REDUCER/INCREASER	PG	PRESSURE GAUGE WITH GAUGE COOK
DU	DIELECTRIC UNION	PS	PRESSURE SWITCH
DBL	DOUBLE	ROW	RIGHT OF WAY
ECO	EXTERIOR CLEANOUT (TO GRADE)	RD	ROOF DRAIN
EL	EXPANSION LOOP (SIZE AS NOTED)	SV	SOLENOID VALVE
EC	ECCENTRIC REDUCER/INCREASER	TPV	TEMPERATURE- PRESSURE RELIEF VALVE
EJ	EXPANSION JOINT	T	THERMOMETER (SPECIFY TYPE)
FFE	FINISHED FLOOR ELEVATION	U	UNION
F	FLANGE	WCO	WALL CLEANOUT
FS	FLOW SWITCH	WHA	WATER HAMMER ARRESTOR
FM	FLOW METER	WS	WYE STRANNER
FC	FLEXIBLE CONNECTOR	WH	WALL HYDRANT
FD	FLOOR DRAIN	YB	YARD BOX



### HEATLAND WASTEWATER SYSTEI IMPROVEMENTS SION I - WASTEWATER TREATME ANT AND REGIONAL LIFT STATIO

Revision Date

Project #: 21-400-194-1

Designed By: WMW

Date:01/04/2023

Drawn By: RLH


Checked By: ALC



Claron Clar

**GENERAL NOTES** 

G002





WHEATLAND WASTEWATER SYSTEM
IMPROVEMENTS

CONSTRUCTION

-T STATION 1 47597


Revision Date

Project #: 21-400-194-1

Designed By: LD

Drawn By: AB, WD


Checked By: VW





FIRE AND LIFE SAFETY PLAN

G10




INTENTIONAL INNOVATION

Project #: 21-400-194-1


Revision

Drawn By: KLB

Date: 1/6/2023



**EXISTING SITE LAYOUT** 




INTENTIONAL INNOVATION

Revision

Designed By: MTR

Drawn By: KLB Checked By: ALC

Date: 1/6/2023




**PROPOSED SITE LAYOUT** 


### LIFT STATION NOTES

- 1. RAIL SYSTEM SHALL ENABLE THE EASY REMOVAL OF THE PUMPS WITHOUT THE NEED FOR A PERSON TO ENTER THE WET WELL. THE GUIDE RAIL SHALL BE SUPPORTED AT THE BOTTOM BY THE DISCHARGE ELBOW, ALIGNED PERFECTLY PLUMB AND SECURELY AFFIXED TO ACCESS FRAME. ONE INTERMEDIATE GUIDE RAIL SUPPORT IS REQUIRED FOR EACH 6' OF GUIDE RAIL LENGTH.
- 2. CHECK VALVE SHALL BE BRONZE SEATED, SHALL BE PROVIDED WITH BOLTED COVERS FOR EASY ACCESS TO THE DISCS, AND SHALL BE OUTSIDE ADJUSTABLE WEIGHT AND LEVER AS APPROVED BY OWNER. PLUG VALVE SHALL BE AN ECCENTRIC BUNA N RUBBER FACED PLUG WITH HAND LEVER OPERATION IN-LINE AND GEAR OPERATION ON BY-PASS, AND SHALL BE AS APPROVED BY OWNER.
- PROVIDE SUFFICIENT FLOAT CHAIN, FLOAT MOUNTING CABLE, AND PUMP POWER & SENSOR CABLE TO ENABLE NON-SPLICED FIELD ADJUSTMENT. LIFT CHAIN SHALL HAVE A MINIMUM WORK LOAD LIMIT OF 1100 POUNDS. FLOAT MOUNTING CABLE SHALL BE HELP IN PLACE BY WEIGHT. FLOATS SHALL BE FASTENED TO CABLE WITH STAINLESS STEEL CLAMPS AT EACH FLOAT LOCATION.
- 4. PIPING IN AND WITHIN 2 FEET OF WET WELL AND VALVE VAULT SHALL BE CLASS 51 FLANGED DUCTILE IRON PIPE. PIPING, VALVES AND FITTINGS IN WET WELL AND VALVE PIT SHALL BE FACTORY PRIMED TNEMEC SERIES 140-POTA-POX PLUS TO A DRY FILM THICKNESS OF 6.0 TO 8.0 MILS AND SHALL BE FIELD PAINTED WITH TNEMEC SERIES 69-HI-BUILD EPOXOLINE II TO A DRY FILM THICKNESS OF 2.0 TO 3.0 MILS. PROVIDE FINISH COLOR AS SELECTED BY OWNER.
- 5. LIFT STATION AND VALVE PIT MANHOLES SHALL BE PRE-CAST CONCRETE IN ACCORDANCE WITH ASTM C-478, WITH RUBBER GASKETS EQUAL TO ASTM C-443 WITH ½" HAMILTON KENT-SEAL EXTRUDABLE PREFORMED GASKET MATERIAL OR OWNER APPROVED EQUAL. DAMP PROOF ALL EXTERIOR VERTICAL, SURFACES WHICH ARE BACKFILLED AGAINST WITH BITUMINOUS COATING, HYDROCIDE 700 MASTIC.
- 6. CONSULT WITH OWNER FOR CAM LOCK COUPLING MODEL NUMBER.
- 7. ALUMINUM HATCHES SHALL BE BILCO OR OWNER APPROVED EQUAL. LEAF SHALL BE ½" ALUMINUM DIAMOND PLATE. CHANNEL FRAME SHALL BE ½" EXTRUDED ALUMINUM WITH A MILL FINISH AND BITUMINOUS COATING ON EXTERIOR SURFACES. HATCH SHALL BE PROVIDED WITH 316 STAINLESS STEEL HARDWARE THROUGHOUT, COMPRESSION SPRING OPERATORS, AUTOMATIC HOLD-OPEN ARM WITH RELEASE HANDLE, RECESSED LOCK HASP WITH FLUSH COVER, SLAM LOCK WITH REMOVABLE HANDLE, FALL PROTECTION GRATING AND 1-1/2" DRAIN COUPLING.
- 8. SEWER CONNECTION TO WET WELL SHALL BE KOR-N-SEAL, A-LOK, DURA-SEAL, OR OWNER APPROVED EQUAL. FOR INVERTS GREATER THAN 30' BELOW GRADE, CONNECTION WILL BE LINK-SEAL OR APPROVED EQUAL.
- 9. FORCE MAIN PENETRATIONS OF WET WELL AND VALVE PIT SHALL BE WATERTIGHT THROUGH THE USE OF PORTLAND CEMENT GROUT.


LIFT STATION SCHEDULE					
PHASE	FULL BUILDOUT				
GRADE/TOP OF CASTING ELEV.	479.65				
BASE ELEV.	448.27				
DEPTH	30.91				
INTERNAL DIAMETER	6.0				
HI ALARM LEVEL 2	452.77				
HI ALARM LEVEL 1	452.27				
LAG PUMP ON	451.77				
LEAD PUMP ON	451.27				
PUMP OFF	449.27				
FORCE MAIN I.E. DISCHARGE	494.75				
GRAVITY SEWER LOWEST I.E.	453.27				





<u>SECTION A-A</u> (TYP. FOR ALL CONCRETE SLABS)



STEPS, 12" MAXIMUM SPACING









### WHEATLAND WASTEWATER SYSTENIMHEATLAND WASTEWATER TREATME

TION

# Revision Date

Project #: 21-400-194-1

Designed By: WMW

Drawn By: RLH


Date:01/04/2023

Checked By: ALC



- Clared Com

LIFT STATION
SECTION AND DETAIL





### WHEATLAND WASTEWATER SYSTEN IMPROVEMENTS DIVISION I - WASTEWATER TREATME PI ANT AND REGIONAL LET STATIONAL LET ST

Revision Date

Project #: 21-400-194-1

Designed By: WMW

Drawn By: RLH
Checked By: ALC


Date:01/04/2023



Claron Crow

SLUDGE DRYING BED PLAN AND SECTIONS - ALT. 3

C302






### WHEATL

<i>‡</i>	Revision	Date


Project #: 21-400-194-1

Drawn By: KLB

Checked By: ALC Date: 1/6/2023



**ALIGNMENT LAYOUT** 





## WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS IVISION I - WASTEWATER TREATMEN

# Revision Date

Project #: 21-400-194-1

Designed By: MTR

Drawn By: KLB
Checked By: ALC


Date: 1/6/2023




Claron Crow




PROFILE LAYOUT





LINE TABLE							
NO.	LENGTH	DIRECTION	START POINT	END POINT			
L1	92.99	N15° 03' 11.27"E	1243740.558, 2891012.092	1243830.359, 2891036.243			
L2	46.84	N13° 51' 54.38"E	1243903.936, 2891117.232	1243949.415, 2891128.458			
L3	73.44	N76° 08' 13.10"W	1243967.572, 2891117.489	1243985.168, 2891046.189			
L4	194.12	S76° 08' 13.10"E	1244000.584, 2891050.501	1243954.073, 2891238.967			
L5	85.56	S31° 08' 13.10"E	1243954.073, 2891238.967	1243880.842, 2891283.208			
L6	74.78	S13° 12' 18.74"W	1243880.842, 2891283.208	1243808.040, 2891266.125			
L7	127.00	N76° 46′ 12.12″W	1243808.040, 2891266.125	1243837.105, 2891142.493			
L8	92.41	S15° 03' 11.27"W	1243826.204, 2891051.694	1243736.965, 2891027.694			
L9	94.69	N15° 02' 33.91"E	1243727.766, 2891060.767	1243819.213, 2891085.343			
L10	216.06	S76° 46' 12.12"E	1243826.272, 2891097.598	1243776.824, 2891307.924			
L11	94.69	S15° 02' 33.91"W	1243820.511, 2891080.515	1243729.064, 2891055.938			
L12	215.99	N76° 46′ 12.12″W	1243781.692, 2891309.069	1243831.123, 2891098.812			
L13	94.69	S15° 02' 33.91"W	1243821.810, 2891075.686	1243730.362, 2891051.110			
L14	215.93	N76° 46′ 12.12"W	1243786.559, 2891310.213	1243835.976, 2891100.015			

				CURVE TABLE	
NO.	LENGTH	RADIUS	CHORD DIRECTION	START POINT	END POINT
C1	23.38	15.0	N60° 05' 43.66"E	1243730.043, 2890993.809	1243740.558, 2891012.092
C2	68.97	60.0	N47° 59' 09.44"E	1243830.359, 2891036.243	1243874.022, 2891084.712
С3	46.81	40.0	N47° 23' 27.16"E	1243874.022, 2891084.712	1243903.936, 2891117.232
C4	23.56	15.0	N31° 08' 09.36"W	1243949.415, 2891128.458	1243967.572, 2891117.489
C5	23.40	15.0	S59° 10′ 11.51"W	1243985.168, 2891046.189	1243974.355, 2891028.071
C6	23.72	15.0	S30° 49′ 48.49″E	1244018.897, 2891039.571	1244000.584, 2891050.501
C7	20.90	40.0	N61° 48′ 09.69″W	1243837.105, 2891142.493	1243846.868, 2891124.284
C8	90.70	44.0	S74° 06' 35.64"W	1243846.868, 2891124.284	1243826.204, 2891051.694
С9	23.78	15.0	S30° 21′ 46.96″E	1243736.965, 2891027.694	1243718.529, 2891038.495
C10	15.71	10.0	N60° 03' 21.55"E	1243819.213, 2891085.343	1243826.272, 2891097.598
C11	23.47	15.0	S59° 53′ 17.99"W	1243831.123, 2891098.812	1243820.511, 2891080.515
C12	31.23	20.0	S59° 47′ 18.20″W	1243835.976, 2891100.015	1243821.810, 2891075.686





# WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS DIVISION I - WASTEWATER TREATMER PLANT AND REGIONAL LIFT STATION

SET

CONSTRUCTION

# Revision Date


Project #: 21-400-194-1

Designed By: MTR

Drawn By: KLB


Checked By: ALC

Date: 1/6/2023



0 20'

**GRADING PLAN** 





### WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS

CONSTRUCTION


# Revision Date

Project #: 21-400-194-1

Designed By: **LC**Drawn By: **JM** 

Checked By: **LC** 

Date: **1/5/2023** 



SCALE:NTS

PROCESS FLOW DIAGRAM

PHASE	1	II
AVERAGE DAILY FLOW (GPD)	58,900	
PEAK FLOW (GPD)	235,600	


4"ø FM

BOT= 448.04'

( 0 ,—

ONSITE LIFT STATION

-30





# WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS DIVISION I - WASTEWATER TREATMENT PLANT AND REGIONAL LIFT STATION

CONSTRUCTION SET

# Revision Date


Project #: 21-400-194-1

Designed By: LC

Drawn By: JM

Checked By: LC


Date: **1/5/2023** 




SCALE:NTS

**HYDRAULIC PROFILE** 


### CHAIN LINK FENCE DETAIL (BID ALTERNATIVE) NOT TO SCALE



### CANTILEVER SLIDE GATE DETAIL (BID ALTERNATIVE) NOT TO SCALE




### CROSS SECTION OF STONE PARKING AREA



### STANDARD CLEANOUT DETAIL

N.T.S



### RESTRAINED JOINTS ON SLIP JOINT PIPE (USING GRIPPING TYPE RETAINERS)

		F	RESTRAIN	NED LEN	IGTHS F	OR 4" D	IA. PIPE	-				
DEPTH OF PIPE	4'	4'	4'	4'	5'	5'	5'	5'	10'	10'	10'	10'
BEND ANGLE	11.25°	22.5°	45°	90°	11.25°	22.5°	45°	90°	11.25°	22.5°	45°	90°
RESTRAINED LENGTH	1'	1'	2'	5'	1'	1'	2'	4'	1'	1'	1'	3'

FORCE MAIN PIPE JOINT RESTRAINT DETAIL
NOT TO SCALE



### WHEATLAND WASTEWATER SYSTEN IMPROVEMENTS WISION I - WASTEWATER TREATME

CONSTRUCTION

# Revision Date


Project #: 21-400-194-1

Designed By: MTR

Drawn By: KLB

Checked By: ALC


Date: 1/6/2023



Claron Cl

NTS

**CIVIL DETAILS** 



INTENTIONAL INNOVATION

WHEAT

Date

Designed By: WMW

Checked By: ALC



**EROSION CONTROL PLAN** 

### CONCRETE WASHOUT (ABOVE GRADE)

### **INSTALLATION:**

PREFABRICATED WASHOUT SYSTEMS/CONTAINERS: 1. INSTALL AND LOCATE ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS.

### DESIGNED AND INSTALLED SYSTEMS:

- 2. UTILIZE AND FOLLOW THE DESIGN IN THE STORM WATER POLLUTION PREVENTION PLAN TO INSTALL THE SYSTEM.
- 3. DEPENDENT UPON THE TYPE OF SYSTEM, EITHER EXCAVATE THE PIT OR INSTALL THE CONTAINMENT SYSTEM. 4. A BASE SHALL BE CONSTRUCTED AND PREPARED THAT IS FREE OF ROCKS AND OTHER DEBRIS THAT MAY CAUSE TEARS OR PUNCTURES IN THE
- 5. INSTALL THE POLYETHYLENE LINING. FOR EXCAVATED SYSTEMS, THE LINING SHOULD EXTEND OVER THE ENTIRE EXCAVATION. THE LINING FOR BERMED SYSTEMS SHOULD BE INSTALLED OVER THE POOLING AREA WITH ENOUGH MATERIAL TO EXTEND THE LINING OVER THE BERM OR CONTAINMENT SYSTEM. THE LINING SHOULD BE SECURED WITH PINS, STAPLES, OR OTHER FASTENERS.
- 6. PLACE FLAGS, SAFETY FENCING, OR EQUIVALENT TO PROVIDE A BARRIER TO CONSTRUCTION EQUIPMENT AND OTHER TRAFFIC.
- 7. PLACE A NON-COLLAPSING, NON-WATER HOLDING COVER OVER THE WASHOUT FACILITY PRIOR TO A PREDICTED RAINFALL EVENT TO PREVENT
- ACCUMULATION OF WATER AND POSSIBLE OVERFLOW OF THE SYSTEM (OPTIONAL). 8. INSTALL SIGNAGE THAT IDENTIFIES CONCRETE WASHOUT AREAS.
- 9. POST SIGNS DIRECTING CONTRACTORS AND SUPPLIERS TO DESIGNATED LOCATIONS.
- 10. WHERE NECESSARY, PROVIDE STABLE INGRESS AND EGRESS OR ALTERNATIVE APPROACH PAD FOR CONCRETE WASHOUT SYSTEMS.

### MAINTENANCE:

- 11. INSPECT DAILY AND AFTER EACH STORM EVENT.
- 12. INSPECT THE INTEGRITY OF THE OVERALL STRUCTURE INCLUDING, WHERE APPLICABLE, THE CONTAINMENT SYSTEM.
- 13. INSPECT THE SYSTEM FOR LEAKS, SPILLS, AND TRACKING OF SOIL BY EQUIPMENT. 14. INSPECT THE POLYETHYLENE LINING FOR FAILURE, INCLUDING TEARS AND PUNCTURES.
- 15. ONCE CONCRETE WASTES HARDEN, REMOVE AND DISPOSE OF THE MATERIAL.
- 16. EXCESS CONCRETE SHOULD BE REMOVED WHEN THE WASHOUT SYSTEM REACHES 50 PERCENT OF THE DESIGN CAPACITY. USE OF THE SYSTEM SHOULD BE DISCONTINUED UNTIL APPROPRIATE MEASURES CAN BE INITIATED TO CLEAN THE STRUCTURE. PREFABRICATED SYSTEMS SHOULD ALSO UTILIZE THIS CRITERION, UNLESS THE MANUFACTURER HAS ALTERNATE SPECIFICATIONS.
- 17. UPON REMOVAL OF THE SOLIDS, INSPECT THE STRUCTURE. REPAIR THE STRUCTURE AS NEEDED OR CONSTRUCT A NEW SYSTEM. 18. DISPOSE OF ALL CONCRETE IN A LEGAL MANNER. REUSE THE MATERIAL ON SITE, RECYCLE, OR HAUL THE MATERIAL TO AN APPROVED
- CONSTRUCTION/DEMOLITION LANDFILL SITE. RECYCLING OF MATERIAL IS ENCOURAGED. THE WASTE MATERIAL CAN BE USED FOR MULTIPLE APPLICATIONS INCLUDING BUT NOT LIMITED TO ROADBEDS AND BUILDING. THE AVAILABILITY FOR RECYCLING SHOULD BE CHECKED LOCALLY.
- 19. THE PLASTIC LINER SHOULD BE REPLACED AFTER EVERY CLEANING; THE REMOVAL OF MATERIAL WILL USUALLY DAMAGE THE LINING. 20. THE CONCRETE WASHOUT SYSTEM SHOULD BE REPAIRED OR ENLARGED AS NECESSARY TO MAINTAIN CAPACITY FOR CONCRETE WASTE. 21.CONCRETE WASHOUT SYSTEMS ARE DESIGNED TO PROMOTE EVAPORATION. HOWEVER, IF THE LIQUIDS DO NOT EVAPORATE AND THE SYSTEM IS NEAR CAPACITY IT MAY BE NECESSARY TO VACUUM OR REMOVE THE LIQUIDS AND DISPOSE OF THEM IN AN ACCEPTABLE METHOD. DISPOSAL MAY BE ALLOWED AT THE LOCAL SANITARY SEWER AUTHORITY PROVIDED THEIR NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM PERMITS
- ALLOW FOR ACCEPTANCE OF THIS MATERIAL. ANOTHER OPTION WOULD BE TO UTILIZE A SECONDARY CONTAINMENT SYSTEM OR BASIN FOR FURTHER DEWATERING 22. PREFABRICATED UNITS ARE OFTEN PUMPED AND THE COMPANY SUPPLYING THE UNIT PROVIDES THIS SERVICE. 23.INSPECT CONSTRUCTION ACTIVITIES ON A REGULAR BASIS TO ENSURE SUPPLIERS, CONTRACTORS, AND OTHERS ARE UTILIZING DESIGNATED
- WASHOUT AREAS. IF CONCRETE WASTE IS BEING DISPOSED OF IMPROPERLY, IDENTIFY THE VIOLATORS AND TAKE APPROPRIATE ACTION. 24. WHEN CONCRETE WASHOUT SYSTEMS ARE NO LONGER REQUIRED, THE CONCRETE WASHOUT SYSTEMS SHALL BE CLOSED. DISPOSE OF ALL HARDENED CONCRETE AND OTHER MATERIALS USED TO CONSTRUCT THE SYSTEM.
- 25. HOLES, DEPRESSIONS AND OTHER LAND DISTURBANCES ASSOCIATED WITH THE SYSTEM SHOULD BE BACKFILLED, GRADED, AND STABILIZED.

CONCRETE WASHOUT DETAIL
NOT TO SCALE

### SILT FENCE

### LOCATION

- INSTALLED PARALLEL TO THE SLOPE CONTOUR
- MINIMUM 10 FEET BEYOND THE TOE OF SLOPE TO PROVIDE A BROAD, SHALLOW
- ACCESSIBLE FOR MAINTENANCE (REMOVAL OF SEDIMENT AND SILT FENCE REPAIR)


### **INSTALLATION**


- L. LAYOUT THE LOCATION OF THE FENCE SO THAT IT IS PARALLEL TO THE CONTOUR OF THE SLOPE AND AT LEAST 10 FEET BEYOND THE TOE OF THE SLOPE TO PROVIDE A SEDIMENT STORAGE AREA. TURN THE ENDS OF THE FENCE UP SLOPE SUCH THAT THE POINT OF CONTACT BETWEEN THE GROUND AND THE BOTTOM OF THE FENCE END TERMINATES AT A HIGHER ELEVATION THAN THE TOP OF THE FENCE AT ITS LOWEST POINT.
- 2. EXCAVATE AN EIGHT-INCH DEEP BY FOUR-INCH WIDE TRENCH ALONG THE ENTIRE LENGTH OF THE FENCE LINE. INSTALLATION BY PLOWING IS ALSO ACCEPTABLE. . INSTALL THE SILT FENCE WITH THE FILTER FABRIC LOCATED ON THE UP-SLOPE SIDE OF THE EXCAVATED TRENCH AND THE SUPPORT POSTS ON THE DOWN-SLOPE SIDE
- OF THE TRENCH. 4. DRIVE THE SUPPORT POSTS AT LEAST 18 INCHES INTO THE GROUND, TIGHTLY STRETCHING THE FABRIC BETWEEN THE POSTS AS EACH IS DRIVEN INTO THE SOIL. A MINIMUM OF 12 INCHES OF THE FILTER FABRIC SHOULD EXTEND INTO THE TRENCH. (IF IT IS NECESSARY TO JOIN THE ENDS OF THE TWO FENCE, USE THE
- 5. LAY THE LOWER FOUR INCHES OF FILTER FABRIC ON THE BOTTOM OF THE TRENCH AND EXTEND IT TOWARD THE UP-SLOPE SIDE OF THE TRENCH.
- 6. BACKFILL THE TRENCH WITH SOIL MATERIAL AND COMPACT IT IN PLACE.

### MAINTENANCE

WRAP JOINT METHOD SHOWN.)

- INSPECT WITHIN 24 HOURS OF A RAIN EVENT AND AT LEAST ONCE EVERY SEVEN CALENDAR DAYS.
- IF FABRIC TEARS, STARTS TO DECOMPOSE, OR IN ANY WAY BECOMES INEFFECTIVE, REPLACE THE AFFECTED PORTION IMMEDIATELY. NOTE: ALL REPAIRS SHOULD MEET SPECIFICATIONS AS OUTLINED WITHIN THIS MEASURE.
- REMOVE DEPOSITED SEDIMENT WHEN IT IS CAUSING THE FILTER FABRIC TO BULGE OR WHEN IT REACHES ONE-HALF THE HEIGHT OF THE FENCE AT ITS LOWEST POINT. WHEN CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED, REMOVE THE FENCE AND SEDIMENT DEPOSITS, GRADE THE SITE TO BLEND WITH THE SURROUNDING AREA, AND STABILIZE.






NOTE: CONTRACTOR TO USE FLEXSTORM CATCH-IT INLET PROTECTOR, DANDY BAG OR APPROVED ALTERNATE.

• REMOVE ALL ACCUMULATED SEDIMENT AFTER EACH STORM EVENT. DISPOSE OF SEDIMENT IN AN AREA WHERE IT WILL NOT REENTER THE PAVED AREA OR STORM DRAINS. TO EMPTY UNIT, LIFT THE UNIT OUT OF THE INLET BY USING THE LIFTING STRAPS AND REMOVE THE GRATE. • WHEN CONTRIBUTING DRAINAGE AREA HAD BEEN STABILIZED, REMOVE INLET PROTECTION.

• INSPECT DAILY.


DROP BAG INLET PROTECTION NOT TO SCALE



	TEMPORARY SEI	EDING SPECIFICATIONS			
SEED SPECIES	RATE PER ACRE	PLANTING DEPTH OPTIMUM DATE			
WHEAT OR RYE	150 LBS	1 TO 1-1/2 INCHES	SEPT. 15 - OCT. 30		
SPRING OATS	100 LBS	1 INCH	MAR. 1 - APR. 15		
ANNUAL RYEGRASS	40 LBS	1/4 INCH	MAR. 1 - MAY 1 AUG. 1 - SEPT. 1		
GERMAN MILLET	40 LBS	1 TO 2 INCHES	MAY 1 - JUNE 1		
SUDANGRASS	35 LBS	1 TO 2 INCHES	MAY 1 - JULY 30		
BUCKWHEAT	60 LBS	1 TO 2 INCHES	APR. 15 - JUNE 1		
CORN (BROADCAST)	300 LBS	1 TO 2 INCHES	MAY 11 - AUG. 10		
SORGHUM	35 LBS	1 TO 2 INCHES	MAY 1 - JULY 15		

NOT TO SCALE

- CHANNEL LINING UTILIZE STAPLE PATTERN "C" WITH ADDITIONAL STAPLES ON SIDE SLOPES AT PROJECTED WATER LINE. 2. STAPLE PATTERNS APPLY TO ALL NORTH AMERICAN GREEN
- EROSION CONTROL BLANKETS STAPLE PATTERNS MAY VERY DEPENDING UPON SOIL TYPE AND AVERAGE RAINFALL. 3. AT SLOPE LENGTHS GREATER THAN 300 FEET OR WHERE DRAINAGE OVER LARGE AREAS IS DIRECTED ONTO THE BLANKETS, STAPLE
- PATTERN "C" SHOULD BE UTILIZED. **OS EROSION CONTROL MAT INSTALLATION AND DETAIL**



INTENTIONAL INNOVATION

Revision

Project #: 21-400-194-1

Drawn By: RLH

Designed By: WMW

Date:01/04/2023

Checked By: ALC



**EROSION CONTROL DETAILS** 

The project is located in the Town of Wheatland, IN and includes properties outside of the town's property line

OWNER'S INFORMATION

Town of Wheatland, Indiana Address: 121 IN-550, Wheatland, IN 47597 Contact: Brett Dawson President of Town Council Telephone: bdawson@townofwheatland.in

OPERATOR'S INFORMATION

Wheatland Water Department Address: 121 IN-550 Wheatland, IN 47597 Contact: Erika Goble

Town of Wheatland Deputy Clerk and Water Operator Apprentice Telephone: (812) 291-0713

Note: Wastewater Operator will be secured at a later date.

NOTICE OF INTENT

All parties defined as owners must submit a Notice of Intent (NOI) at least 48 hours prior to commencement of on-site construction activities. Submittal of late NOI's is not prohibited; however, authorization under the construction general permit is only for discharges that occur after permit coverage is granted. Unpermitted discharges may be subject to enforcement actions by the EPA. For the purposes of this permit, an owner is defined as any party meeting either of the following requirements:

1) The party has operational control over the construction plans and specifications, including the ability to make modifications to those plans and specifications.

2) The party has day-to-day operational control of those activities at a project that are necessary to ensure compliance with a stormwater pollution prevention plan for the site or other permit conditions.

A2 11" x 17" PLAT

Refer to the Site Layout Plan.

A3 PROJECT NARRATIVE

The Town of Wheatland Wastewater Improvements Division I project involves installation of a new packaged WWTP that includes an aeration treatment facility with a manual influent bar screen, activated sludge aeration tanks, secondary clarifiers, ultraviolet disinfection, and post aeration. Solids management includes aerobic digestion and a sludge holding tank, along with a covered drying bed. A regional lift station will also be included to pump collections and decant.

A4 VICINITY MAP

Refer to the Cover Sheet

A5 LEGAL DESCRIPTION OF THE PROJECT SITE

Township: Steen

A6 LOCATION OF ALL LOTS AND PROPOSED SITE IMPROVEMENTS

The site is not subdivided into lots; therefore, all proposed site improvements are shown on the included plans.

A7 HYDROLOGIC UNIT CODE (HUC)

05120202090

A8 STATE AND FEDERAL WATER QUALITY PERMITS

Indiana Department of Environmental Management (IDEM) Rule 5

A9 SPECIFIC POINTS WHERE STORMWATER DISCHARGE WILL LEAVE THE SITE

Stormwater drainage from the Town of Wheatland drains via roadside stormpipes and vegetated drainage ditches to Steen Ditch for the south side of the town and the Opossum branch on the north side of the town. Both the Opossum Branch and Steen Ditch outlet into

A10 LOCATION AND NAME OF ALL WETLANDS, LAKES, AND WATERCOURSES ON AND ADJACENT TO THE SITE

Steen Ditch runs through the south side of town. There are no ponds or stormwater detention reservoirs within the limits of the town of Wheatland except for the red pond for the town's water treatment plant. This pond is meant for red water detention from the WTP and only collects sheet flow directly around the outside edge of the pond.

A 11 IDENTIFICATION OF ALL RECEIVING WATERS

White River is the ultimate receiving water for this project. Temporary stormwater storage is done in Pond Creek and in Kessinger Ditch, which are upstream of White River and Steen Ditch flows into Pond Creek.

A12 IDENTIFICATION OF ALL POTENTIAL DISCHARGES TO GROUNDWATER

There are no locations on site where surface water may be discharged into groundwater.

A13 100 YEAR FLOODPLAINS, FLOODWAYS, AND FLOODWAY FRINGES

The project site is located in an unshaded Zone X as indicated on the Hancock County, IN Flood Insurance Rate Map 1804220175C dated

A14 PRE-CONSTRUCTION AND POST CONSTRUCTION ESTIMATE OF PEAK DISCHARGE

PRE-DEVELOPMENT POST-DEVELOPMENT Q2 = 0.342 CFS Q2 = 0.342 CFS Q10 = 0.488 CFQ10 = 0.488 CFSQ25 = 0.578 CFSQ25 = 0.578 CFSQ100 = 0.733 CFSQ100 = 0.733 CFS

A15 ADJACENT LAND USE

North: Agricultural Agricultural East: Agricultural Agricultural

A16 LOCATIONS AND APPROXIMATE BOUNDARIES OF ALL DISTURBED AREAS

Approximate boundaries of disturbed areas are as identified on the Erosion Control Plan.

A17 IDENTIFICATION OF EXISTING VEGETATIVE COVER

Locations of stormwater systems:

Approximate areas of existing vegetative cover are as shown on the Existing Conditions Plan or Topographic Survey.

Refer to the Site Utility Plan

A18 SOILS MAP INCLUDING SOIL DESCRIPTION AND LIMITATIONS

The Natural Resources Conservation Service (NRCS) Web Soil Survey of Knox County, Indiana indicates Ragsdale silt loam (Ra), and Reesville silt loam (ReA), are located within the project site.

The on-site soil will be treated as recommended by the geotechnical engineer if the conditions are unsuitable for the proposed

A19 LOCATIONS, SIZE, AND DIMENSIONS FOR THE PROPOSED STORMWATER SYSTEMS

Refer to the Site Utility Plan or Storm Sewer Profiles Size of storm sewers:

Details of storm inlets and manholes: Refer to the Construction Details A20 PLANS FOR ANY OFF-SITE CONSTRUCTION ACTIVITIES ASSOCIATED WITH THIS PROJECT

No projects directly adjacent to the town limits of the Town of Wheatland, IN are to occur during the construction of the new packaged WWTP and regional Lift Station A21 LOCATIONS OF PROPOSED SOIL STOCKPILES AND/OR BORROW/DISPOSAL

Excess soil shall be immediately stockpiled, surrounded with silt fence, and seeded and/or removed from the project site in accordance with all applicable laws. If topsoil stockpiles are anticipated for this project, they are shown on the Erosion Control Plan.

A22 EXISTING SITE TOPOGRAPHY

Refer to the Existing Conditions Plan or Topographic Survey

A23 PROPOSED FINAL SITE TOPOGRAPHY

Refer to the Site Grading Plan

B1 DESCRIPTION OF POTENTIAL POLLUTANT SOURCES ASSOCIATED WITH CONSTRUCTION ACTIVITIES

The following potential pollutant sources may be associated with construction activities on site: Material storage areas

Construction waste material Fuel storage areas and fueling stations Exposed soils Leaking vehicles and equipment

Sanitary waste from temporary toilet facilities

Windblown dust Soil tracking off site from construction equipment

The following materials may be staged or stored on site at various points during construction: Structural fill

HDPE, PVC, RCP, or Ductile Iron Pipe Precast concrete, HDPE, or PVC drainage and sanitary structures

B2 SEQUENCE DESCRIBING STORMWATER QUALITY MEASURE IMPLEMENTATION RELATIVE TO LAND-DISTURBING ACTIVITIES

1. The exact locations of all existing utilities within the project limits are to verified prior to construction. 2. Schedule pre-construction meeting with local stormwater authority 48 hours prior to start of construction.

3. Install protection fencing for existing trees to remain in place within the project limits

Construction Site Access Install gravel construction entrance

2. Post the NOI and contact information at the construction entrance. NOI to remain posted for duration of the project. 3. Install construction staging pads, fueling station, material storage areas, concrete washout, construction parking areas, and stabilize construction routes

Pavement base stone

1. Utilize the gravel construction entrance for installation of the perimeter silt fence. Add stone if needed.

Initial Land Clearing and Grading Activities 1. Add protection measures to existing inlets. 2. Strip the topsoil and stabilize the topsoil stockpile

Secondary Land Grading Activities 1. Begin site grading/construction of detention basins (if applicable) and stabilize any soil stockpiles that will be left dormant

for more than 10 days 2. Complete the cut and fills on the site. Final grade and seed the pond slopes (if applicable). Stabilize slopes with erosion control blanket.

3. Install storm sewer system and install inlet protection immediately upon complete of the inlet and install rip-rap outlet protection prior to installing outlets.

Surface Stabilization

1. Apply temporary seeding and stabilize slopes in areas where rough grading has been completed. 2. Apply permanent seeding and stabilize slopes in areas where final grading has been completed.

1. Prior to building construction install stone surface for paved areas. 2. Building pads left dormant for more than 10 days, must be temporarily seeded. 3. Start building construction. Install staging area for building materials and stabilize.

5. Remove all erosion and sediment control practices when areas have a uniform grass cover.

Final Shaping/Landscaping 1. Utilize topsoil salvage in applicable areas and apply permanent seeding. 2. Apply permanent seeding around the perimeter of the site. 3. Complete utility installation, curbs, paving, and building construction.

4. Install landscaping plant material and stabilize all disturbed areas.

B3 STABLE CONSTRUCTION ENTRANCE LOCATIONS AND SPECIFICATIONS

Construction entrances will be in place prior to any site construction or demolition. Entrances are shown on the Erosion Control Plan. Refer to the Erosion Control Details for details.

B4 SEDIMENT CONTROL MEASURES FOR SHEET FLOW AREAS

B5 SEDIMENT CONTROL MEASURES FOR CONCENTRATED FLOW AREAS

Sheet flow areas will be protected by seed and mulch or hydroseeding. Erosion control blankets will be installed on sloped areas where the slope exceeds 4:1 (horizontal to vertical). Silt fencing will be utilized to prevent sedimentation from leaving the site. Refer to the Erosion Control Plan for locations and the Erosion Control Details for details.

Proposed swales will be stabilized with erosion control blankets. Straw bales and silt fences will not be allowed as concentrated

flow protection measures. Refer to the Erosion Control Plan for locations and the Erosion Control Details for details.

B6 STORM SEWER INLET PROTECTION MEASURE LOCATIONS AND SPECIFICATIONS

B11 TEMPORARY SURFACE STABILIZATION METHODS APPROPRIATE FOR EACH SEASON

The contractor shall install appropriate inlet protection measures at each inlet. Refer to the Erosion Control Plan for locations and the Erosion Control Details for details. Straw bales will not be allowed as inlet protection measures. These inlet protection measures should be installed as soon as the inlets are installed or shortly thereafter

**B7 RUNOFF CONTROL MEASURES** 

**B8 STORMWATER OUTLET PROTECTION MEASURES** 

B9 GRADE STABILIZATION STRUCTURE LOCATIONS

B10 LOCATION, DIMENSIONS, SPECIFICATIONS, AND CONSTRUCTION DETAILS OF EACH STORMWATER QUALITY MEASURE

Refer to the Erosion Control Plan for locations of each stormwater quality measure and the Erosion Control Details and Site Construction Details.

Surface stabilization is required on any bare or thinly vegetated areas that is scheduled or likely to remain inactive for a period of 10 days or more. Refer to the Temporary Seeding Detail within the Erosion Control Details for specifics on soil amendments, seed mixtures, and mulching. The surface stabilization for the lots needs to be established as soon as possible to prevent dirt wash-out into the streets. If this is not possible, then silt fencing will need to be installed along the back of curbs.

B12 PERMANENT SURFACE STABILIZATION SPECIFICATIONS

1.) Loosen lawn area to a minimum depth of 6 inches. Mix soil amendments and fertilizers with topsoil at rates specified. Organic soil amendments such as peat, compost, or manure shall be applied at 2" depth evenly over soil and incorporated into the top 6" of topsoil. Provide fertilizer with percentage of nitrogen required to provide not less than 1 pound of actual nitrogen per 1,000 square feet of lawn area and not less than 4 percent phosphoric acid and 2 percent potassium. At least 50 percent of nitrogen to be organic form. Delay mixing of fertilizer if planting will not follow placing of planting soil within a few days.

2.) Fertilizer for lawns: provide a fast release fertilizer with a composition of 1 lb per 1,000 square feet of actual nitrogen, 4 percent phosphorous, and 2 percent potassium by weight. 3.) Slow-release fertilizer for trees and shrubs: granular fertilizer consisting of 50 percent water-insoluble nitrogen, phosphorous and potassium made up of a composition by weight of 5 percent.

4.) Grade lawn and grass areas to a smooth, even surface with loose, uniformly fine texture. Limit fine grading to areas that can be planted within immediate future. Remove trash, debris, stones larger than 1 inch diameter, and other objects that may interfere with planting or maintenance operations. Sow seed using a spreader of seeding machine. Do not seed when wind velocity exceeds 5 miles per hour.

5.) Distribute seed evenly over entire area by sowing equal quantity in 2 directions at right angles to each other. 6.) Rake seed lightly into top 1/8 inch of soil, roll lightly, and water with a fine spray.

7.) Install erosion control blankets as indicated on the Erosion Control Plan. 8.) Protect seeded areas against erosion by spreading clean, seed-free straw mulch after completion of speeding operations. Spread uniformly to form a continuous blanket not less than 1-1/2 inches loose measurements over seeded areas. 9.) Water newly planted lawn areas and keep moist until new grass is established. Immediately repair any lawn areas disturbed by construction activities including tree and shrub installation.

10.) Refer to the Permanent Seeding Details within the Erosion Control Detail Sheet, for timing of permanent seeding, grass seed specifications and mulching specifications.

B13 MATERIAL HANDLING AND SPILL PREVENTION PLAN

No solid material, including building materials, is permitted to be discharged to surface waters or buried on site. All solid waste materials, including disposable materials incidental to construction activity, must be collected in containers or closed dumpsters. The collection containers must be emptied periodically and the collected material hauled to a landfill permitted by the State and/or appropriate local municipality to accept the waste for disposal.

A foreman or supervisor should be designated in writing to oversee, enforce, and instruct construction workers on proper solid waste procedures.

Whenever possible, minimize the use of hazardous materials and generation of hazardous wastes. All hazardous waste materials

Use containment berms in fueling and maintenance areas and where potential for spills is high.

will be disposed in the manner specified by federal, state, or local regulations or by the manufacturer.

A foreman or supervisor should be designated in writing to oversee, enforce, and instruct construction workers on proper hazardous waste procedures. The location of any hazardous waste storage areas should be indicated on the stormwater pollution prevention plan by the operator following on-site location of the facility.

Dust Control/Off-Site Vehicle Tracking During construction, water trucks should be used, as needed, by each contractor or subcontractor to reduce dust. After construction, the site should stabilized to reduce dust.

Construction traffic should enter and exit the site at a Construction Entrance with a rock pad or equivalent device. The purpose of the rock pad is to minimize the amount of soil and mud that is tracked onto existing street. If sediment escapes the construction site, off-site accumulations of sediment must be removed a frequency sufficient to minimize off-site impacts.

Sanitary/Septic

Contractors and subcontractors must comply with all state and local sanitary sewer, portable toilet, or septic system regulations. Sanitary facilities shall be provided at the site by each contractor or subcontractor throughout construction activities. The sanitary facilities should be utilized by all construction personnel and be serviced regularly. All expenses associated with providing sanitary facilities are the responsibility of the contractors and subcontractors. The location of any sanitary facilities should be indicated on the stormwater pollution prevention plan by the operator following on-site location of said facilities.

Water used to establish and maintain grass, to control dust, and for other construction purposes must originate from a public water supply or private well approved by the State or local health department.

**Equipment Fueling and Storage Areas** 

Equipment fueling, maintenance, and cleaning should only be completed in protected areas (i.e., bermed area). Leaking equipment and maintenance fluids will be collected and not allowed to discharge onto soil where they may be washed

Equipment wash-down (except wheel washes) should take place within an area surrounded by a berm. The use of detergents is prohibited.

Chemicals, paint, solvents, fertilizers, and other toxic or hazardous materials should be stored in their original containers (if original container is not resealable, store the products in a clearly labeled, waterproof container). Except during application, the containers should be kept in trucks or in bermed areas within covered storage facilities. Runoff containing such materials shall be collected, removed from the site, and disposed of in accordance with the federal state, and local

As may be required by federal, state or local regulations, the Contractor should have a Hazardous Materials Management Plan and/or Hazardous Materials Spill and Prevention Program in place. A foreman or supervisor should be designated in writing to oversee, enforce, and instruct construction workers on proper hazardous materials storage and handling procedures. The location of any hazardous material storage areas should be indicated on the stormwater pollution prevention plan by the operator following on-site location of the storage areas.

Discharge of hazardous substances or oil into stormwater is subject to reporting requirements. In the event of a spill of a hazardous substance, the operator is required to notify the National Response Center (1-800-424-8802) to properly report the spill. In addition, the operator shall submit a written description of the release (including the type and amount of material released, the date of the release, the circumstances of the release, and the steps to be taken to prevent future spill) to the local governing authority. The SWPPP must be revised within 14 calendar days after the release to reflect the release, stating the information above along with modifications minimize the possibility of future occurrences. Each contractor and subcontactor is responsible for complying with these reporting requirements.

All concrete trucks waste material shall be completely contained and disposed in accordance with all local, state, and federal regulations. A pit or container is required when cleaning concrete chutes.

Minor - Small spills that typically involve oil, gasoline, paint, hydraulic fluid, etc. can be controlled by the first responder at the discovery of the spill.

• Contain spill to prevent material from entering storm or groundwater. Do not flush with water or bury. • Use absorbent material to clean-up spill material and any subsequently contaminated soil and dispose of properly. Semi-Significant Spills - Approximately ten gallons or less of pollutant with no contamination of ground or surface waters. Minor spills can be generally controlled by the first responder with help from other site personnel. This response may require other operations to stop to make sure the spill is quickly and safely addressed. At the discovery of the spill:

• Contain spill to prevent material from entering storm or ground water. Do not flush with water or bury. • Use absorbent material to clean-up spills and dispose of properly. Spills on impervious surfaces should be disposed of as soon as possible to prevent migration deeper into the soil and groundwater. Dispose of contaminated soils or

absorbents properly. Contact 911 if the spill could be a safety issue

• Contact supervisors and designated site inspectors, including MS4 personnel, immediately. • Contaminated solids are to be removed to an approved landfill.

Major or Hazardous Spills - More than ten gallons, there is the potential for death, injury or illness to humans or animals, or has the potential for surface or groundwater pollution. • Control or contain the spill without risking bodily harm. Temporarily plug storm drains if possible to prevent migration

of the spill into the stormwater system • Immediately contact the local Fire Department at 911 to report any hazardous material spill • Contact supervisors and designated site inspectors immediately. Governing authorities, including MS4 personnel, responsible for stormeater facilities should be contacted as well. The contractor is responsible for having these contact numbers available at the job site. A written report should be submitted to the owner as soon as possible.

• As soon as possible but within 2 hours of discovery, contact the local agency responsible for spill management. The following information should be noted for future reports to the agency: •• Name, address and phone number of person making the spill report

•• The location of the spill •• The time of the spill

•• Identification of the spilled substance •• Approximate quantity of the substance that has been spilled or may be further spilled

•• The duration and source of the spill Name and location of the damaged waters

 Name of spill response organization •• What measures were taken in the spill response

 Other information that may be significant Additional regulations or requirement may be present. A spill response professional should be consulted to make sure all appropriate and required steps have been taken. Contaminated solids should only be removed from the site after

approval is give by the appropriate agency. B14 MONITORING AND MAINTENANCE GUIDELINES FOR EACH PROPOSED STORMWATER QUALITY MEASURE

nspection Schedule/Reporting All impacted areas, as well as all erosion and sediment control devices, will be inspected every seven (7) calendar days and within 24 hours after a rianfall of 0.5 inch or greater. Where sites have been final or temporarily stabilized or on sites where runoff is unlikely due to winter conditions (e.g. site is covered with snow, ice, or frozen ground exists), such inspections shall be conducted at least once every month.

Inspections shall be conducted and a written report prepared, by a designated and qualified person familiar with the USEPA NPDES Storm Water General Permit, this SWPPP, and the Project.

Inspection reports shall be completed including scope of the inspection, name(s) and qualifications of personnel making the inspection, the date of the inspection, observations relating to the implementation of the SWPPP, and any actions taken as a result of incidents of noncompliance noted during the inspection. The inspection report should state whether the site was in compliance or identify and incidents of noncompliance. The contractor shall keep a copy of the inspection reports on site and permanently for a period of two years following construction. The on-site reports may be requested by inspections conducted by the local governing authority.

Locations where vehicles exit the site shall be inspected for evidence of off-site sediment tracking. Each contractor and subcontractor shall be responsible for maintaining the Construction Entrance and other controls as described in this

Inspectors must evaluate areas used for storage of materials that are exposed to precipitation. The purpose is to ensure that materials are protected and/or impounded so that pollutants cannot discharge from storage areas. Off-site material

control plans and site inspection reports. Seeded areas will be inspected to confirm that a healthy stand of vegetation is maintained. The site has achieved final stabilization once all areas are covered with pavement or have a stand of vegetation with at least 70% of the background

vegetation density. The density of 70% or greater must be maintained to be considered as stabilized. The operator or their

storage areas used solely b the subject project are considered to be part of the project and must be included in the erosion

Erosion and Sediment Control Inspections

representative will water, fertilize, and reseed disturbed areas as needed to achieve this goal.

All controls should be inspected at least once every seven (7) calendar days and following any storm event of 0.5 inch or greater. The following is a list of inspection/maintenance practices that will be used for specific controls: 1. Geotextiles/Erosion Control Mats: Missing or loose matting must be replaced or re-anchored.

2. Inlet Protection: If silt fence inlet protection is to be used, sediment should be removed when it reaches

5. Stabilized Construction Entrance: Periodic re-grading and top dressing with additional stone.

approximately one-half the height of the fence. If a sump is used, sediment should be removed when the volume of the basin is reduced by 50%. 3. Mulching: Inspect for thin or bare spots caused by natural decomposition or weather-related events. Mulch in high traffic areas should be replaced on a regular basis to maintain uniform protection. 4. Silt Fence: Removal of built-up sediment will occur when the sediment reaches one-third the height of the fence.

6. Vegetation: Protect newly seeded areas from excessive runoff and traffic until vegetation is established. Establish a watering and fertilizing schedule. 7. Good Housekeeping: Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges through screening of outfalls and daily pickup

In the event that sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize adverse impacts. An example of this may be the situation where sediment has washed into the street and could be carried into the storm sewers by the next rainfall and/or pose a safety hazard to user of public Modifications/Revisions to SWPPP

Based on inspection results, any necessary modification to this SWPPP shall be implemented within seven (7) calendar days of the inspection. A modification is necessary if a control measure or operational procedure does not provide adequate pollutant control. All revisions shall be recorded on a Record of Revisions within seven (7) calendar days of the

It is the responsibility of the operator to maintain effective pollutant discharge controls. Physical site conditions or contractor/subcontractor practices could make it necessary to install more control than were originally planned. Fore example, localized concentrations of surface runoff or unusually steep areas could required additional silt barrier or other structural controls. Assessing the need for and installing additional controls will be a continuing contractor/subcontractor responsibility until final stabilization is achieved. Contractors and subcontractors implementing this SWPPP must remain alert to the need to periodically refine and update this SWPPP in order to accomplish the intended goals.

Compliance of the site with the General Construction Permit remains the responsibility of all operators that have submitted an NOI until such time as they have submitted a Notice of Termination (NOT). The permittee's authorization to discharge under the General Construction Permit terminates at midnight of the day the NOT is signed.

All permittees must submit an NOT within thirty (30) days after one or more of the following conditions have been met: 1. Final stabilization has been achieved on all portions of the site for which the permittee was responsbile. 2. Another operator/permittee has assumed control over all areas of the site that have not been finally stabilized. 3. In residential construction operations, temporary stabilization has been completed and the residence has been transferred to the homeowner.

B15 EROSION AND SEDIMENT CONTROL SPECIFICATIONS FOR INDIVIDUAL BUILDING LOTS

The site is not currently subdivided, therefore the entire site is on this plan's Erosion Control Plan.

C1 DESCRIPTION OF POLLUTANTS AND THEIR SOURCES ASSOCIATED WITH THE PROPOSED LAND USE

The proposed land use is for the construction of the Wheatland Wastewater System Improvements Division II - Gravity Sewer System Project which involves constructing new 8 in. gravity sanitary sewer in residential and commercial areas. The pollutants and sources of each pollutant normally expected from the types of land use within the town are as follows; Pollutant Source: Passenger vehicles, delivery vehicles.

antifreeze, windshield cleaner solution, brake fluid, dust, rubber, glass, metal and plastic fragments, grit, road de-icing Pollutant Source: Building

Type of Pollutant: Cleaning solutions or solvents, leaks from HVAC equipment, grit from roof drainage, aggregate or rubber

Type of Pollutant: Oil, gasoline, diesel fuel, any hydrocarbon associated with vehicular fuels and lubricants, grease,

Pollutant Source: Trash Dumpster Type of Pollutant: Cleaning solutions or solvents, litter (paper, plastic, general refuse associated with distribution

fragments from roofing system.

operations), uneaten food products, bacteria. Pollutant Source: Parking Lot

compounds from periodic maintenance (sealing, resurfacing, and patching), pavement de-icing materials, paint fragments

Type of Pollutant: Any pollutant associated with vehicular sources, grit from asphalt wearing surface, bituminous

from parking stall striping, concrete fragments, wind-blown litter from off-site sources, elevated water temperatures from contact with impervious surfaces.

Pollutant Source: Lawn and Landscape Areas

Type of Pollutant: Fertilizers, soil, organic material (leaves, mulch, grass clippings) C2 SEQUENCE DESCRIBING STORMWATER QUALITY MEASURE IMPLEMENTATION

The grass-lined channels and swales will serve as the permanent water quality features after construction is complete. The purpose of these features is to filter pollutants and sediment.

C3 DESCRIPTION OF PROPOSED POST-CONSTRUCTION STORMWATER QUALITY MEASURES

Vegetated swales are designed to reduce pollutant and sediment loads in stormwater runoff. Stormwater runoff is directioned in the swale which conveys the runoff from the site. While moving through the swale, runoff velocity is greatly decreased allowing biofiltration (uptake of nutrients by plants), infiltration (percolation of water through the swale's porous soil substrate), and sedimentation (settling of later suspended particles).

Topsoil will be placed in lawn areas and seeded with grass, and graded not to exceed 3:1 slopes. Proposed landscape trees

and shrubs will also be added. These bio areas will act as a natural filter strip to help improve stormwater quality. The vegetated areas will slow the velocities of stormwater runoff, reduce sediment runoff, and reduce problems associated

with mud or dust from bare soils. Good Housekeeping Measures Good housekeeping measures such as regular street or pavement sweeping, installation of trash receptacles, and

C4 LOCATION, DIMENSIONS, SPECIFICATIONS, AND CONSTRUCTION DETAILS OF EACH STORMWATER QUALITY MEASURE

reduction in fertilizer overspray can be incorporated by the owner and/or occupant.

Refer to the Erosion Control Plans for locations and Erosion Control Details for details.

C5 DESCRIPTION OF MAINTENANCE GUIDELINES FOR POST-CONSTRUCTION STORMWATER QUALITY MEASURES Maintenance requirements for the stormwater quality measures which will remain in place after construction is complete,

are described below. Vegetated swales require little maintenance if properly designed. Mow as needed during the growing season; inspect for

Wet Detention Pond Remove debris and sediment from entire pond when necessary. Inspect perimeter of basin annually and after major storm events. Regrade soil if gullies form and replant ground. Inspect inlet and outlet devices and structures annually and after

erosion control problems twice during the first year, annually thereafter; and removed sediment, trash and debris annually



KNOX COUNTY SOILS CHARACTERISTICS AND LIMITATIONS Ra - RAGSDALE SILT LOAM • ReA - REESVILLE SILT LOAM, 0 TO 2 % SLOPES

INTENTIONAL INNOVATION

STEM S Ш PR M WHE/ 1


ON

Project #: 21-400-194-1


Revision

Designed By: WMW Drawn By: RLH

Checked By: ALC



STORMWATER **POLLUTION** PREVENTION PLAN



В



CONSTRUCTION SET
WHEATLAND WASTEWATER SYSTEM
IMPROVEMENTS
DIVISION I - WASTEWATER TREATMENT PL

STATION

REGIONAL

AND


Revision Date


Project #: 21-400-194-1


Designed By: LD

Drawn By: AB, WD

Checked By: LD









WHEATLAND WASTEWATER SYSTEM
IMPROVEMENTS
VISION I - WASTEWATER TREATMENT PLAN

Project #: 21-400-194-1

Revision

Date

Designed By: LD

Drawn By: AB, WD

Checked By: LD

No. ARTISOO136


STATE OF

WOLANA
CHITE
CHI



DEMOLITION PLAN - BASE BID

AD100





### WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS /ISION I - WASTEWATER TREATMENT PLAN

CONSTRUCTION

# Revision Date

Project #: 21-400-194-1

Designed By: LD


Drawn By: AB, WD

Checked By: LD





FIRST FLOOR
REFLECTED DEMOLITION
CEILING PLAN - ALT. 1





### WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS /ISION I - WASTEWATER TREATMENT PLAN


Revision Date

Project #: 21-400-194-1

Designed By: LD

Drawn By: AB, WD


Checked By: LD





FIRST FLOOR PLAN -BASE BID

AF10





### WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS VISION I - WASTEWATER TREATMENT PLAN AND REGIONAL LIFT STATION

Revision


Date

Project #: 21-400-194-1

Designed By: Designer

Drawn By: Author


Checked By: Checker





FIRST FLOOR PLAN - ALT. 2

AF103





STEWATER SYSTEM CONSTRUCTION DIVISION I - WASTEWA WHEATLAND WA


Date

Revision

Project #: 21-400-194-1


Designed By: LD

Drawn By: AB, WD





FIRST FLOOR CEILING PLAN - ALT. 2





STEWATER SYSTEM

Revision Date

Project #: 21-400-194-1


Designed By: LD

Checked By: LD





ARCHITECTURAL ROOF PLAN - ALT. 1





WHEATLAND WASTEWATER SYSTEM DIVISION I - WASTEWATER

AND REGIONAL LIFT STATION WHEATLAND, IN 47597


Date

Project #: 21-400-194-1


Revision


Designed By: LD

Checked By: VW



OVERALL BUILDING **ELEVATIONS** 







CONSTRUCTION SET
WHEATLAND WASTEWATER SYSTEM
IMPROVEMENTS

AND REGIONAL LIFT STATION WHEATLAND, IN 47597

# Revision Date


**DIVISION I - WASTEWATER** 

Project #: 21-400-194-1

Designed By: LD

Drawn By: AB, WD


Checked By: LD





ENLARGED RESTROOM PLAN

A410






CONSTRUCTION SET
WHEATLAND WASTEWATER SYSTEM
IMPROVEMENTS

# Revision Date

Project #: 21-400-194-1


Designed By: LD

Drawn By: AB, WD
Checked By: LD



DOOR AND FRAME SCHEDULE

A600





WHEATLAND WASTEWATER SYSTEM
IMPROVEMENTS
ISION I - WASTEWATER TREATMENT PLAN


Revision Date

Project #: 21-400-194-1

Designed By: LD

Drawn By: AB, WD


Checked By: LD






INTERIOR FINISH PLANS

IN10'







WHEATLAND WASTEWATER SYSTEN IMPROVEMENTS
DIVISION I - WASTEWATER TREATMENT PAND REGIONAL LIFT STATION

CONSTRUCTION

Project #· 21-400-194-1

Revision


Date

Project #: 21-400-194-1

Designed By: LD

Drawn By: AB, WD

Checked By: LD



INTERIOR SECTIONS & DETAILS

IN300

### **GENERAL NOTES:**

- 1. Building Code: Indiana Building Code, 2014 Edition
- 2. Design Loads:

A. Access Stair and Platform: Live Load = 150 psf

Dead Load = 4.8 psf (Grating)

2.8 plf (Handrail)

B. Manual Bar Screen: Dead Load = 4.8 psf (Grating)
120 pcf (Soil)

- 3. Contractor to install all equipment in complete accordance with all manufacturer's recommendations.
- 4. All fasteners, supports etc. to be Stainless Steel.
- 5. Refer to specifications for further information.
- 6. All concrete to be min. F'c = 4,000 psiAll reinforcing steel to be min. F'y = 60,000 psi
- 7. See Structural detail sheets and Electrical/Mechanical sheets for further detail.
- 8. See Plant Control/Monitor specifications for necessary equipment coordination.
- 9. All Ferrous metal surfaces to be prepared and painted in accordance with the specifications.
- 10. Contractor to coordinate with all other applicable plan sheets and specifications. 7.
- 11. Contractor to verify equipment mounting elevations and dimensions prior to construction.
- 12. Reinforcing details shown represent minimum requirements. Alternate but equal methods are acceptable, but they shall not be used without prior approval 8. of the engineer.
- 13. "L" Represents the minimum development according to ACI 318, based on grade 60 steel reinforcing and 4,000 psi (211 kg/mm) 28-day concrete.
- 14. All dowels shall be of the same size and spacing as the bar being doweled or as shown elsewhere on the drawings.
- 15. The reinforcing details shown on this drawing are intended to establish basic reinforcing requirements for various general types of horizontal and vertical joints in reinforced concrete structures. Details designated as "Plan" are horizontal joints and details designated as "Section" are vertical joints. Other details are self explanatory. When the condition exists in a structure that conforms to one of these details, the reinforcing requirements shown on the applicable detail shall be incorporated into the structure unless the condition is specifically detailed elsewhere on the drawings.
- 16. The following concrete cover shall be provided for reinforcement unless otherwise indicated:
  - A. Concrete cast against and permanently exposed to earth: 3" (bottom mat and sides of slabs or other concrete cast against the earth).
  - B. Concrete exposed to earth, weather or fluid surfaces: 2" (tank walls, beams, slabs, columns).
  - C. Concrete not exposed to earth in contact with ground: 1 1/2".
- 17. An undimensioned bend represents a standard hook.
- 18. Where one grid of reinforcing is required in a wall or slab, the grid shall be centered in the element unless otherwise located on the plans with a clear distance to either side of the element.
- 19. All reinforcing splices to meet ACI requirements.
- 20. Max. "A" for walls = 4'-0", Max. "A" and "B" for slabs = 4'-0". Larger Openings require special treatment.
- 1. Chamfer all exposed edges 3/4" (Typical)

### FOUNDATION NOTES:


- 1. Design soil bearing Pressure = 2,000 psf
- Backfilling along walls and grade beams shall be placed simultaneously where walls have fill on each side. Backfilling of cantilevered retaining walls shall be with clean sand and gravel placed with a minimum amount of tamping or compacting once concrete has attained full strength. Walls to be tied into slab on grade shall be braced until the concrete slab on grade and adjacent wall have attained full strength.
- 3. No horizontal construction joints are permitted in walls unless noted.
- 4. All anchor bolts shall be furnished by the Structural Steel Contractor and installed buy the Foundation Contractor.
- 5. Footings and slabs shall be poured on firm, undisturbed soil or on engineered fill. Engineered fill shall be free-draining and compacted to a minimum dry density of 100% of the maximum standard proctor dry density (ASTM-D698) placed in 6" to 8" lifts.
- 6. Undercutting of the soil for foundation and/or slab placement may be required. These drawings do not indicate the entire scope of the undercutting, fill or bad soil removal that may be required to attain the design soil bearing pressures. It is the responsibility of the Contractor to obtain a soils investigation report, before bidding, to assess the extent of excavation and compaction that may be required to meet the design criteria.
- 7. The Geotechnical Representative shall be retained to monitor all backfilling operations and to inspect footing bearing materials. A Report certified by the soils engineer shall be furnished to the Architect/Engineer verifying that all foundations were placed on a material capable of sustaining the design bearing pressures.
- 8. The bottoms of all foundations shall be protected from moisture damage and/or freezing if the foundation cannot be cast immediately.
- 9. If dewatering is required, sumps shall not be placed within the foundation excavation.

### **REINFORCED CONCRETE:**

- 1. Unless otherwise noted, cover, laps, splices and embedment lengths shall conform to ACI 318-2019 (22).
- 2. No horizontal construction joints shall be permitted in grade beams or walls unless specifically shown on the drawings. Horizontal reinforcement in perimeter walls shall be continuous with a lap of 1'-9" minimum.
- 3. All horizontal bars in walls or grades beams shall be bent at coners or intersections in such a way that continuity is provided through the joint.

### STRUCTURAL STEEL:

- 1. All beam end connections shall be designed for 0.5Wc/L (kips). Beam end connections shall be single angle framed beam connections. Wc = uniform load constant (kip-ft) for the beam as shown in the AISC Manual 15th Edition. L = Beam span in feet.
- 2. All welding shall be done by the electric arc method in accordance with the AWS Structural Welding Code D1.1 E70XX electrodes conforming to AWS A5.1 orA5.5 shall be used for the shielded metal arc method and E70XX flux-electrode combination conforming to AWS5.17 for the submerged arc method.
- 3. All Rolled structural steel shall conform to ASTM A50 U.N.O. All structural steel tube shal conform to ASTM A500.
- 4. All field connections shall be made with 3/4" diameter ASTM A325N bearing type bolts with threads assumed in the shear plane U.N.O. in the specifications. Connections for horizontal and vertical bracing shall develop 50% of the member strength.
- 5. All connections shall be a minimum of two (2) 3/4" diameter A325 bolts. or a weld developing a minimum force of 10 kips.
- Weld all floor plates to beam with 3/16" x 2" long at 2'-8" on centers.
- 7. All Structural steel shall be detailed, fabricated, installed and erected in accordance with the latest AISC "Specifications for Design, Fabrication and Erection of Structural Steel for Buildings".
- 8. See the specifications regarding the painting of steel.
- 9. Steel framing connections shall be tightened and columns shall be leveled and grouted in place before decking is placed.
- 10. Burning of holes in structural steel is not permitted without prior approval of the structural engineer.
- 11. All steel floor plates shall span continuously over a minimum of 3 spans. All floor plates shall butt into a continuous 1/4" bent toe plate around platform perimeter.





WHEATLAND WASTEWATER SYSTEM
IMPROVEMENTS
IVISION I - WASTEWATER TREATMEN
PLANT AND REGIONAL LIFT STATION

SET

CONSTRUCTION

# Revision Date


Project #: 21-400-194-1

Designed By: KJJ

Drawn By: DRD

Checked By: KJJ


Date: 01/05/2023



200' 0 200' 4

**GRAPHIC SCALE** 

STRUCTURAL DETAILS






## WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS

# Revision Date

Project #: 21-400-194-1
Designed By: KJJ

Drawn By: DRD
Checked By: KJJ


Date: 01/05/2023



Terrett J. Jane

GRAPHIC SCALE

STRUCTURAL DETAILS





### WHEATLAND WASTEWATER SYSTEN IMPROVEMENTS (VISION I - WASTEWATER TREATME)

# Revision Date


Project #: 21-400-194-1

Designed By: KJJ

Drawn By: DRD

Checked By: KJJ


Date: 01/05/2023









STRUCTURAL DETAILS







Scale: 1/2" = 1'-0"




### SYSTEM WHEATLAND WA

CONSTRUCTION SE

# Revision


Project #: 21-400-194-1 Designed By: KJJ Drawn By: DRD Checked By: KJJ

Date: 01/05/2023





STRUCTURAL STEEL **DETAILS** 





# WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS [VISION I - WASTEWATER TREATMEN]

CONSTRUCTION SET

# Revision Date


Project #: 21-400-194-1

Drawn By: DRD

Designed By: KJJ

Date: 01/05/2023


Checked By: KJJ



Termeth J. January



STRUCTURAL STEEL DETAILS



WHEATLAND WASTEWATER SYSTEM
IMPROVEMENTS
SION I - WASTEWATER TREATMENT PLANT

 $\forall$ 

ONA

CD #

# Revision Date

Project #: 21-400-194-1

Designed By: RH

Drawn By: RH

Checked By: KI

Date: 12/28/22

No. 12200401

STATE OF

WOJANA


NOT FOR CONSTRUCTION



PLUMBING SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES

P00

В



WHEATLAND WASTEWATER SYSTEM
IMPROVEMENTS
DIVISION I - WASTEWATER TREATMENT PLANT
AND REGIONAL LIFT STATION
WHEATLAND, IN 47597

Revision Date

Project #: 21-400-194-1

Designed By: RH

Drawn By: RH


Checked By: KI

Date: 12/28/22


No. 12200401

STATE OF

NOT FOR CONSTRUCTION



FOUNDATION PLUMBING PLANS



WHEATLAND WASTEWATER SYSTEM
IMPROVEMENTS
DIVISION I - WASTEWATER TREATMENT PLA
AND REGIONAL LIFT STATION
WHEATLAND, IN 47597

CONSTRUCTION

# Revision Date

Project #: 21-400-194-1

Designed By: RH


Drawn By: RH

Checked By: KI





FIRST FLOOR PLUMBING PLANS




Date

Project #: 21-400-194-1

Drawn By: RH

ROOF PLUMBING PLAN



HEATLAND WASTEWATER SYSTEM IMPROVEMENTS

# Revision Date

Project #: 21-400-194-1

Drawn By: RH

Checked By: KI

Designed By: RH

Date: 12/28/22

No. 12200401

STATE OF

WOIANA


WOIANA

STATE

ST

NOT FOR CONSTRUCTION

PLUMBING SCHEDULES





IMPROVEMENTS
DIVISION I - WASTEWATER TREATMENT PLANT
AND REGIONAL LIFT STATION
WHEATLAND, IN 47597


Revision

Date

Project #: 21-400-194-1

Checked By: KI


Date: 12/28/22



NOT FOR CONSTRUCTION



PLUMBING WASTE AND VENT PIPING ISOMETRIC



WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS

TATION

# Revision Date

Project #: 21-400-194-1

Designed By: RH

Drawn By: RH

Checked By: KI

Date: 12/28/22


No. 12200401

STATE OF

NOT FOR CONSTRUCTION

N

**DETAILS - PLUMBING** 



'ATION

SYSTEM WHEATL

> Revision Date

Project #: 21-400-194-1

Designed By: Designer


Checked By: Checker

Date: 12/28/22



NOT FOR CONSTRUCTION

DETAILS - PLUMBING



ST S  $\simeq$ ш EWA. 黑黑 Ш Ш 8 IMPROV STEWA WA N  $\bowtie$ WHE/

'ATION

ONAL ATLAND,

CD H

 $\Delta$ 

Date

Project #: 21-400-194-1

Revision


Designed By: N.H. Drawn By: N.H.

Checked By: D.B.


Date: 12/28/22



NOT FOR CONSTRUCTION



MECHANICAL SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES



WHEATLAND WASTEWATER SYSTEM
IMPROVEMENTS
ISION I - WASTEWATER TREATMENT PLAN
AND REGIONAL LIFT STATION

Revision Date


Project #: 21-400-194-1

Drawn By: N.H.

Checked By: D.B.

Designed By: N.H.


Date: 12/28/22




NOT FOR CONSTRUCTION



FIRST FLOOR MECHANICAL PLANS







WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS


# Revision Date

Project #: 21-400-194-1

Designed By: LC

Drawn By: **JM**Checked By: **LC** 

Date: **1/5/2023** 





SCALE:NTS

AEROMOD TANK LAYOUT

NOTE:

1. WATER LEVEL FROM DOWNSTREAM
TREATMENT CAN NOT BACK UP ABOVE 40"
BELOW TOP OF WALL.





CLARATOR MODEL #16272 ELEVATION

### NOTE:

- 1. THIS WASTEWATER TREATMENT SYSTEM LAYOUT IS BASED ON AEROMOD PACKAGE PLANT DESIGN. CONTRACTOR SHALL PROVIDE WWTP PACKAGE PLANT DESIGN AS SHOWN AND SPECIFIED.
- 2. ALL WASTEWATER TREATMENT EQUIPMENT SHOWN HEREIN SHALL BE PROVIDED BY THE PACKAGE PLANT SUPPLIER FOR SYSTEM INTEGRITY.
- 3. PROVISION OF PVC PROCESS PIPING, PVC AIR HEADER, DIP OR WELDED STEEL AIR PIPING AND PNEUMATIC PIPING OUTSIDE THE TANK UNDERGROUND SHALL BE SUPPLIED BY GENERAL CONTRACTOR.
- 4. REFER TO SPEC SECTION 46 07 53 FOR DETAILS OF WWTP PACKAGE PLANT DESIGN



WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS
IVISION I - WASTEWATER TREATMEN

SET


# Revision Date

Project #: 21-400-194-1

Designed By: LC

Drawn By: **JM**Checked By: **LC** 


Date: 1/5/2023




SCALE:NTS

**CLARIFIER DETAIL** 

- THIS WASTEWATER TREATMENT SYSTEM LAYOUT IS BASED ON AEROMOD PACKAGE PLANT DESIGN. CONTRACTOR SHALL PROVIDE WWTP PACKAGE PLANT DESIGN AS SHOWN AND SPECIFIED.
- 2. ALL WASTEWATER TREATMENT EQUIPMENT SHOWN HEREIN SHALL BE PROVIDED BY THE PACKAGE PLANT SUPPLIER FOR SYSTEM INTEGRITY.
- 3. PROVISION OF PVC PROCESS PIPING, PVC AIR HEADER, DIP OR WELDED STEEL AIR PIPING AND PNEUMATIC PIPING OUTSIDE THE TANK UNDERGROUND SHALL BE SUPPLIED BY GENERAL CONTRACTOR.
- 4. REFER TO SPEC SECTION 46 07 53 FOR DETAILS OF WWTP PACKAGE PLANT DESIGN



CLARATOR MODEL #16272 PROFILE



### WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS

# Revision Date


Project #: 21-400-194-1

Designed By: LC

Drawn By: JM


Checked By: LC


Date: **1/5/2023** 




SCALE:NTS


CLARIFIER DETAIL SECTION VIEW A-A






- REF DETAIL B, SHEET M308







TYP. AERATION TANK AERATOR WA-PS2-2

**PROFILE VIEW** 

APPROX

POST AERATION TANK AERATOR WA-PF4/6-2

TYPICAL WALL AERATOR WA-HS2-2



WHEATLAND WASTEWATER SYSTEM
IMPROVEMENTS
DIVISION I - WASTEWATER TREATMEN
PLANT AND REGIONAL LIFT STATION

# Revision Date

Project #: 21-400-194-1

Designed By: **LC** 


Drawn By: **JM**Checked By: **LC** 

Date: **1/5/2023** 





SCALE:NTS





TYPICAL WALL AERATOR, WAD-HSS2-2





TYPICAL WALL AERATOR, WAD-HSS2-2A



WHEATLAND WASTEWATER SYSTEM
IMPROVEMENTS

DIVISION I - WASTEWATER TREATMEN
PLANT AND REGIONAL LIFT STATION

# Revision Date


Project #: 21-400-194-1

Designed By: **LC** 

Drawn By: **JM** 

Checked By: LC


Date: **1/5/2023** 




SCALE:NTS

WALL AERATOR WAD-HSS2-2 & 2A EQUIPMENT DETAIL

### MODEL AL-300 SOLIDS WASTING AIRLIFT



MODEL AL-300L SOLIDS WASTING AIRLIFT



DO PROBE

### NOTE:

- FOR BEST ACCURACY DISSOLVED OXYGEN
   MEASUREMENTS, THE PROBE SHOULD BE TAKEN 2'-0"
   BELOW THE WATER SURFACE, AND 3'-0" AWAY FROM
   THE TANK WALL.
- 2. THE DO PROBE, MOUNTING BRACKET AND SENSOR CABLE CONNECTION TO THE DO ANALYZER SHOULD BE PROVIDED BY WWTP PACKAGE SYSTEM SUPPLIER.



# WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS DIVISION I - WASTEWATER TREATMEN

# Revision Date


Project #: 21-400-194-1

Designed By: LC

Drawn By: **JM** 

Checked By: LC


Date: **1/5/2023** 




SCALE:NTS


AIR LIFT & DO PROBE DETAILS

1. MATERIAL IS .038 NOMINAL THICKNESS, PRESSURE MOLDED TELENE.







### ROUND INLET SCREEN



TYPICAL SUCTION HOOD





SLIDE GATE



### WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS IVISION I - WASTEWATER TREATMEN PI ANT AND REGIONAL LIFT STATION

# Revision Date


Project #: 21-400-194-1

Designed By: **LC** 

Drawn By: **JM** 

Checked By: LC

Date: **1/5/2023** 





SCALE:NTS

SMALL COMPONENT DETAILS (1 OF 3)


### DIGESTER SUPERNATANT RETURN WEIR

(INSTALL ON DIGESTER SIDE OF WALL)





DETAIL A (NTS)



**AERATOR DETAILS** 



WHEATLAND WASTEWATER SYSTEN IMPROVEMENTS


# Revision Date

Project #: 21-400-194-1

Designed By: LC

Drawn By: **JM**Checked By: **LC** 


Date: **1/5/2023** 



SCALE:NTS

SMALL COMPONENT DETAILS (2 OF 3)

- 1. THIS WASTEWATER TREATMENT SYSTEM LAYOUT IS BASED ON AEROMOD PACKAGE PLANT DESIGN. CONTRACTOR SHALL PROVIDE WWTP PACKAGE PLANT DESIGN AS SHOWN AND SPECIFIED.
- 2. MANUAL BAR SCREEN IS PROVIDED BY PACKAGE PLANT SUPPLIER. CONTRACTOR SHALL FIELD VERIFY BAR SCREEN MOUNTING AND INLET PIPE WALL PENETRATION LOCATION.
- 3. DUE TO MOVEMENT, WEIGHT & VIBRATION, PIPING OVER WALL & OUTSIDE OF TANKS MUST BE RIGIDLY SUPPORTED TO PREVENT INTERIOR PVC PIPING DAMAGE. EXPANSION JOINTS ARE ALSO REQUIRED TO ISOLATE MOVEMENT OF PVC PIPING AND D.I.P. OR WELDED STEEL PIPING AT CONNECTION INSIDE TANKS. (THIS IS THE RESPONSIBILITY OF THE GENERAL CONTRACTOR)



MANUAL BAR SCREEN



### WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS

CONSTRUCTION SET


# Revision Date

Project #: 21-400-194-1

Designed By: LC

Drawn By: **JM**Checked By: **LC** 

Date: **1/5/2023** 



SCALE:NTS

SMALL COMPONENT DETAILS (3 OF 3)



SEE SITE PLAN M300 FOR CONTINUATION TO UV SYSTEM

6"x6"X4"

REDUCING TEE

WHEATLAND WASTEWATER SYSTEN IMPROVEMENTS
VISION I - WASTEWATER TREATME

# Revision Date

Project #: 21-400-194-1
Designed By: **LC** 

Drawn By: **JM**Checked By: **LC** 

Date: **1/5/2023** 



SCALE:NTS

PIPING PLAN OVERALL LAYOUT

M310

BRACKETS USED FOR SUPPORTING PVC PIPING ARE TYPICALLY SPACED 5'-0" APART. AEROMOD WILL SUPPLY THE PNEUMATIC TUBING AND FITTINGS ASSOCIATED WITH THE OPERATION OF THE AEROMOD EQUIPMENT. PIPE SUPPORTS FOR NON-PVC PIPE WILL NEED TO BE SUPPLIED BY THE GENERAL CONTRACTOR.

3. DUE TO MOVEMENT, WEIGHT & VIBRATION, PIPING OVER WALL & OUTSIDE OF TANKS MUST BE RIGIDLY SUPPORTED TO PREVENT INTERIOR PVC PIPING DAMAGE. EXPANSION JOINTS ARE ALSO REQUIRED TO ISOLATE MOVEMENT OF PVC PIPING AND D.I.P. OR WELDED STEEL PIPING AT CONNECTION INSIDE TANKS. (THIS IS THE RESPONSIBILITY OF THE GENERAL CONTRACTOR)

4. REFER TO SPEC SECTION 46 07 53 FOR DETAILS OF WWTP PACKAGE PLANT DESIGN AND SCOPE.

### SECTION VIEW A-A

### NOTE

- 1. PROVISION OF PVC PROCESS PIPING, PVC AIR HEADER, DIP OR WELDED STEEL AIR PIPING AND PNEUMATIC CONDUITS OUTSIDE THE TANK UNDERGROUND SHALL BE SUPPLIED BY GENERAL CONTRACTOR.
- 2. AEROMOD SCOPE OF SUPPLY INCLUDES THE STAINLESS STEEL SUPPORTS (WALL BRACKETS) FOR THE PVC PIPE INSIDE OF THE TANKS, AS WELL AS THE FLEX HOSES THAT ATTACH PIPING TO AERO-MOD SUPPLIED EQUIPMENT. THE WALL AND ANGLE BRACKETS USED FOR SUPPORTING PVC PIPING ARE TYPICALLY SPACED 5'-0" APART. AEROMOD WILL SUPPLY THE PNEUMATIC TUBING AND FITTINGS ASSOCIATED WITH THE OPERATION OF THE AEROMOD EQUIPMENT. PIPE SUPPORTS FOR NON-PVC PIPE WILL NEED TO BE SUPPLIED BY THE GENERAL CONTRACTOR.
- 3. DUE TO MOVEMENT, WEIGHT & VIBRATION, PIPING OVER WALL & OUTSIDE OF TANKS MUST BE RIGIDLY SUPPORTED TO PREVENT INTERIOR PVC PIPING DAMAGE. EXPANSION JOINTS ARE ALSO REQUIRED TO ISOLATE MOVEMENT OF PVC PIPING AND DIP OR WELDED STEEL PIPING AT CONNECTION INSIDE TANKS. (THIS IS THE RESPONSIBILITY OF THE GENERAL CONTRACTOR)
- 4. REFER TO SPEC SECTION 46 07 53 FOR DETAILS OF WWTP PACKAGE PLANT DESIGN AND SCOPE.



# WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS IVISION I - WASTEWATER TREATMEN

# Revision Date

Project #: 21-400-194-1

Designed By: LC

Drawn By: JM


Checked By: **LC** 

Date: **1/5/2023** 



SCALE:NTS

PIPING PLAN SECTION VIEW A-A



### SECTION VIEW B-B

### NOT

- 1. PROVISION OF PVC PROCESS PIPING, PVC AIR HEADER, DIP OR WELDED STEEL AIR PIPING AND PNEUMATIC PIPING OUTSIDE THE TANK UNDERGROUND SHALL BE SUPPLIED BY GENERAL CONTRACTOR.
- 2. AEROMOD SCOPE OF SUPPLY INCLUDES THE STAINLESS STEEL SUPPORTS (WALL BRACKETS) FOR THE PVC PIPE INSIDE OF THE TANKS, AS WELL AS THE FLEX HOSES THAT ATTACH PIPING TO AERO-MOD SUPPLIED EQUIPMENT. THE WALL AND ANGLE BRACKETS USED FOR SUPPORTING PVC PIPING ARE TYPICALLY SPACED 5'-0" APART. AEROMOD WILL SUPPLY THE PNEUMATIC TUBING AND FITTINGS ASSOCIATED WITH THE OPERATION OF THE AEROMOD EQUIPMENT. PIPE SUPPORTS FOR NON-PVC PIPE WILL NEED TO BE SUPPLIED BY THE GENERAL CONTRACTOR.
- 3. DUE TO MOVEMENT, WEIGHT & VIBRATION, PIPING OVER WALL & OUTSIDE OF TANKS MUST BE RIGIDLY SUPPORTED TO PREVENT INTERIOR PVC PIPING DAMAGE. EXPANSION JOINTS ARE ALSO REQUIRED TO ISOLATE MOVEMENT OF PVC PIPING AND DIP OR WELDED STEEL PIPING AT CONNECTION INSIDE TANKS. (THIS IS THE RESPONSIBILITY OF THE GENERAL CONTRACTOR)
- 4. REFER TO SPEC SECTION 46 07 53 FOR DETAILS OF WWTP PACKAGE PLANT DESIGN AND SCOPE.



# WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS

# Revision Date


Project #: 21-400-194-1

Designed By: **LC** 

Drawn By: **JM** 


Checked By: **LC** 

Date: **1/5/2023** 





PIPING PLAN SECTION VIEW B-B






WHEATLAND WASTEWATER SYSTEM
IMPROVEMENTS
DIVISION I - WASTEWATER TREATMEN
PLANT AND REGIONAL LIFT STATION

# Revision Date

Project #: 21-400-194-1
Designed By: **LC** 

Drawn By: **JM** 

Checked By: **LC**Date: **1/5/2023** 




SCALE:NTS

PIPING PLAN SECTION VIEWS C-C & D-D


Checked By: LC

Date: **1/5/2023** 




SCALE:NTS

PIPING PLAN SECTION VIEW E-E



SECTION VIEW E-E





WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS

CONSTRUCTION

# Revision Date


Project #: 21-400-194-1

Designed By: LC

Checked By: LC


Drawn By: **JM** 


Date: 1/5/2023



SCALE:NTS

PIPING PLAN SECTION VIEWS F-F & G-G







### WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS EVISION I - WASTEWATER TREATMER


# Revision Date

Project #: 21-400-194-1

Designed By: LC

Drawn By: **JM**Checked By: **LC** 

Date: **1/5/2023** 



SCALE:NTS

PIPING PLAN SECTION VIEWS H-H & J-J

2" PVC -CONDUIT ELBOW VERTICAL AIR BRACKET, TYP. FLEX HOSE, TYP. (PART #VA-9.5) 6" WALL BRACKET, TYP√ (PART #6SSWB) 2" PVC AIR LINE TO FLEX HOSE FOR A WAD-HSS2-2A 2" PVC AIR -LINE, TYP. 10" WALL BRACKET, TYP. -(PART #10SSWB) WALL AERATOR ASS'Y, TYP. 4" PVC ELBOW, TYP. 4" PVC AIR LINE └ 10" WALL BRACKET, TYP. 4" x 2" PVC CLAMP-ON SADDLES, TYP. 14'-0", (PART 310SSWB) REF 12'-8" 2" PVC ELBOWS — FINISHED GRADE ELEV 479.75'± SELECTOR **AERATION TANK A1** TANK (1ST STAGE) - FINISHED FLOOR ELEV. 475.75

SECTION VIEW K-K



### WHEATL DIVISION


# Revision Date

Project #: 21-400-194-1 Designed By: LC

Drawn By: **JM** 

Checked By: LC


Date: **1/5/2023** 



SCALE:NTS


PIPING PLAN SECTION VIEW K-K

TYP ADJUSTABLE PIPE SUPPORT DETAIL SCALE: NTS




ADJUSTABLE PIPE SUPPORT WITH "U" BOL1 SCALE: NTS

ADJUSTABLE PIPE SUPPORT (HOT DIPPED GALVANIZED) DIMENSIONS IN INCHES					
21/2	21/2	11/2	9	9	3
3	21/2	1½	9	9	3
31/2	21/2	1 1/2	9	9	3
4	3	2 1/2	9	9	6
6	3	2 ½	9	12	6
8	3	2 ½	12	12	6
10	3	2 ½	12	12	10
12	3	2 ½	12	15	10
14	4	3	12	15	10
16	4	3	12	18	10
18	6	4	14	18	10
20	6	4	14	20	10
24	6	4	14	24	10



PIPE SUPPORT BRACKET

SCALE: NTS



SCALE: NTS

TYPICAL WALL PENETRATION AND REINFORCEMENT DETAIL

INTENTIONAL INNOVATION

WHEATL

CONSTRUCTION


# Revision

Project #: 21-400-194-1

Designed By: **LC** 

Drawn By: **JM** Checked By: LC

Date: **1/5/2023** 



SCALE:NTS

PIPING DETAILS

<u>M318</u>

### WHEATLAND WASTEWATER SYSTE IMPROVEMENTS

# Revision Date

Project #: 21-400-194-1


Designed By: **LC**Drawn By: **JM** 


Checked By: **LC**Date: **1/5/2023** 



SCALE:NTS

**WALKWAY PLAN** 







# WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS EVISION I - WASTEWATER TREATMEN PI ANT AND REGIONAL LIFT STATION

# Revision Date

Project #: 21-400-194-1

Designed By: LC

Drawn By: **JM**Checked By: **LC** 


Date: **1/5/2023** 



10' 0 10'

GRAPHIC SCALE

WALKWAY DETAILS (1 OF 2)



INTENTIONAL INNOVATION

SYSTEM WHEATL

# Revision Date

Project #: 21-400-194-1

Checked By: LC



WALKWAY DETAILS (2 OF 2)

<u>M321</u>

STAIRCASE & LANDING ELEVATION



# WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS [VISION I - WASTEWATER TREATMEN

CONSTRUCTION

# Revision Date


Project #: 21-400-194-1

Designed By: **LC** 

Drawn By: **JM** 

Checked By: LC


Date: **1/5/2023** 



20' 0 20' 4

STRUCTURE FRAME PROFILE

STAIRWAY DETAILS



GENERAL CONTRACTOR)

SCOPE.

6. REFER TO SPEC SECTION 46 07 53 FOR DETAILS OF BLOWER PACKAGE, COMPRESSOR AND DRYER UNIT DESIGN AND

BQ / W
INTENTIONAL INNOVATION

AND WASTEWATER SYSTEM IMPROVEMENTS
- WASTEWATER TREATMENID REGIONAL LIFT STATION


# Revision Date

Project #: 21-400-194-1

Designed By: LC


Drawn By: JM

Checked By: **LC**Date: **1/5/2023** 



1' 0 1'
GRAPHIC SCALE

POLE BARN BLOWER LAYOUT





WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS
[VISION I - WASTEWATER TREATMEN

# Revision Date


Project #: 21-400-194-1

Designed By: LC

Drawn By: **JM**Checked By: **LC** 

Date: **1/5/2023** 





POLE BARN SECTION VIEWS A-A & B-B



### WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS IVISION I - WASTEWATER TREATMER

# Revision Date


Project #: 21-400-194-1

Designed By: **LC** 


Drawn By: **JM**Checked By: **LC** 

Date: **1/5/2023** 





POLE BARN SECTION VIEW C-C




INTENTIONAL INNOVATION



SCALE: NTS

PNEUMATIC CONNECTION PLAN

<u>M326</u>





# WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS IVISION I - WASTEWATER TREATMEN

# Revision Date

Project #: 21-400-194-1

Designed By: LC

Drawn By: **JM** 

Checked By: **LC**Date: **1/5/2023** 



SCALE: NTS

UV SYSTEM & & POST AERATION


**M327** 

Designed By: **LC** 

Drawn By: **JM** 


Checked By: LC


Date: **1/5/2023** 



SCALE: NTS


UV SYSTEM & POST AERATION DETAILS





### INSTRUMENT SUNSHIELD DETAILS

### CONTROL PANEL MOUNTING STATION



UV MODULE SECTIONS

### SINGLE AND MULTI-ZONE DX SPLIT SCHEDULE

REMARKS:

1. PROVIDE WIRELESS REMOTE CONTROLLER KIT FOR EACH INDOOR UNIT

2. OUTDOOR UNIT SHALL BE RATED FOR LOW AMBIENT CONTROL DOWN TO -5 F. PROVIDE RATED CAPACITIES AS LISTED FOR COOLING AT 47F AND HEATING AT 17F.

4. CONTRACTOR SHALL SIZE ALL REFRIGERANT PIPING SO AS NOT TO REDUCE RATED CAPACITY. SUBMIT REFRIGERANT PIPING DETAIL WITH SUBMITTAL

5. INDOOR UNITS SHALL BE POWERED THROUGH OUTDOOR UNIT

6. MOUNT OUTDOOR UNITS ON 12" HIGH ROOF RAILS OR STAND FOR GRADE MOUNTED UNITS. 7. OUTDOOR UNIT SHALL BE RATED FOR OPERATION DOWN TO 0 DEG F

8. PROVIDE WITH VENTILATION KIT.

DIT NO VIDE VVIIII																		
OUTDOOR UNIT					INDOOR UNI	т						OUTDOOR UN	ΙΙΤ					
MARK	MANUFACTURER	MARK	MODEL	STYLE	MAX CFM	OUTSIDE AIR CFM	COOLING MBH	HEATING MBH	MARK	MODEL	COOLING CAPACITY	HEAITNG CAPACITY	SEER/EER	HSPF	МСА	МОСР	VOLTS/ PHASE	REMARKS
ACCU-1	LG	AC-1A	LSN120HSV5	WALL MOUNT	460	0	12.0	13.0	ACCU-1	LSU120HSV5	12 MBH	12 MBH	22/12.5	10	10	15	208 / 1	1,2,3,4,5,6,7
ACCU-2	LG	AC-2A	ARNU123TRD4	CASSETTE	335	35	12.0	13.0	ACCU-2	ARUN024GSS4	24 MBH	27 MBH	17 / 10.7	10	19.6	30	208 / 1	1,2,3,4,5,6,7,8
ACCU-2	LG	AC-2B	ARNU123TRD4	CASSETTE	335	35	12.0	13.0	ACCU-2	AKUN024G334	24 (VIDIT	27 IVIDIT	17 / 10.7	10	19.0	30	200 / 1	1,2,3,4,5,6,7,8

BERKO (OR EQUAL)

UH-1 BERKO (OR EQUAL)

SRA2024DSF

HUH-524SA

	EXHAUST FAN SCHEDULE																					
. PROVIDE W	/ITH 16" HIGH INSUL	LATED ROOF CURB.																				
MANUFACT	URER TO PROVIDE	MOTOR STARTER.																				
	LOCATION					WHEEL				MOTOR									UNIT	DESIGN RE	FERENCE	
MARK	NAME	SERVICE	TYPE	CEM	ESP (IN-WG)	TYPE	FAN RPM	ΗD	ВНР	VOLTS/PHASE/HE RTZ	FLA	EMERGENCY POWER		BELT B	IRD	GRAVITY BDD	MOTORIZED DAMPER	VIBRATION ISOLATORS	MTD. DISC. SW	MANUFACTURER	MODEL NO.	REMARKS
EF-1	ROOF	EXHAUST FAN	CENTRIFUGAL DOWNBLAST	1000	0.50	DI	1057	0.25	0.13	115/1/60	3.8	No	Yes		res	Yes	No	Yes	Yes	GREENHECK	G-130-VG	1,2

WALL MOUNTED

CEILING/STRUCTURE MOUNTED

### **CONTROLS**:

### **DX SPLIT SYSTEMS:**

DX SPLIT SYSTEMS SHALL MODULATE BETWEEN COOLING AND HEATING DEPENDING ON SPACE REQUIREMENTS. SYSTEM SHALL STAGE COMPRESSORS TO MAINTAIN SPACE SETPOINTS. UNIT SHALL BE CONTROLLED BY WIRELESS REMOTE/THERMOSTAT KIT PROVIDED BY MANUFACTURER. THE SUPPLY FAN SHALL RUN CONTINUOUSLY TO PROVIDE THE REQUIRED VENTILATION RATE FOR THE OFFICE.

В

A

ERV SHALL OPERATE CONTINUOUSLY EXTRACTING EXHAUST AIR FROM THE BATHROOM AND PROVIDING FRESH AIR TO THE OFFICE.

### **ROOF EXHAUST FAN:**

ROOF EXHAUST FAN SHALL BE TIED TO A LABELED WALL SWITCH TO ALLOW FOR SUMMER VENTILATION/DESTRATIFICATION.

### **ELECTRIC WALL HEATERS (EWH-1, 2):**

ELECTRIC WALL HEATERS SHALL MODULATE THE HEATING ELEMENT TO MAINTAIN SPACE TEMPERATURE SETPOINT OF 68 DEG (ADJ).

### **ELECTRIC UNIT HEATERS (UH-1):**

ELECTRIC UNIT HEATERS SHALL MODULATE THE HEATING ELEMENT TO MAINTAIN SPACE TEMPERATURE SETPOINT OF 55 DEG (ADJ.)

### **INSULATION REQUIREMENTS:**

### **DUCTWORK:**

ALL DUCTWORK ASSOCIATED WITH THE ERV AND ALL TRANSFER AIR DUCTWORK SHALL BE INSULATED WITH ONE OF THE FOLLOWING OPTIONS.

- 1. FLEXIBLE ELASTOMERIC: 1-1/2 INCHES THICK.
- 2. MINERAL-FIBER BLANKET: 1-1/2 INCHES THICK AND 0.75-LB/CU. FT. NOMINAL DENSITY.
- 3. MINERAL-FIBER BOARD: 1-1/2 INCHES THICK AND 2-LB/CU. FT. NOMINAL DENSITY. EXHAUST DUCTWORK ASSOCIATED WITH THE ROOF MOUNTED EXHAUST FAN DOES NOT NEED

TO BE INSULATED.

### PIPING:

SUCTION/HOT GAS PIPING SHALL HAVE 2" FLEXIBLE ELASTOMERIC INSULATION. OUTDOOR PIPING MUST HAVE A UV RESISTANT PVC JACKET.

### **ELECTRIC HEATER SCHEDULE** REMARKS: PROVIDE WITH UNIT MOUNTED DPST THERMOSTAT. 2. THERMOSTAT TO CYCLE FAN UPON A CALL FOR HEATING 3. PROVIDE WITH FACTORY MOUNTED INTEGRAL DISCONNECT SWITCH. 4. REFER TO FLOOR PLANS FOR UNIT QUANTITIES AND LOCATIONS **ELECTRICAL** MANUFACTURER **MODEL NUMBER TYPE** MOCP CHARACTERISTICS BERKO (OR EQUAL) SRA1512DSF WALL MOUNTED 5.12 120 V/ 1PH 12.5 15.6 20 1,2,3 1.5

				<b>ERV SC</b>	HEDULE	•				
REMARKS:	:									
1. PROVID	E WITH SPEED CONTROL SW	ITCH. MOUNT ON UNIT	·							
2. PROVID	E WITH VENT CAPS WITH BA	CKDRAFT GRAVITY DAN	IPERS AT OUT	SIDE PENETRATIO	NS.					
MARK	MANUFACTURER	MODEL NUMBER	EXHAUST CFM	EXHAUST ESP (in.w.c)	OUTSIDE AIR CFM	OUTSIDE AIR ESP (in.w.c)	WATTS	ELECTRICAL CHARACTERISTICS	МОСР	REMARKS
ERV-1	PANASONIC (OR EQUAL)	FV-10VEC2	70	0.25	70	0.25	18	120 V/ 1PH	20	1,2,3,4

6.83

208 V/ 1PH

208 V/ 1PH

7.3

20.8

10.5

26

15

30

1,2,3

1,2,3

			L	OUV	/ER	SCI	HED	)UL	.E			
1. FURNISH	WITH ALUMINU	M BUG SCREEN AND	SECURITY BAR	S.								
2. FURNISH	WITH KYNAR P.	AINT FINISH OF STAI	NDARD COLOR S	ELECTION	BY ARCHIT	ECT.						
3. PROVIDE	BACKDRAFT DA	AMPER.										
	LOCATION					DIMENSIONS		FREE			BIRD	
								AREA			SCREE	
MARK	NAME	MANUFACTURER	MODEL NO.	CFM	W	Н	D	(SF)	MAX FAV	APD	N	REMARKS
LV-1	LAB	RUSKIN	ELF6375DXD	2000	3' - 0"	3' - 0"	0' - 6"	4.9	500 FPM	0.10 in-wa	Yes	1.2.3

			DI	FFUSE	ER / G	RILLI	E SCH	HEDUL	E		
REMARKS:											
1. BRANCH DUCT	WORK TO THE DIFF	USER SHALL BE THI	E SAME SIZE AS 1	THE NECK UNLESS O	THERWISE NOTED	).					
2. PROVIDE FRAM	IE STYLE APPROPE	RIATE FOR CEILING T	YPE (I.E. LAY IN,	SURFACE MOUNT).							
3. PROVIDE SQUA	ARE TO ROUND TRA	NSITION FOR ROUN	ID RUN OUTS AS F	REQUIRED.							
4. PROVIDE CEILII	NG RADIATION DAM	IPER TO MEET RATII	NG OF CEILING C	ONSTRUCTION WHEF	RE REQUIRED.						
TAG	NECK SIZE	FACE LENGTH	FACE WIDTH	MATERIAL	FINISH	MAX NC	MAX THROW (FT)	MAX TOTAL APD (IN WG)	MANUFACTURER	MODEL	NOTES
E1	6"Ø	12"	12"	ALUMINUM	WHITE	15	6	0.05	PRICE	E-80	1,2,3,4
T1	6"Ø	12"	12"	ALUMINUM	WHITE	15	6	0.05	PRICE	E-80	1.2.3.4

ËR

Date Revision

Project #: 21-400-194-1

Designed By: N.H.

Drawn By: N.H. Checked By: D.B.


Date: 12/28/22



NOT FOR CONSTRUCTION



SCHEDULES -**MECHANICAL** 



SYSTEM TER WHEATL

TREATMENT

'ATION

Date Revision

Project #: 21-400-194-1

Designed By: N.H. Drawn By: N.H.

Checked By: D.B.

Date: 12/28/22

TIN E. BAR No. 12200401 STATE L

WOIANA

NONAL EN

NOT FOR CONSTRUCTION



**DETAILS - MECHANICAL** 

M800

C

В

**GENERAL NOTES** 

### NO SHADING INDICATES NORMAL POWER HALF SHADED INDICATES UNSWITCHED EMERGENCY FULL SHADED INDICATES SWITCHED EMERGENCY

LIGHTING

24" x 48" LIGHTING FIXTURE

24" x 24" LIGHTING FIXTURE

12" x 48" LIGHTING FIXTURE

12" x 36" LIGHTING FIXTURE

12" x 24" LIGHTING FIXTURE

12" x 12" LIGHTING FIXTURE

12" x 96" LIGHTING FIXTURE

6" x 96" LIGHTING FIXTURE

6" x 48" LIGHTING FIXTURE

6" x 36" LIGHTING FIXTURE

6" x 24" LIGHTING FIXTURE

WALL MOUNTED LIGHT

CEILING EXIT LIGHT (DUAL FACED)

CEILING EXIT LIGHT (SINGLE FACE)

WALL EXIT WITH EMERGENCY LIGHTS

WALL EXIT WITH INTERIOR AND

**EXTERIOR EMERGENCY LIGHTS** 

**EXIT LIGHT DIRECTIONAL ARROWS** 

WALL EMERGENCY BATTERY LIGHT

CEILING EMERGENCY BATTERY LIGHT

EXTERIOR POLE LIGHT (ONE HEAD)

EXTERIOR POLE LIGHT (TWO HEADS)

EXTERIOR POLE LIGHT (THREE HEADS)

EXTERIOR POLE LIGHT (FOUR HEADS)

EXTERIOR POLE LIGHT (TOP MOUNT)

TOGGLE SWITCH - HORSE POWER RATED MANUAL MOTOR

STARTER WITH THERMAL OVERLOAD PROTECTION

WALL OCCUPANCY SENSOR - 1 BUTTON CONTROL

WALL OCCUPANCY SENSOR - 2 BUTTON CONTROL

WALL OCCUPANCY SENSOR - DUAL RELAY FOR

WALL VACANCY SENSOR - 1 BUTTON CONTROL

WALL VACANCY SENSOR - 2 BUTTON CONTROL

0 - 3 HOUR TIMER SWITCH - 20 AMP, 120/277VAC

LOW VOLTAGE LIGHTING CONTROLLER

EXTERIOR BOLLARD

**ELECTRICAL SWITCHES** 

TOGGLE SWITCH - 20 AMP, 120/277VAC

TOGGLE SWITCH - KEY OPERATED

DIMMER SWITCH - 20 AMP, 120/277VAC

**DESCRIPTION** 

TOGGLE SWITCH - 3 WAY

TOGGLE SWITCH - 4 WAY

TOGGLE SWITCH - PILOT LIGHT

DIMMER SWITCH - 3 WAY

DIMMER SWITCH - 4 WAY

EXHAUST FAN CONTROL

PHOTO CELL

CEILING OCCUPANCY SENSOR

8" DOWNLIGHT

6" DOWNLIGHT

4" DOWNLIGHT

WALL EXIT LIGHT

**DESCRIPTION** 

POWER

POWER

<u>SYMBOL</u>

 $\bigcirc$ 

0

4\_}

**-**□

**□**•□

品

<u>SYMBOL</u>

 $D^3$ 

D 4

OC1

OC2

OC3

**©** 

VS1 VS2 LC

T PC

EL	ECTRICAL RECEPTACLES	
SYMBOL	<u>DESCRIPTION</u>	SYN
Φ	DUPLEX RECEPTACLE - NORMAL POWER CIRCUIT	\ \ \ \ \
•	DUPLEX RECEPTACLE - EMERGENCY POWER CIRCUIT	
П	DUPLEX GFCI RECEPTACLE - NORMAL POWER CIRCUIT	
<b>P</b>	DUPLEX GFCI RECEPTACLE - EMERGENCY POWER CIRCUIT	
₩	QUADRAPLEX RECEPTACLE - NORMAL POWER CIRCUIT	
₩	QUADRAPLEX RECEPTACLE - EMERGENCY POWER CIRCUIT	S V
甲	QUADRAPLEX GFCI RECEPTACLE - NORMAL POWER CIRCUIT	
甲	QUADRAPLEX GFCI RECEPTACLE - EMERGENCY POWER CIRCUIT	
φ	SIMPLEX RECEPTACLE - NORMAL POWER CIRCUIT	(R
•	SIMPLEX RECEPTACLE - EMERGENCY POWER CIRCUIT	
	SPECIAL RECEPTACLE - NORMAL POWER CIRCUIT	
•	SPECIAL RECEPTACLE - EMERGENCY POWER CIRCUIT	
₽	DUPLEX RECEPTACLE - TOP SWITCHED	<b>│                                    </b>
RECE	PTACLE LEGEND	•
Ŷ	RECEPTACLE ABOVE COUNTERTOP AT +2" ABOVE BACKSPLASH TO BOTTOM OF DEVICE. COORDINATE WITH CASEWORK TO BE INSTALLED.	
₽	RECEPTACLE INSTALLED BELOW COUNTERTOP AT +18" A.F.F. COORDINATE WITH CASEWORK TO BE INSTALLED.	(H
Ψ <sub>x</sub>	"X" DENOTES AS FOLLOWS:  NONE - 20 AMP, 125VAC  HM - 20 AMP, 125VAC, HORIZONTAL MOUNT TYPE  IG - 20 AMP, 125VAC, ISOLATED GROUND TYPE  S - 20 AMP, 125VAC, SURGE GUARD PROTECTION TYPE  ST - 20 AMP, 125VAC, SAFETY TYPE  WP - 20 AMP, 125VAC, WEATHERPROOF TYPE	
	CEILING DUPLEX RECEPTACLE - NORMAL POWER CIRCUIT	
<b>1 6</b>	CEILING DUPLEX RECEPTACLE - EMERGENCY POWER CIRCUIT	
I 🌦	CEILING QUADRAPLEX RECEPTACLE - NORMAL POWER CIRCUIT	
l 🌦	CEILING QUADRAPLEX RECEPTACLE - EMERGENCY POWER CIRCUIT	
I (T)	FLOOR BOX DUPLEX RECEPTACLE - NORMAL POWER CIRCUIT	
	FLOOR BOX DUPLEX RECEPTACLE - EMERGENCY POWER CIRCUIT	
	FLOOR BOX QUADRAPLEX RECEPTACLE - NORMAL POWER CIRCUIT	[ ]
	FLOOR BOX QUADRAPLEX RECEPTACLE - EMERGENCY POWER CIRCUIT	│
	FLOOR BOX BLANK	( €
₩Φ	FLOOR BOX POWER AND TELECOM	FA
	MULTI-OUTLET ASSEMBLY (POWER AND/OR TELECOM)	FA
<u> </u>	NFORMATION SYSTEMS	N/
SYME	BOL DESCRIPTION	

VOICE AND DATA ONLY OUTLET

# - QUANTITY OF JACK(S) AND CABLE(S)

TELECOMMUNICATIONS EQUIPMENT RACK

MICROPHONE INPUT RECEPTACLE - WALL MOUNTED

MICROPHONE INPUT RECEPTACLE - CEILING MOUNTED

CCTV COAXIAL CABLE OUTLET AND POWER OUTLET

"X" DENOTES AS FOLLOWS:

R - ROUGH-IN ONLY

CEILING - VOICE AND DATA WAP - WIRELESS ACCESS

TV SYSTEM OUTLET

FLOOR BOX - VOICE AND DATA

AUDIO/VISUAL CONTROLLER

SPEAKER - CEILING MOUNTED

**DOOR SECURITY SYSTEM** 

**DESCRIPTION** 

DOOR BUZZER

CCTV MONITOR OUTLET

ELECTRIC DOOR OPENER

ELECTRIC DOOR STRIKE

SECURITY DUTY STATION

SECURITY CARD READER

SECURITY DOOR CONTACTS

SECURITY EXIT PUSH BUTTON

MOTION DETECTOR

SECURITY MONITOR

SECURITY KEYPAD

CAMERA

BIOSCAN ACCESS PAD

SECURITY CONTROL PANEL

SECURITY DOOR EGRESS

SECURITY STAFF STATION

INTERCOM UNIT FLUSH MTD.

MASTER INTERCOM AND DIRECTORY UNIT

SECURITY DOOR ALARM MAGNETIC LOCK

SPEAKER - WALL MOUNTED

**VOLUME CONTROL** 

**CLOCK SYSTEM OUTLET** 

POINT

TV

HS

SYMBOL CCTV

MTV

DS

 $\square$ 

SCP

	⟨M⟩	MANUAL SENDING STATION
	<b>S</b> D	WALL SMOKE DETECTOR
	ŠĎ.	WALL SMOKE DETECTOR WITH SOUNDER BASE
	(SD)	CEILING SMOKE DETECTOR
	SD	CEILING SMOKE DETECTOR WITH SOUNDER BASE
Г	ÓD <sub>X</sub>	AUTOMATIC DUCT DETECTOR ("X" DENOTES AS FOLLOWS)  NONE - PHOTOELECTRIC TYPE S - SUPPLY R - RETURN
	<b>₹</b> T	REMOTE DETECTOR TEST STATION
	⟨RI⟩	REMOTE DETECTOR INDICATOR STATION
	(HD)	HEAT DETECTOR
	€D	FLAME DETECTOR
	₿D	BEAM DETECTOR
	H	WALL HORN ONLY
	H	WALL HORN STROBE
	Н	CEILING HORN ONLY
	H	CEILING HORN STROBE
	S	WALL SPEAKER ONLY
	\S\S	WALL SPEAKER STROBE
	Į Š	CEILING SPEAKER STROBE
	$\bigvee$	WALL VISUAL ONLY
		CEILING VISUAL ONLY
	ÁR>	FIRE ALARM ADDRESSABLE RELAY
	$\downarrow$	FIREMANS JACK
	<b>₩</b>	DOOR UNLOCK
	<b>Ø</b> ₽	DOOR RELEASE
	<b>₹</b> \$	SPRINKLER SYSTEM FLOW SWITCH
1	(TS)	SPRINKLER SYSTEM TAMPER SWITCH
	<b>₽IV</b>	POST INDICATOR VALVE
	FACP	FIRE ALARM CONTROL PANEL
J	FAAP	FIRE ALARM ANNUNCIATOR PANEL
]	NAC	FIRE ALARM NOTIFICATION APPLIANCE CONTROL PANEL
1		TDICAL ECHIDMENT
		CTRICAL EQUIPMENT
	SYMBOL	DESCRIPTION
1	ı    ⊰  ≻	

PAD MOUNTED TRANSFORMER

SUSPENDED TRANSFORMER

DISTRIBUTION PANELBOARD

BRANCH PANELBOARD - RECESSED MOUNT

COMBINATION MOTOR CONTROLLER / DISCONNECT

**BRANCH PANELBOARD - SURFACE MOUNT** 

DISCONNECT SWITCH - NON-FUSED

DISCONNECT SWITCH - FUSED

TELECOM TERMINAL BOARD

PUSHBUTTON OR PUSH PLATE

MOTOR ("X" DENOTES HORSEPOWER)

MOLDED CASE CIRCUIT BREAKER

AUTOMATIC TRANSFER SWITCH

**RACEWAY SYSTEM** 

<u>DESCRIPTION</u>

- PHASE CONDUCTORS

- GROUND

FOR ADDITIONAL INFORMATION

- FEEDER SIZE. (REFER TO FEEDER SCHEDULE

JUNCTION OR PULL BOX

ELECTRIC THERMOSTAT

**GROUND CONNECTION** 

**GROUND POINT** 

GROUND ROD

**GENERATOR** 

MOTOR CONTROLLER

GROUND BAR

<u>SYMBOL</u>

FXX

**FIRE ALARM SYSTEM** 

**DESCRIPTION** 

ACP	ACCESS PANEL AIR CONDITIONING UNIT	INCAN	INCANDESCENT
ACU		INCL	INCLUDE
ADD	ADDITION	ISG	ISOLATED GROUND SURGE GUARD JUNCTION BOX
ADJ	ADJUSTABLE	JB	
AF	AMPERE FRAME	JT	JOINT
AFC	ABOVE FINISHED CEILING	KEC	KITCHEN EQUIPMENT CONTRACTOR KITCHENETTE
AFF	ABOVE FINISHED FLOOR	KT	
AFG	ABOVE FINISHED GRADE	KVAR	KILOVOLT AMPERE
AHU	AIR HANDLING UNIT AMPERE INTERRUPTING CAPACITY	KVAR	KILOVOLT AMPERE REACTIVE
AIC		KW	KILOWATT
AL	ALUMINUM	LAB	LABORATORY
AM	AMMETER	LB	POUND
AMB	AMBIENT	LF	LINEAR FEET
APPROX.	APPROXIMATELY	LOC	LOCATION
ARCH	ARCHITECT	LS	LIFE SAFETY
ATS	AUTOMATIC TRANSFER SWITCH	LT	LIGHT
AUTO	AUTOMATIC	LTG	LIGHTING
AVG	AVERGE	LV	LOW VOLTAGE
BC	BARE COPPER	MATV	MASTER ANTENNA TELEVISION
BKR	BREAKER	MAX	MAXIMUM
BHP	BRAKE HORSEPOWER	MC	MECHANICAL CONTRACTOR
BL	BUILDING LINE	MCB	MAIN CIRCUIT BREAKER MOTOR CONTROL CENTER
BLDG	BUILDING	MCC	
BR	BRANCH	MDP	MAIN DISTRIBUTION PANEL
BTM	BOTTOM	MECH	MECHANICAL
C	CONDUIT	MH	MANHOLE
°C	DEGREES CELSIUS	MIN MISC	MINIMUM
CAB	CABINET	MLO	MISCELLANEOUS
CB or C/B	CIRCUIT BREAKER		MAIN LUGS ONLY
C/C	CENTER TO CENTER CLOSED CIRCUIT TELEVISION	MTD	MOUNTED
CCTV		MTG HT	MOUNTING HEIGHT
CKT	CIRCUIT	MU	MEDICINE UNIT
CL	CENTER LINE	OD	OUTSIDE DIAMETER OWNER FURNISHED-CONTRACTOR INSTA
CLG	CEILING	OFCI	
COL	COLUMN	OFOI	OWNER FURNISHED-OWNER INSTALLED
COMM	COMMUNICATION	OPNG	OPENING
COMP	COMPRESSOR	OPP	OPPOSITE
CONC	CONCRETE CONSTRUCTION	OR P	OPERATING ROOM
CONST CONT	CONTINUOUS	PB	POLE PUSHBUTTON
CONTR	CONTRACTOR	PBOX	PULL BOX PNEUMATIC ELECTRIC CONVERTER
CR	CRITICAL	PE	
CT	CURRENT TRANSFORMER	PF	POWER FACTOR
CU	COPPER	PH or Ø	PHASE
DB	DIRECT BURIAL	PV	POST INDICATOR VALVE
DC	DIRECT CURRENT	PNL	PANELBOARD
DEPT	DEPARTMENT	PL	PILOT LIGHT
DF	DRINKING FOUNTAIN	PREFAB	PREFABRICATED
DIST	DISTRIBUTION	PRES	PRESSURE
DM	DEMAND METER	PT	PNEUMATIC TUBE
DO	DRAWOUT	PTS	PNEUMATIC TUBE STATION
DRS	DOCTORS	PW	PART WINDING
DWG	DRAWING	PWR	POWER
EC	ELECTRICAL CONTRACTOR	RACU	ROOM AIR CONDITIONING UNIT
EF	EXHAUST FAN	RAD	RADIATION
ELEC	ELECTRIC	RECEPT	RECEPTACLE
ELEV	ELEVATOR	REF or REFR	REFRIGERATOR
ELV	ELEVATION	REINF	REINFORCED
EMER	EMERGENCY	RGIP	REMOTE GROUND INDICATING PANEL
ENCL	ENCLOSURE ELECTRIC PNEUMATIC	RM	ROOM
EP		RPM	REVOLUTIONS PER MINUTE
EQUIP	EQUIPMENT	SA	SUPPLY AIR
EWC	ELECTRIC WATER COOLER	SC	SHORT CIRCUIT
EX	EXPLOSIONPROOF	SG	SURGE GUARD PROTECTION
EXH	EXHAUST	SHT	SHEET
EXP	EXPANSION	SIG	SIGNAL
EXT	EXTERIOR DEGREES FAHRENHEIT	SN	SOLID NEUTRAL
⁰F		SPEC	SPECIFICATIONS
FA	FIRE ALARM	SQ	SQUARE
FAAP	FIRE ALARM ANNUNCIATOR PANEL	SS	SAFETY SWITCH
FACP	FIRE ALARM CONTROL PANEL	SSSS	SOLID STATE SOFT START
FC	FLAT CABLE	STD	STANDARD
FCU	FAN COIL UNIT	STN	STATION
FFC	FOOD FACILITY CONTRACTOR	STR	STRUCTURAL
FFS	FOOD FACILITY SUPPLIER FIRE HOSE CABINET	SUSP	SUSPENDED
FHC		SW	SWITCH
FIN	FINISH	SWBD	SWITCHBOARD
FIXT	FIXTURE	SWGR	SWITCHGEAR TEMPERATURE CONTROL CONTRACTOR
FL	FLOOR	TCC	
FLUOR	FLUORESCENT	TELE	TELECOMMUNICATION
FLEX-CONN FPC	FLEXIBLE CONNECTION FIRE PROTECTION CONTRACTOR	TEMP TMH	TEMPERATURE TOP OF MANHOLE
FSS	FUSED SAFETY SWITCH FOOTING	TV	TELEVISION
FTG		TYP	TYPICAL
FVR	FILMVIEWER	UC	UNDER CARPET
FV	FULL VOLTAGE	U/C	UNDER CABINET or UNDER COUNTER UNIT HEATER
FVNR	FULL VOLTAGE NON REVERSING	UH	
G or GND	GROUND	UV	UNIT VENTILATOR
GALV	GALVANIZED	V	VOLT
GC	GENERAL CONTRACTOR	VAC	VACUUM
GEN	GENERATOR	VB VC	VACUUM BREAKER
GFCI	GROUND FAULT CKT. INTERRUPTER GROUND FAULT INTERRUPTER	VC	VACUUM CLEANING
GFI		VEL	VELOCITY
GFP HGT	GROUND FAULT PROTECTION HEIGHT	VFD VM	VARIABLE FREQUENCY DRIVE VOLTMETER
HH	HANDHOLE	VOL	VOLUME
HID	HIGH INTENSITY DISCHARGE	VP	VAPORPROOF
HO	HAND OPERATED	VSD/VFC	VARIABLE SPEED DRIVE/CONTROLLER
HOA	HAND-OFF-AUTOMATIC	W/	WITH
HORZ	HORIZONTAL	W/O	WITHOUT
HP	HORSEPOWER	WTR	WATER
HPS	HIGH PRESSURE SODIUM	WP	WEATHERPROOF
HTR	HEATER	WT	WEIGHT
HV	HIGH VOLTAGE	XFMR	TRANSFORMER
		Z	IMPEDANCE
	<u>LINE SYMBOI</u>	<u>_S</u>	
	<del></del>		

LIGHT/SCREENED SOLID OR DASHED LINES INDICATE EXISTING TO REMAIN

— — HEAVY DASHED LINES INDICATE EXISTING TO BE REMOVED

— HEAVY CONTINUOUS LINES INDICATE NEW WORK

**ELECTRICAL ABBREVIATIONS** 

ID

INCAN

ABBREVIATION DESCRIPTION

HERTZ

INTERCOMMUNICATION

INSIDE DIAMETER

INCANDESCENT

**ABBREVIATION** 

A or AMP

A/C

ACP


**DESCRIPTION** 

AIR CONDITIONING

ACCESS PANEL

ALTERNATING CURRENT


AMPERE



### SYST 'ATION $\Delta$ ш MEN. EWA IONAL ATLAND, **IMPROVE** AND WHE/ Date Revision

SE


CONS\_



NOT FOR CONSTRUCTION

Project #: 21-400-194-1

Designed By: DJ




ELECTRICAL SYMBOLS, ABBREVIATIONS, AND **GENERAL NOTES** 

### 12/28/2022 3:23:56 PM




Date



NOT FOR CONSTRUCTION

FIRST FLOOR ELECTRICAL DEMOLITION



RQAW

WHEATLAND WASTEWATER SYSTEM
IMPROVEMENTS
ISION I - WASTEWATER TREATMENT PLAN
AND REGIONAL LIFT STATION

Date

Revision


Project #: 21-400-194-1

Designed By: DJ


Drawn By: DJ

Checked By: DB


Date: 12/28/22



NOT FOR CONSTRUCTION



FIRST FLOOR LIGHTING AND SYSTEMS PLANS





WHEATLAND WASTEWATER SYSTEM
IMPROVEMENTS
/ISION I - WASTEWATER TREATMENT PLAN
AND REGIONAL LIFT STATION
WHEATLAND, IN 47597

Date

Revision

Project #: 21-400-194-1

Designed By: Designer

Drawn By: Author


CONSTRUC

Checked By: Checker

Date: 12/28/22



NOT FOR CONSTRUCTION



FIRST FLOOR POWER PLAN

### GENERAL ELECTRICAL NOTES: ALL SHEETS

- A. LOCATE ALL EXISTING PIPING AND UTILITIES BEFORE INSTALLING UNDERGROUND CONDUITS; PROTECT ALL EXISTING INSTALLATIONS.
- B. ALL BELOW GRADE CONDUIT SHALL BE SCH. 40 PVC. ALL TRANSITIONS (90 DEGREE ELBOW) FROM BELOW GRADE TO ABOVE GRADE OR THROUGH A CONCRETE SLAB SHALL BE GALVANIZED RIGID STEFL.
- C. ALL OUTDOOR ABOVE GRADE CONDUIT SHALL BE RIGID ALUMINUM. SUPPORT EVERY 3'.
- D. ALL RIGID ALUMINUM CONDUIT WHERE IN CONTACT WITH EARTH OR CONCRETE SHALL HAVE OXIDATION RESISTANT COATING.
- E. ALL EQUIPMENT, WIRING, AND CONDUIT INSTALLED WITHIN WET WELL OR INTO A CLASS 1 DIVISION 1 AND/OR DIVISION 2 HAZARDOUS AREA SHALL BE EXPLOSION—PROOF RATED. ALL UNDERGROUND CONDUITS INSTALLED INTO A CLASS 1 DIVISION 1 AND/OR DIVISION 2 HAZARDOUS AREA SHALL BE GALVANIZED RIGID STEEL.
- F. PROVIDE PUTTY TYPE DUCT SEAL FOR ALL UNDERGROUND CONDUIT OPENINGS IN OUTDOOR EQUIPMENT.
- G. MAINTAIN 3' SEPARATION BETWEEN 480V POWER CONDUITS AND LOW VOLTAGE (NETWORK, 24V DC CONTROL, OR INTRINSICALLY SAFE CIRCUIT) CONDUITS. MAINTAIN 1' SEPARATION BETWEEN 120V POWER CONDUITS AND LOW VOLTAGE (NETWORK, 24V DC CONTROL, OR INTRINSICALLY SAFE CIRCUIT) CONDUITS.
- H. WHERE CONDUIT CROSSES UNDER EXISTING OR FUTURE ROADS/DRIVES, CONDUIT SHALL BE GALVANIZED RIGID STEEL. SAW CUT AND REPAIR EXISTING PAVEMENT AS NECESSARY.
- I. ANTI-CORROSION SUBSTANCE SHALL BE USED AS A BARRIER BETWEEN ALL DISSIMILAR METALS TO PREVENT CORROSION. USE IDEAL NOALOX ANTI-OXIDANT COMPOUND OR APPROVED EQUAL.
- J. WIRE AND CONDUIT ROUTES AND ELECTRICAL EQUIPMENT LOCATIONS ARE APPROXIMATE, FIELD VERIFY EXACT INSTALLATIONS.
- K. ALL WIRING, CONDUIT, AND TERMINATIONS FURNISHED AND INSTALLED BY CONTRACTOR.
- L. SEE ELECTRICAL ONE-LINE DIAGRAM FOR WIRING AND CONDUIT REQUIREMENTS.
- M. CONTRACTOR SHALL TAKE NECESSARY MEANS TO PROTECT AND SUPPORT CABLES TO PREVENT DAMAGE DURING CONSTRUCTION. PROTECT EXISTING SYSTEMS AND CABLING DURING CONSTRUCTION.
- N. MAINTAIN 5' MINIMUM SEPARATION BETWEEN VENTED TERMINAL BOXES AND OTHER ELECTRICAL EQUIPMENT. MAINTAIN 3' MINIMUM SEPARATION BETWEEN WET WELL HATCH AND ELECTRICAL EQUIPMENT.
- O. OWNER WILL COORDINATE WITH DUKE ENERGY TO PROVIDE 480V, 3PH POWER TO SITE.

### ELECTRICAL KEYED NOTES:

- 1. AREA LIGHTING. SEE LIGHTING FIXTURE SCHEDULE E313.
- 2. LIFT STATION CONTROL PANEL.
- 3. LIFT STATION POWER.
- 4. POWER & INSTRUMENTATION.
- 5. PAD MOUNTED TRANSFORMER.
- 6. GENERATOR PAD AND GENERATOR.
- 7. HEAT TRACE.8. UTILITY PRIMARY.



## WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS VISION I - WASTEWATER TREATMEN

Revision Date

Project #: 21-400-194-1

Designed By: WK/DD/JR

Drawn By: CG

Checked By: WRK/JWS

Date: 01/06/2023



SIMS-DURKIN ASSOCIATES
ENGINEERING COMPANY
5755 WEST 74TH STREET
INDIANAPOLIS, INDIANA 46278
PHONE: 317-209-4035
FAX: 317-222-4120
WEB: WWW.SIMS-DURKIN.COM

SDA PROJECT NUMBER: 2022141

PRINT DATE: 1/6/23
PLOT SCALE: 1:186 9116 EDIT DATE: 1/6/23

ELECTRICAL SITE PLAN

SCALE: 1"=30'-0"

0
30'
60

BUILDING ELECTRICAL EQUIPMENT LAYOUT

ELECTRICAL KEYED NOTES:

- 1. ELECTRIC SERVICE METER 277/480V 3PH, 4W.
- 2. SEE SHT M323 FOR COMPRESSORS & BLOWERS LAYOUT
- 3. TRANSFORMER FURNISHED AND INSTALLED BY UTILITY; REINFORCED CONCRETE PAD BY ELECTRICAL CONTRACTOR. 10' MINIMUM CLEARANCE IN FRONT, 3' MINIMUM CLEARANCE ALL OTHER SIDES. MINIMUM 4' AWAY FROM BUILDING.
- 4. GENERATOR WITH SUB-BASE 24HR FUEL TANK, ON REINFORCED CONCRETE PAD, 4' MINIMUM CLEARANCE ALL SIDES.
- 5. TWO GROUND RODS, 10' APART. SEE ONE-LINE.
- 6. 120V AIR DRYER RECEPTACLE. HOME RUN TO PANEL P-1.
- 7. 3 VFD BLOWER CONTROL PANELS. SEE ONE-LINE E303.
- 8. BLOWER DISCONNECT SWITCH. MOUNTED TO WALL. SEE ONE-LINE E303.
- 9. NEW HONEYWELL CHART RECORDER FOR WWTP FLOW METERING/RECORDING.
- 10. UBIQUITY AIRMAX ETHERNET WIRELESS BRIDGE.
- 11. 6" REINFORCED CONCRETE PAD.
- 12. CP-BSB/SQC AEROMOD PLC CONTROL PANEL.
- 13. LIGHTING CONTROL PANEL. SEE E312 DETAILS.
- 14. PANEL P-1
- 15. 480-120/208V TRANSFORMER.
- 16. DRYER.
- 17. COMPRESSOR ALTERNATION PANEL.
- 18. 2 COMPRESSORS.
- 19. BOLLARDS.
- 20. CONTROL AND ACCESSORY CIRCUITS. SEE E309.
- 21. EMERGENCY STOP FOR GENERATOR.
- 22. RECEPTACLE FOR COMPRESSOR AUTO DRAIN. HOME RUN TO PANEL P-1.



INTENTIONAL INNOVATION

Revision

Project #: 21-400-194-1

Designed By: WK/DD/JR

Drawn By: CG

Checked By: WRK/JWS


Date: 01/06/2023



SIMS-DURKIN ASSOCIATES

ENGINEERING COMPANY 5755 WEST 74TH STREET INDIANAPOLIS, INDIANA 46278 PHONE: 317-209-4035 FAX: 317-222-4120 WEB: WWW.SIMS-DURKIN.COM SDA PROJECT NUMBER: 2022141

BUILDING ELECTRICAL **EQUIPMENT LAYOUT** 



7. **15AT-EIN BREANEALINNHMIGEV A**PT-110 N

### ĒΜ

4

Revision

Project #: 21-400-194-1

Designed By: WK/DD/JR

Ш

**∃** 

Drawn By: CG

Checked By: WRK/JWS

Date: 01/06/2023



Joseph W. Sims

**ELECTRICAL ONE-LINE DIAGRAM** 



ELECTRICAL KEYED NOTES:

- 1. WET WELL.
- 2. FORCE MAIN.
- 3. VENTED TERMINAL BOX. SEE DETAILS.
- 4. EQUIPMENT CONCRETE PAD. SEE DETAILS.
- 5. BOLLARD TYPICAL OF 4. SEE DETAILS.
- 6. EQUIPMENT RACK. SEE DETAILS.
- 7. AREA LIGHT AND WIRELESS ETHERNET BRIDGE ON MAST.
- 8. LIFT STATION MAIN POWER FUSED DISCONNECT. SEE ONE-LINE.
- 9. CONTROL PANEL.
- 10. TRANSFORMER.
- 11. FIT PANEL MODEL MC608I. NO EQUALS.
- 12. FLOW METER CABLE FURNISHED BY FLOW METER MANUFACTURER, IN 1 1/4"C BY CONTRACTOR. THIS CABLE CANNOT BE CUT OR SPLICED. COORDINATE PROPER DISTANCE WHEN ORDERING.
- 13. PROVIDE LINK SEAL FOR EACH WET WELL PENETRATIONS.
- 14. UTILIZE KELLUM GRIPS FOR EACH CABLE SUSPENDED FROM BOX.
- 15. SUBMERSIBLE LEVEL SENSOR. KSPI MODEL 710 OR EQUIVALENT.
- 16. FLOAT SWITCHES. PROVIDE WITH STAINLESS STEEL "J" HOOKS.
- 17. FLOAT SWITCH AND SUBMERSIBLE TRANSMITTER MANUFACTURER CABLES. ALL CABLES TO BE LONG ENOUGH TO PUMP CONTROL PANEL. NO SPLICES ALLOWED.
- 18. INDIVIDUAL PUMP LEAD CONDUIT AND CABLES.
- 19. EUROMAG FLOW METER MODEL MUT2300. NO EQUALS.



INTENTIONAL INNOVATION

### TEWATER SYSTEM EMENTS WATER TREATMENT NAL LIFT STATION

REGIONAL

Project #: 21-400-194-1

# Revision

Designed By: WK/DD/JR

WHE/

Drawn By: CG


Checked By: WRK/JWS

Date: 01/06/2023




SIMS-DURKIN ASSOCIATES ENGINEERING COMPANY 5755 WEST 74TH STREET

5755 WEST 74TH STREET INDIANAPOLIS, INDIANA 46278 PHONE: 317-209-4035 FAX: 317-222-4120 WEB: WWW.SIMS-DURKIN.COM SDA PROJECT NUMBER: 2022141



NOT TO SCALE

- B. PROVIDE LINK SEAL WITH STAINLESS HARDWARE FOR ALL CONDUIT PENETRATIONS INTO LIFT STATION WET WELL.
- C. PROVIDE STAINLESS STEEL HARDWARE FOR ALL EQUIPMENT INSTALLED IN WET WELL; THIS INCLUDES BUT NOT LIMITED TO KELLEM'S CABLE GRIPS, CABLE RACKS, MOUNTING BRACKETS. BOLTS AND NUTS.
- D. WET WELL CLASSIFICATION IS CLASS 1, DIVISION 1 GROUP D ALL WIRING SHALL COMPLY.
- 1. STATION MOUNTED AREA LIGHT. LED TYPE MOUNTED ON 10' ALUMINUM MAST ON OR NEAR EQUIPMENT RACK. SEE FIXTURE SCHEDULE E313.
- 2. NEW DUPLEX PUMP CONTROL PANEL. SEE ONE-LINE AND PUMP CONTROL
- 3. ALUMINUM POSTS SHALL HAVE A CORROSION PROTECTIVE COATING.
- 8. 15A WEATHERPROOF GFCI COURTESY OUTLET WITH IN-USE COVER. BULKHEAD STYLE WITH TRIP BREAKER AND ETHERNET PORT. SIMILAR TO
- 9. 3"X3" ALUMINUM EQUIPMENT RACK. ALL RISERS TO HAVE CAPS TO PREVENT WATER PENETRATION. VERTICAL EQUIPMENT MOUNTS SHALL BE STAINLESS
- 11. 3' X 10' 8" RE-ENFORCED CONCRETE PAD ON GRAVEL SUBBASE.
- 14. UBIQUITY AIRMAX ETHERNET BRIDGE MODEL LITEBEAM M 5 NO EQUALS.
- 17. POWER FOR MAGNETIC FLOW METER FROM LIFT STATION CONTROL PANEL.



VENTED TERMINAL BOX DETAIL-TYPICAL

SIMS-DURKIN ASSOCIATES ENGINEERING COMPANY 5755 WEST 74TH STREET INDIANAPOLIS, INDIANA 46278 PHONE: 317-209-4035 F A X : 3 1 7 - 2 2 2 - 4 1 2 0

WEB: WWW.SIMS-DURKIN.COM SDA PROJECT NUMBER: 2022141

INTENTIONAL INNOVATION

Revision

MH

Project #: 21-400-194-1 Designed By: WK/DD/JR Drawn By: CG Checked By: WRK/JWS Date: 01/06/2023



LIFT STATION ELECTRICAL DETAILS

### NOTE:

- THE CONTRACTOR/PANEL FABRICATOR SHALL BE RESPONSIBLE FOR THE FINAL SELECTION OF COMPONENTS, LAYOUT, FABRICATION, WIRING AND TESTING; ALL SUBJECT TO SHOP DRAWING REVIEW. THESE DETAILS ARE INTENDED TO INDICATE SCOPE OF WORK, QUALITY REQUIREMENTS, AND EXPECTATIONS
- SAGINAW CONTROL AND ENGINEERING (SCE): ENCLOSURE, EQUIPMENT PANEL AND DEAD FRONT SWING PANEL SHOWN FOR REFERENCE.

PUMP CONTROL PANEL SIDE VIEW

### ELECTRICAL KEYED NOTES:

- 1. NEMA 4X STAINLESS STEEL ENCLOSURE, 72"X60"X24" MINIMUM.
- 2. 72"X60" INTERIOR EQUIPMENT PANEL.
- 3. DEAD FRONT SWING PANELS.
- 4. ALARM STROBE LIGHT.
- 5. GREEN PUSH-TO-TEST AND AMBER PUST-TO-TEST PILOT LIGHTS, TYPICAL FOR EACH PUMP. 30.5MM NEMA4X.
- 6. 3 POSITION HOA SWITCH, TYPICAL FOR EACH PUMP. 30.5MM NEMA4X.
- 7. MOTOR PROTECTION RELAYS FLUSH MOUNT. MATCH PUMP MANUFACTURER SPECIFICATIONS. FLYGT MINICAS II SHOWN. IF FLUSH—MOUNT VERSION IS NOT AVAILABLE, PROVIDE PILOT LIGHTS AND PUSH BUTTONS FOR SEAL FAIL, OVERTEMP AND RESET.
- 8. 2 POSITION SELECTOR SWITCH FOR PLC OR FLOAT MODE SELECTION.
- 9. NAME PLATES. WHITE WITH BLACK LETTERS. TYPICAL.
- 10. THREE PHASE MAIN POWER ENTRY DISTRIBUTION BLOCK.


PUMP CONTROL PANEL OUTER DOOR VIEW

- 11. MAIN POWER GROUND BLOCK.
- 12. WIRE DUCT AS REQUIRED.

- 13. 15A 1P CONTROL POWER CIRCUIT BREAKER.
- 14. SPARE 1P CIRCUIT BREAKER 15A.
- 15. 2 POLE 15A POWER TRANSFORMER CIRCUIT BREAKER.
- 16. PHASE MONITOR RELAY.
- 17. 3 PHASE MONITOR RELAY CIRCUIT BREAKER.
- 18. 3 PHASE SURGE PROTECTOR DEVICE (SPD) CIRCUIT BREAKER.
- 19. 3 PHASE SPD.
- 20. CONTROL RELAYS, 120VAC COIL AND 10A MIN. CONTACT RATING. DPDT TYPICAL.
- 21. RUNTIME HOUR METER. TYPICAL
- 22. LOCKABLE HANDLE.
- 23. FIELD WIRING AND SWING PANEL COMPONENT INTERFACE WIRING TERMINAL BLOCKS.
- 24. SEAL FAIL MODULE FIELD WIRING TERMINAL BLOCKS.
- 25. INTRINSICALLY SAFE BARRIER (ISB) BOX WITH 4-CHANNEL DIGITAL ISB MODULE FOR FLOAT SWITCHES AND ANALOG ISB FOR LEVEL SENSOR.
- 26. VARIABLE FREQUENCY DRIVES (VFD): ABB ACQ580-31 ULH AC DRIVE, WITH EMBEDDED ETHERNET/IP, STANDARD PROTECTION,

- FORCED AIR, AC INPUT WITH DC TERMINALS, OPEN TYPE, 10 AMPS, 5HP ND, 480 VAC, 3 PH AND REMOTE KEYPAD MODULE.
- 27. AIR CONDITIONING UNIT WITH HEATER, SCE—AC3400 OR SIMILAR. AIR CONDITIONING UNIT TO BE SIZED BY CONTRACTOR BASED ON HEAT LOSS CALCULATIONS FOR THIS SIZE OF ENCLOSURE AND EQUIPMENT.
- 28. 2P-15A CIRCUIT BREAKER FOR AIR CONDITIONING UNIT.
- 29. THERMAL MAGNETIC MOTOR PROTECTION CIRCUIT BREAKERS WITH LOCKOUT/TAGOUT. TMAX—X OR EQUAL PER MANUFACTURER SPECIFICATION.
- 30. LINE REACTORS, TYPICAL PER MANUFACTURER RECOMMENDATION.
- 31. ENCLOSURE LED PANEL LIGHTING.
- 32. EARTH GROUND TERMINAL BLOCK.
- 33. OPEN AREA FOR HEATER PER MANUFACTURER RECOMMENDATION.
- 34. LOAD REACTORS, TYPICAL PER MANUFACTURER RECOMMENDATION.
- 35. GROUND BLOCK.
- 36. MAIN 120VAC 15A POWER CIRCUIT BREAKER.
- 37. POWER FAIL RELAY. RELAY TO REPORT TO SCADA UPON LOSS OF POWER.
- 38. PHOENIX CONTACT PLUGTRAB SURGE PROTECTION DEVICE.

- 39. 5A REDUNDANT 24VDC POWER SUPPLY.
- 40. POWER SUPPLY REDUNDANCY MODULE.
- 41. UPS BYPASS CONTACTOR.
- 42. ETHERNET SWITCH.
- 43. COMPACTLOGIX L24ER WITH EMBEDDED IO.
- 44. COMPACTLOGIX MIX ANALOG INPUT MODULE.
- 45. DIGITAL INPUT FIELD TERMINAL BLOCKS.
- 46. 1000VA UPS. DUAL CONVERSION TYPE.
- 47. ANALOG INPUT FIELD TERMINAL BLOCKS.
- 48. 100W PANEL HEATER WITH INTEGRAL THERMOSTAT. ALLOW PROPER SPACING PER MANUFACTURER REQUIREMENTS. IF AC UNIT HAS HEATER, PANEL HEATER IS NOT REQUIRED.
- 49. DIGITAL OUTPUT ISOLATION RELAYS.
- 50. 3A POWER SUPPLY CIRCUIT BREAKERS.
- 51. HMI MAPLESYSTEMS CMT3072XHT.
- 52. 120V BUS TERMINAL BLOCKS.
- 53. 24VDC BUS TERMINAL BLOCKS.



LIFT STATION PUMP CONTROL PANEL LAYOUT DETAILS

SCALE: NONE

SIMS-DURKIN ASSOCIATES
ENGINEERING COMPANY
5755 WEST 74TH STREET
INDIANAPOLIS, INDIANA 46278
PHONE: 317-209-4035
FAX: 317-222-4120
WEB: WWW.SIMS-DURKIN.COM
SDA PROJECT NUMBER: 2022141

RQ/W
INTENTIONAL INNOVATION

WHEATLAND WASTEWATER SYSTEM
IMPROVEMENTS
VISION I - WASTEWATER TREATMEN

# Revision Date


Project #: 21-400-194-1

Designed By: WK/DD/JR

Drawn By: CG


Checked By: WRK/JWS

Date: 01/06/2023




LIFT STATION PUMP
CONTROL PANEL
LAYOUT DETAILS

F306



FROM TRANSFORMER



SIMS-DURKIN ASSOCIATES
ENGINEERING COMPANY
5755 WEST 74TH STREET
INDIANAPOLIS, INDIANA 46278
PHONE: 317-209-4035
FAX: 317-222-4120
WEB: WWW.SIMS-DURKIN.COM

SDA PROJECT NUMBER: 2022141

RQ/W
INTENTIONAL INNOVATION

## WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS VISTON 1 - WASTEWATER TREATMEN

# Revision Date


Project #: 21-400-194-1

Designed By: WK/DD/JR

Drawn By: CG

Checked By: WRK/JWS

Date: 01/06/2023



LIFT STATION PUMP CONTROL PANEL WIRING DETAILS F207

LIFT STATION PUMP CONTROL PANEL LAYOUT DETAILS CONT

NOTE:

THE CONTRACTOR/PANEL FABRICATOR SHALL BE RESPONSIBLE FOR THE FINAL SELECTION OF COMPONENTS, LAYOUT, FABRICATION, WRING AND PROGRAMMING; ALL SUBJECT TO SHOP DRAWING REVIEW. THESE DETAILS ARE INTENDED TO INDICATE SCOPE OF WORK, QUALITY REQUIREMENTS, AND EXPECTATIONS.

SIMS-DURKIN ASSOCIATES
ENGINEERING COMPANY
5755 WEST 74TH STREET
INDIANAPOLIS, INDIANA 46278
PHONE: 317-209-4035
FAX: 317-222-4120
WEB: WWW.SIMS-DURKIN.COM
SDA PROJECT NUMBER: 2022141

RQ/W
INTENTIONAL INNOVATION

WHEATLAND WASTEWATER SYSTEM
IMPROVEMENTS
DIVISION I - WASTEWATER TREATMEN
PLANT AND REGIONAL LIFT STATION

CONSTRUCTION SET

# Revision Date


Project #: 21-400-194-1

Designed By: WK/DD/JR

Drawn By: CG

Checked By: WRK/JWS

Date: 01/06/2023



LIFT STATION PUMP CONTROL PANEL WIRING

**DETAILS CONT** 

LIFT STATION PLC WIRING DETAILS



# WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS IVISION I - WASTEWATER TREATMEN PLANT AND REGIONAL LIFT STATION

# Revision Date

Project #: 21-400-194-1

Designed By: WK/DD/JR

Drawn By: CG

Checked By: WRK/JWS


Date: 01/06/2023



LIFT STATION PUMP CONTROL PANEL WIRING DETAILS CONT


INDIANAPOLIS, INDIANA 46278 PHONE: 317-209-4035 FAX: 317-222-4120


WEB: WWW.SIMS-DURKIN.COM SDA PROJECT NUMBER: 2022141



ELECTRICAL KEYED NOTES:

- 1. SLUDGE PUMP. SEE E303.
- 2. SUBMERSIBLE SLUDGE PUMP CONTROL PANEL FURNISHED BY AEROMOD INSTALLED BY ELECTRICAL CONTRACTOR. SEE MANUFACTURERS DETAILS. INSITE SENSOR PROBE CABLE WILL BE 33 LF LONG AND CANNOT BE CUT OR SPLICED. THIS CABLE WILL NEED TO BE CONNECTED TO THE BARRIER JUNCTION BOX AS PER NOTE [7]. THE E.C. WILL NEED TO PROVIDE CABLE FROM THE BARRIER JUNCTION BOX TO THE PROBE ANALYZER/DO MONITOR (ITEM [5]).
- 3. SLUDGE PUMP 3 PHASE POWER. SEE E303.
- 4. SLUDGE PUMP CONTROL/MONITORING WIRE TO CP-BSB CONTROL PANEL. 12-#14 CU, 1" C. (RUN STATUS, FAIL STATUS, ON/OFF CALL, SEAL FAIL, OVERTEMP AND SPARE).
- 5. DO MONITOR INSITE MODEL MPA-48. MOUNT TO TOP RAILING USING INSITE MOUNTING KIT.
- 6. DO PROBE INSITE MODEL 12 DO.
- 7. BARRIER JUNCTION BOX INSITE MODEL SJB—1 FOR EACH PROBE. MOUNT TO RAILING NEAR DO MONITOR. CONNECTION TO SENSOR CABLE REQUIRES NEMA 4X, CL1, DIV 2, GR A,B,C,D APPROVED SEALED FITTING.
- 8. MANUFACTURER CABLE IN 3/4" C. DO NOT CUT OR SPICE. ORDER FOR APPROPRIATE DISTANCE. MAX 200'.
- 9. 2-#16 TSP IN 3/4" C.
- 10. ULTRASONIC FLOW SENSOR FOR EFFLUENT FLOW RATE THROUGH WEIR. FLO—CORP CHANNELFLOW UOCM. NO EQUALS.
- 11. ULTRASONIC FLOW TRANSMITTER/CONTROLLER. FLO-CORP FIGICOM 200 MODEL #: UCOM-1-DC2-A-E-N-N4, NO EQUALS.
- 12. ULTRASONIC FLOW SENSOR MANUFACTURER CABLE. 3/4" C.
- 13. UV SYSTEM CONTROLLER. TROJAN UV 3000B WITH FLOW PACING.
- 14. STAINLESS STEEL SPLITTER WITH UV SYSTEM MODULE WEATHERPROOF OUTLETS. PROVIDE PER MANUFACTURER REQUIREMENTS.
- 15. MANUFACTURER LAMP MODULE CABLES.
- 16. TROJAN UV 3200K PTP UV SYSTEM.
- 17. 3"X3" WELDED ALUMINUM EQUIPMENT RACK. SAME DETAILS AS LIFT STATION. LENGTH AS REQUIRED.
- 18. 12" X 12" JUNCTION BOX FOR 120V CONTROL POWER OF EQUIPMENT TO "P-1". SEE PANEL SCHEDULE.
- 19. 12" X 12" JUNCTION BOX FOR CONTROL/MONITORING SIGNAL WIRES.
- 20. POWER WIRES FOR EQUIPMENT, SEE P-1 PANEL SCHEDULE. FLOW METER ELECTRONICS, DISSOLVED OXYGEN SENSOR ELECTRONICS, PDR OUTLETS FOR UV, HEAT TRACE PLUS SPARES: 12 #12 CU, 2 #12 CU GND, 1-1/4" C.
- 21. SIGNAL WIRES: 4-#16 TSP, 6-#14 CU, 1-1/4" C.
- 22. PULL BOX POWER WIRE.
- 23. PULL BOX ANALOG TYPE SIGNAL CABLES.
- 24. MAINTAIN 3' SEPARATION BETWEEN ANALOG SIGNAL CABLES AND AC POWER WIRING.
- 25. 2-#12 CU, 1-#12 CU GND, 1" C.
- 26. BALLARD, SEE DETAILS.





SIMS-DURKIN ASSOCIATES ENGINEERING COMPANY

5755 WEST 74TH STREET INDIANAPOLIS, INDIANA 46278 PHONE: 317-209-4035 FAX: 317-222-4120 WEB: WWW.SIMS-DURKIN.COM SDA PROJECT NUMBER: 2022141

RQ/W
INTENTIONAL INNOVATION

### WASTEWATER SYSTEM IMPROVEMENTS ISION I - WASTEWATER TREATMEN

# Revision Date

Project #: 21-400-194-1

Designed By: WK/DD/JR


Drawn By: CG

Checked By: WRK/JWS

Date: 01/06/2023



UV / AEROMOD SYSTEM PLAN



RQ/W
INTENTIONAL INNOVATION

# WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS

# Revision Date


Project #: 21-400-194-1

Designed By: WK/DD/JR

Drawn By: CG

Checked By: WRK/JWS

Date: 01/06/2023



**I&C ONE-LINE** 


SIMS-DURKIN ASSOCIATES ENGINEERING COMPANY

5755 WEST 74TH STREET INDIANAPOLIS, INDIANA 46278

PHONE: 317-209-4035 FAX: 317-222-4120 WEB: WWW.SIMS-DURKIN.COM SDA PROJECT NUMBER: 2022141 E311


**I&C ONE-LINE DIAGRAM** 


NOT TO SCALE




NOT TO SCALE


NOT TO SCALE







LIGHTING CONTROL PANEL LAYOUT NOT TO SCALE



LIGHTING CONTROL PANEL WIRING DIAGRAM

NOT TO SCALE



5755 WEST 74TH STREET INDIANAPOLIS, INDIANA 46278 PHONE: 317-209-4035 F A X : 3 1 7 - 2 2 2 - 4 1 2 0 WEB: WWW.SIMS-DURKIN.COM SDA PROJECT NUMBER: 2022141


INTENTIONAL INNOVATION

SYSTEM TER WHEATL

# Revision

Project #: 21-400-194-1 Designed By: WK/DD/JR Drawn By: CG Checked By: WRK/JWS

Date: 01/06/2023



**GENERAL ELECTRICAL DETAILS** 

GENERAL ELECTRICAL DETAILS

NOT TO SCALE

PHOTOMETRIC PLAN DESIGNED BY ESL-SPECTRUM WWW.ESL-SPECTRUM.COM

PHONE: 317.951.2300

Luminaire S	Schedule							
Project: 202	220282-HG V	VHEATLAND	) WWTP - SITE LIGHTING R	1 1-5-23				
Symbol	Qty	Label	Arrangement	Lum. Watts	Lum. Lumens	LLF	Manufacturer	Description
-	1	F-1	Single	52.7	7032	0.850	BEACON	VP-F-1-132L-55-4K7-W-UNV
-	4	P-1	Single	241.7	23985	0.850	BEACON	(1) VP-ST-2-72L-240-4K7-4W-UNV
8	5	P-2	2 @ 90 degrees	241.7 Avg/Min N.A.	<b>23985</b>	0.850	BEACON	(2) VP-ST-2-72L-240-4K7-4W-UNV
	3	P-4	4 @ 90 Degrees	241.7	<sup>1</sup> 23985	0.850	BEACON	(4) VP-ST-2-72L-240-4K7-4W-UNV

CALCULATIONS ARE MAINTAINED HORIZONTAL ILLUMINANCE FIGURES IN FOOT-CANDLES POINTS SHOWN ARE AT GRADE FIXTURE MOUNTING HEIGHTS ARE SPECIFIED NEXT TO FIXTURES AS "MH" POLES ARE 20'-0" ON A 3'-0" BASE

PSEUDO COLOR ILLUMINANCE LEVELS

SLUDGE

Calculation Summary						
Project: 20220282-HG WHEATLA	AND WWTP - SITE LIGHTING R1 1-5-	-23				
Label	CalcType	Units	Avg	Max	Min	
PERIMETER @ GRADE	Illuminance	Fc	0.54	19.5	0.0	
SITE @ GRADE	Illuminance	Fc	6.05	16.4	0.7	

ESL-Spectrum's services are for estimation purposes only, and are not warranties.

Final design and illumination levels must be determined and specified by an electrical engineer.

Field results may differ from computer predictions because of many uncontrollable factors and adverse test conditions such as:

line voltage variations, lamp performance, product manufacturing tolerances, jobsite conditions, and other unrecoverable light-loss factors.

THE FIXTURE TYPE(S) AND LAMPING(S) SPECIFIED ON THIS LAYOUT MUST BE USED IN ORDER TO MEET THE EXACT CRITERIA AND PERFORMANCE DATA SHOWN. IES RECOMMENDED ILLUMINANCE TARGETS USED WHERE APPLICABLE.

APPROXIMATED SITE AREA Area = 63670 Sq.ft



LIGHTING DETAILS

SCALE: NONE





### ATLAND WASTEWATER SYSTEM IMPROVEMENTS

WHE/

#	Revision	Date


Designed By: WK/DD/JR

Drawn By: CG

Checked By: WRK/JWS

Project #: 21-400-194-1

Date: 01/06/2023



LIGHTING DETAILS


E313

: 1/6/23 1:186.9116 EDIT DATE: 1/6/23 - 9:42 AM EDITED BY: CORY GRAVES DRAWING FILE: \\TRUENAS\OPER

SITE LIGHTING - PLAN VIEW Scale: 1 inch= 20 Ft.


VINT DATE: 1/6/23





PIPE W/ 2" INSULATION

N.T.S.



HEAT TRACE ONE-LINE

N.T.S.

### **GENERAL ELECTRICAL NOTES:**

- A. ALL EQUIPMENT, WIRING, AND CONDUIT ON THIS PLAN FURNISHED AND INSTALLED BY CONTRACTOR UNLESS OTHERWISE NOTED. VERIFY ALL REQUIREMENTS WITH APPROVED SHOP DRAWINGS BEFORE ROUGH—IN.
- B. ALL CONTROL PANELS SHALL HAVE LOCKOUT/TAGOUT AVAILABLE.
- C. OPEN TANK AREAS ARE CLASSIFIED CLASS 1 DIVISION 2: ALL WIRING SHALL COMPLY.
- D. RIGID ALUMINUM GALVANIZED RIGID STEEL FOR ALL CONDUIT ABOVE GRADE. RIGID GALVANIZED STEEL FOR ALL CONDUITS BELOW DRIVING SURFACES AND ENTRANCE TO CLASSIFIED AREAS. SCHEDULE 40 PVC FOR ALL OTHER UNDERGROUND CONDUIT.
- E. CONDUIT ENTRY INTO ALL ENCLOSURES SHALL BE THRU BOTTOM OF ENCLOSURE.

### ELECTRICAL KEYED NOTES:

- 1. PANEL P-1. SEE SHEET E600.
- 2. AMBIENT TEMPERATURE SENSOR.
- 3. HEAT TRACE THERMOSTAT SET FOR 45 DEGREES.
- 4. HEAT TRACE POWER CONNECTION KIT. RAYCHEM JBS-A00-A OR EQUAL.
- 5. HEAT TRACE TERMINATION.
- 6. HEAT TRACE TAPE 120V, 8W/FT. RAYCHEM 8BTV2-CT OR EQUAL.
- 7. CONTRACTOR SHALL LOOP HEAT TRACE AT FLANGES.
- 8. FLEXIGLASS CLOSED CELL FOAM INSULATION OR EQUAL COVERED BY ALUMINUM JACKETING. SEAL JACKETING ALONG ALL ENDS, EDGES, AND PENETRATIONS.
- 9. 4" INFLUENT PIPE.
- 10. 120V FROM THERMOSTAT.
- 11. 2-#12 CU IN 1-1/2" C

RQ/W

### INTENTIONAL INNOVATION WENT

CONSTRUCTION SET

WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS
DIVISION I - WASTEWATER TREATMEN

# Revision Date

Project #: 21-400-194-1

Designed By: WK/DD/JR

Drawn By: CG

Checked By: WRK/JWS

Date: 01/06/2023



**HEAT TRACE** 

	Location: ELECTRICAL Supplied From: Mounting: Surface Enclosure Type: Type 1	. 102	Voltage:208Y/120BrPhase:3A.I.C. RWire:4MainGround:Equipment Ground BusMain R										L	
General I	Panel Comments:													
Circuit Number	Circuit Description	Trip	Poles		<b>A</b>	E	3	(	C	Poles	Trip	Circuit Desc	cription	Circu Numb
1	Receptacle BLOWERS 103	20 A	1	1.1	0.5					1		Receptacle OFFICE 101		2
3	Receptacle OFFICE 101	20 A	1			0.5	0.5			1	20 A	Receptacle OFFICE 101		4
5	Receptacle RR 104	20 A	1	0.4	0.0			0.2	0.4	1	20 A	Receptacle ELECTRICAL 102		6
7	Receptacle STORAGE 105	20 A	1	0.4	2.2	0.0	0.0			2	30 A	UH-1		8
9	UH-1	30 A	2			2.2	2.2	2.2	2.2					10 12
13				2.2	2.2			2.2	2.2	2	30 A	UH-1		14
15	UH-1	30 A	2	2.2	2.2	2.2	2.2							16
17	EWH-1	20 A	1			<i>L.L</i>	2.2	1	2.2	2	30 A	UH-1		18
19	EWH-1	20 A	1	1	0.8			<u> </u>		_				20
21				•	0.0	2	0.8			2	15 A	EWH-2		22
23	ACCU-2	30 A	2					2	0.6		45.4	100114		24
25	EF-1	20 A	1	0.5	0.6					2	15 A	ACCU-1		26
27	UV Controller	25 A	1			0.5	0.5			1	20 A	Ultrasonic Flow Meter		28
29	UV PDR	15 A	1					0.5	0.5	1	15 A	UV PDR		30
31	DO Analyzer	20 A	1	0.5	1					1	20 A	EWH-1		32
33	ERV-1	20 A	1			0.1	3			2	40 A	EWH-1		34
35	SPARE	20 A	1					0	3					36
37	SPARE	20 A	1	0	0.2					1		Honeywell Chart Recorder		38
39	SPARE	20 A	1			0	0.5		0.7	1		SQC Panel	00	40
41	SPARE	20 A	1	_	0.4			0	0.7	1		Lighting Room 101, 104, 105, 1	03	42
43 45	SPARE SPARE	20 A 20 A	1	0	0.1	0	0.1			1		Lighting ELECTRICAL 102 Lighting		44 46
47	SPARE	20 A	1			U	0.1	0	0	1		SPARE		48
49	SPARE	20 A	1	0	0			-	0	1		SPARE		50
51	SPARE	20 A	1	U	U	0	0			1		SPARE		52
53	SPARE	20 A	1					0	0	1		SPARE		54
55	SPARE	20 A	1	0	0			_		1		SPARE		56
57	SPARE	20 A	1			0	0			1		SPARE		58
59	SPARE	20 A	1					0	0	1		SPARE		60
			l Load:		kVA	Load S	kVA Sumamr	y:	kVA					
	ssification		ected Lo	oad	De	mand Fa		Es		Demand		Panel	Totals	
_ighting	.1		958 VA			100.00%			958			T-4-10 1 1	40020 \ / 4	
Mechanic Meter	31		600 VA			70.00%			2520			Total Conn. Load:		
Motor Receptac	Δ		1700 VA 780 VA			100.00%		-	34700 6780			Total Est. Demand: Total Conn. Current:		
чесеріас	<del>e</del>	0	700 VA			100.007	0		0700	VA		Total Est. Demand Current:		
								+						

LIGHT FIXTURE SCHEDULE - INTERIOR LIGHTING								
FIXTURE TYPE	FIXTURE NAME	DESCRIPTION	VOLTAGE	MAXIMUM ALLOWED WATTAGE	LAMP TYPE	COLOR TEMPERATURE	DELIVERED LUMENS	ACCEPTABLE MANUFACTURERS
F4	LED STRIP FIXTURE	4" WIDE X 4' LONG, SURFACE MOUNT OR SUSPENDED, FROSTED DROP LENS, WIDE DISTRIBUTION, DAMP LOCATION LISTED.	120 V	41 W	LED	3500K	5000	LITHONIA Z1LD, METALUX SNLED, COLUMBIA MPS
FEM		FLAME RETARDANT THERMOPLASTIC HOUSING, SELF DIAGNOSTICS AVAILABLE, UL 924 LISTED EMERGENCY BATTERY WITH A MINIMUM OF 90 MINUTES OF RUNTIME.	120 V	3 W	LED			HUBBELL – PROGRESS LIGHTING – PE2EU, COOPER - SURE-LITES – AP2SQLED, LITHONIA LIGHTING – EU2C
FX	EXIT LIGHT	DIE CAST ALUMINUM EXIT, WHITE HOUSING, DIRECTIONAL ARROWS AND NUMBER OF FACES AS PER DRAWINGS, UNIVERSAL CEILING OR WALL MOUNT, STENCIL FACE, RED LETTERS, UL LISTED, MEETS UL924, NFPA 101, NEC, AND OSHA ILLUMINATION STANDARDS, FIVE YEAR WARRANTY.	120 V	4 W	LED			DUAL-LITE SE, LITHONIA LE, SURE-LITES CX

LIGHT FIXTURE SCHEDULE - EXTERIOR LIGHTING								
FIXTURE TYPE	FIXTURE NAME	DESCRIPTION	VOLTAGE	MAXIMUM ALLOWED WATTAGE	LAMP TYPE	COLOR TEMPERATURE	DELIVERED LUMENS	ACCEPTABLE MANUFACTURERS
EX1	EXTERIOR WALL PACK	18"W X 9"D X 9"T, DIE-CAST ALUMINUM HOUSING, TYPE IV DISTRIBUTION, WET LOCATION LISTED, PROVIDE WITH INTEGRAL 90 MINUTE EMERGENCY BATTERY. FINISH COLOR TO BE SELECTED BY ARCHITECT	120 V	29 W	LED	4000K	3053	LITHONIA WSQ, OR APPROVED EQUAL

### GENERAL NOTES - LIGHT FIXTURES:

- A. ALL FIXTURES SHALL BE CERTIFIED BY A NATIONALLY RECOGNIZED TESTING LABORATORY (NRTL) TO US SAFETY STANDARDS-UL, ETL, CSA.
- B. ALL FIXTURES SHALL BE PAINTED AFTER FABRICATION.
- C. THIS SCHEDULE DOES NOT NECESSARILY INDICATE TYPE OF TRIM REQUIRED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING TRIM TYPE WITH TYPE OF CEILING SYSTEM AT EACH INSTALLATION LOCATION. REFER TO THE ARCHITECTURAL REFLECTED CEILING PLANS AND PROVIDE ACCORDINGLY.
- D. ALL FIXTURES LOCATED IN AN EXTERIOR AND/OR UNCONDITIONED ENVIRONMENT SHALL BE PROVIDED WITH HOUSINGS, LAMPS, AND/OR DRIVERS SUITABLE FOR THIS ENVIRONMENT.
- E. ALL LED FIXTURES SHALL BE LM-79/LM-80 TESTED AND COMPLIANT.
- F. ALL LED FIXTURES SHALL BE PROVIDED WITH A MINIMUM OF FIVE-YEAR WARRANTY. REFER TO SPECIFICATION SECTION 265100 FOR ADDITIONAL REQUIREMENTS.
- G. LUMENS LEVELS LISTED IN THIS SCHEDULE ARE INTENDED TO BE DELIVERED LUMENS. SUBMITTALS ARE TO INCLUDE THE DELIVERED LUMEN TOTAL OF EACH FIXTURE AND MUST MEET THE LEVEL INDICATED FOR EACH FIXTURE TYPE.
- H. WATTAGE LISTED IN THIS SCHEDULE ARE TO BE MAXIMUM ALLOWABLE WATTAGE FOR EACH FIXTURE. SUBMITTED LIGHT FIXTURES MUST NOT EXCEED LISTED MAXIMUM WATTAGE TO ACHIEVE SPECIFIED DELIVERED LUMENS.

SYSTEM WASTEWATER AND WHEATL

#	Revision	Date

Project #: 21-400-194-1

Designed By: DJ


Drawn By: DJ

Checked By: DB

Date: 12/28/22

No. 12200401

NOT FOR CONSTRUCTION




ELECTRICAL SCHEDULES

E600

В

Α



RQAW

WHEATLAND WASTEWATER SYSTEM IMPROVEMENTS

STATION

# Revision Date

Project #: 21-400-194-1

Designed By: DJ

Drawn By: DJ

Checked By: DB

Date: 12/28/22

No. 12200401

STATE OF

WOJANA

SON AL

ENTITY

ENTITY

SON AL

ENTITY

SON AL

ENTITY

SON AL

ENTITY

SON AL

NOT FOR CONSTRUCTION

N

ELECTRICAL DETAILS