

# CONSTRUCTION PLANS FOR: **RILEY VILLAGE** **SANITARY SEWER** GREENFIELD, HANCOCK COUNTY, INDIANA

SHEET INDEX :	
SHEET #	SHEET NAME
T001	COVER SHEET
G001	GENERAL NOTES & SYMBOLS
C200 - C206	SANITARY SEWER PLAN & PROFILES
C500	EROSION CONTROL PLAN
C501	EROSION CONTROL DETAILS
C502	STORMWATER POLLUTION PREVENTION PLAN
C600 - C601	CONSTRUCTION DETAILS

REVISIONS :		
REVISION #	REVISION DESCRIPTION	DATE

**FLOOD NOTE:**  
THE ACCURACY OF ANY FLOOD HAZARD DATA SHOWN ON THESE PLANS IS SUBJECT TO MAP SCALE UNCERTAINTY AND TO ANY OTHER UNCERTAINTY IN LOCATION OR ELEVATION ON THE REFERENCED FLOOD INSURANCE RATE MAP. THE WITHIN DESCRIBED TRACT OF LAND LIES WITHIN FLOOD HAZARD ZONE X AS SAID TRACT PLOTS BY SCALE ON COMMUNITY PANEL NUMBER 18059C0129D DATED 12/04/2007 FOR THE FLOOD INSURANCE RATE MAPS FOR HANCOCK COUNTY, INDIANA.

**DISCLAIMER:**  
EXISTING CONDITIONS/SURVEY INFORMATION PROVIDED BY COOR CONSULTING. RQAW IS NOT RESPONSIBLE FOR THE ACCURACY OF THE EXISTING CONDITION/SURVEY INFORMATION PROVIDED. CONTRACTOR TO FIELD VERIFY LOCATION AND SIZES OF ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION AND CONTACT ENGINEER AND OWNER IF DISCREPANCIES OCCUR.

## PLANS PREPARED FOR:

NINESTAR CONNECT  
2243 E MAIN STREET  
GREENFIELD, INDIANA 46140  
TELEPHONE: (317) 323-2035  
CONTACT PERSON: ALAN MARTIN, MANAGER  
OF WATER & WASTEWATER UTILITIES  
AMARTIN@NINESTARCONNECT.COM

## OPERATING AUTHORITIES

**SANITARY SEWER AUTHORITY**  
NINESTAR CONNECT  
2243 E MAIN ST.  
GREENFIELD, IN 46140  
TELEPHONE: (317) 694-7299  
ALAN MARTIN  
MANAGER OF WATER &  
WASTEWATER UTILITES

**CABLE UTILITY**  
COMCAST CABLE  
TELEPHONE: (317) 275-6443  
WILL MORRIS

**ELECTRICAL/POWER AUTHORITY**  
NINESTAR CONNECT  
2243 E. MAIN ST.  
GREENFIELD, IN 46140  
TELEPHONE: (317) 477-2200  
ERIC MEYER

**STORM SEWER AUTHORITY**  
CITY OF GREENFIELD  
10 S. STATE ST.  
GREENFIELD, IN 46140  
TELEPHONE: (317) 325-1327  
DAN MILLER  
STORMWATER UTILITY MANAGER


**WATER AUTHORITY**  
NINESTAR CONNECT  
2243 E MAIN ST.  
GREENFIELD, IN 46140  
TELEPHONE: (317) 326-3131  
CONTACT PERSON  
TITLE

**COMMUNICATIONS UTILITY**  
NINESTAR CONNECT  
2243 E. MAIN ST.  
GREENFIELD, IN 46140  
TELEPHONE: (317) 326-3141  
GEORGE PLISINSKI



## SITE VICINITY MAP

NOT TO SCALE



## SITE LOCATION MAP

NOT TO SCALE

CALL 2 WORKING DAYS BEFORE YOU DIG

**1-800-382-5544**

CALL TOLL FREE

PER INDIANA STATE LAW IC8-1-26.  
IT IS AGAINST THE LAW TO EXCAVATE WITHOUT  
NOTIFYING THE UNDERGROUND LOCATION SERVICE  
TWO (2) WORKING DAYS BEFORE COMMENCING  
WORK.

BIDDING SET  
**RILEY VILLAGE SANITARY SEWER**

2243 E MAIN STREET  
GREENFIELD, IN 46140

#	Revision	Date

Project #: 20-400-286-2

Designed By: TAC

Drawn By: JLB

Checked By: ALC

Date: 02/02/2023



*Aaron Cron*

COVER SHEET


**T001**



GENERAL NOTES

- ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS FOR THIS PROJECT. ADDITIONS, DELETIONS, AND/OR REVISIONS SHALL NOT BE MADE WITHOUT PRIOR APPROVAL BY THE ENGINEER. KEEP AND MAINTAIN IN GOOD CONDITION, A COMPLETE SET OF THE CONTRACT DOCUMENTS ON THE JOB SITE AT ALL TIMES.
- ALL WORK SHALL BE IN ACCORDANCE WITH THE NINESTAR CONNECT RULES AND REGULATIONS. COMPLY WITH LOCAL, STATE AND FEDERAL CODES, ORDINANCES, RULES, REGULATIONS, ORDERS, AND OTHER LEGAL REQUIREMENTS OF AUTHORITIES HAVING JURISDICTION.
- IN THE EVENT THAT THE CONTRACTOR DISCOVERS A DISCREPANCY IN THE CONTRACT DOCUMENTS OR A POTENTIAL UTILITY CONFLICT, NOTIFY THE ENGINEER IMMEDIATELY FOR CLARIFICATION, PRIOR TO PROCEEDING WITH CONSTRUCTION OF THE PORTION OF THE WORK IN QUESTION. FIELD LOCATE ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION. VERTICAL AND HORIZONTAL LOCATIONS TO BE CONFIRMED. ANY NECESSARY PIPE MODIFICATIONS SHALL BE MADE BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.
- CONSTRUCTION SHALL NOT COMMENCE UNTIL ALL NECESSARY LOCAL PERMITS HAVE BEEN OBTAINED.
- ALL RIGHT-OF-WAY AND PROPERTY LINES AND EASEMENTS SHOWN ON THE PLANS ARE APPARENT AND WERE DETERMINED BASED UPON AVAILABLE INFORMATION. VERIFY ALL RIGHT-OF-WAY AND PROPERTY LINES. STAKE ALL RIGHT-OF-WAY, PROPERTY, AND EASEMENT LINES THROUGHOUT THE DURATION OF CONSTRUCTION.
- CONSTRUCTION STAKING SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. PROPERTY LINES AND RIGHT-OF-WAY SHALL BE STAKED FOR THE DURATION OF CONSTRUCTION ACTIVITIES.
- PROTECT ALL EXISTING UTILITIES FROM DAMAGE, IN A MANNER APPROVED BY THE UTILITY COMPANIES AND THE ENGINEER. COORDINATE WITH UTILITY COMPANIES, AS NECESSARY, TO COMPLETE THE WORK. PROTECT BENCH MARKS, SURVEY CONTROL POINTS, AND EXISTING STRUCTURES FROM NECESSARY DAMAGE OR DISPLACEMENT.
- PROVIDE ALL AUTOMOBILE AND PEDESTRIAN TRAFFIC CONTROL DEVICES REQUIRED BY FEDERAL, STATE, OR LOCAL AGENCIES. THE AMOUNT, LOCATION AND SIZE SHALL BE AS REQUIRED IN ACCORDANCE WITH THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.
- DURING CONSTRUCTION, IT MAY BE NECESSARY TO TRIM OR REMOVE A TREE WITHIN THE RIGHT-OF-WAY OR AN EASEMENT. NOTIFY THE ENGINEER, OWNER AND ANY AFFECTED PROPERTY OWNER PRIOR TO ANY REQUIRED TREE REMOVAL. TREE TRIMMING AS REQUIRED WITHIN THE RIGHT-OF-WAY OR EASEMENT SHALL BE MINIMIZED. NO ADDITIONAL COMPENSATION WILL BE PROVIDED FOR TREE REMOVAL OR TRIMMING.
- ALL DISTURBED AREAS INCLUDING, BUT NOT LIMITED TO, STREETS, DRIVES, WALKS, LAWNS, FENCES, RETAINING WALLS, ETC. SHALL BE RESTORED TO ORIGINAL OR BETTER CONDITION.
- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO REMOVE ALL MUD, DIRT, GRAVEL AND ANY OTHER MATERIALS TRACKED ONTO ANY PUBLIC OR PRIVATE STREETS, PARKING LOTS, OR WALKS. THIS MATERIAL REMOVAL OR SWEEPING OF THE STREETS SHALL BE DONE AS FREQUENTLY AS NECESSARY TO MAINTAIN AREAS REASONABLY CLEAN. AIRBORNE DUST SHALL BE KEPT TO A MINIMUM BY USING WATER OR OTHER METHODS AS NECESSARY.
- PROVIDE TEMPORARY GRASS SEED WITHIN 7-DAYS OF ALL EARTH DISTURBING ACTIVITIES.
- PROVIDE AND MAINTAIN ALL NECESSARY STRAW BALES, FILTER FENCE, INLET PROTECTION, ETC. IN EXISTING AND PROPOSED DITCHES, CULVERTS, STORM PIPES & DRAINAGE STRUCTURES TO PREVENT DAMAGE. BIO-DEGRADABLE EROSION CONTROL DEVICES SHOULD BE PLACED IN ALL DISTURBED DRAINAGE DITCHES WITH DEPTHS GREATER THAN 12".
- REGRADE AREAS AS NECESSARY WITHIN THE CONSTRUCTION LIMITS TO ALLOW PROPER DRAINAGE TO EXISTING STORM SEWER STRUCTURES.
- MAINTAIN 10'-0" HORIZONTAL AND 1'-6" VERTICAL SEPARATION FROM SEWER AND WATER MAINS UNLESS SPECIFICALLY NOTED IN THE PLANS.
- PROVIDE FILL AROUND PROPOSED AND EXISTING PIPING AT ALL OPEN-CUT UTILITY CROSSINGS TO ADEQUATELY SUPPORT AND PROTECT EACH CONDUIT.
- PRESERVE EXISTING RIGHT-OF-WAY MARKERS. IF R/W MARKERS ARE DISTURBED, RESET MARKERS AT NO ADDITIONAL COST TO THE OWNER.
- CALL LOCAL UTILITY LINE INFORMATION SERVICE NOT LESS THAN THREE WORKING DAYS BEFORE PERFORMING WORK. REQUEST UNDERGROUND UTILITIES TO BE LOCATED AND MARKED WITHIN AND SURROUNDING CONSTRUCTION AREAS. IDENTIFY REQUIRED LINES, LEVELS, CONTOURS, AND DATUM LOCATIONS.
- ESTABLISH TEMPORARY TRAFFIC CONTROL AND DETOURS WHEN TRENCHING IS PERFORMED IN PUBLIC RIGHT-OF-WAY. RELOCATE CONTROLS AND REROUTE TRAFFIC AS REQUIRED DURING PROGRESS OF WORK.
- DO NOT LEAVE MORE THAN 50 FEET OF TRENCH OPEN AT END OF WORKING DAY, PROTECT OPEN TRENCH TO PREVENT DANGER TO THE PUBLIC.
- STOCKPILE EXCAVATED AND FILL MATERIALS ON SITE AT LOCATIONS APPROVED BY OWNER, STOCKPILE IN SUFFICIENT QUANTITIES TO MEET PROJECT SCHEDULE AND REQUIREMENTS. SEPARATE DIFFERENT AGGREGATE MATERIALS WITH DIVIDERS OR STOCKPILE INDIVIDUALLY TO PREVENT MIXING. DIRECT SURFACE WATER AWAY FROM STOCKPILE SITE TO PREVENT EROSION OR DETERIORATION OF MATERIALS. STOCKPILE CLEANUP: REMOVE STOCKPILE, LEAVE AREA IN CLEAN AND NEAT CONDITION. GRADE SITE SURFACE TO PREVENT FREE STANDING SURFACE WATER.
- SOIL STOCKPILE SHALL BE LOCATED WITHIN THE TEMPORARY EASEMENTS OF THE PROJECT.
- FINAL CONTOURS: PERFORM FINISH GRADING AND BLEND INTO CONFORMATION WITH REMAINING NATURAL GROUND SURFACES. LEAVE ALL FINISHED GRADING SURFACES SMOOTH AND FIRM TO DRAIN. BRING FINISH GRADES TO ELEVATIONS WITHIN PLUS OR MINUS 0.10 FOOT OF EXISTING OR CONTOURS SHOWN.
- UTILIZE LOCATION OF CRAWL SPACES FOR SANITARY LATERAL INSTALLATION WHERE POSSIBLE.
- CONTRACTOR TO ENSURE SURFACE, LANDSCAPING, AND ALL OTHER HOMEOWNER FEATURES ARE RESTORED BACK TO EXISTING CONDITIONS.
- REFERENCE NINESTAR WATER & SANITARY SEWER RULES AND STANDARDS FOR ALL OTHER INFORMATION.
- CONTRACTOR TO ENSURE STRUCTURAL STABILITY OF BUILDING FOUNDATIONS DURING LATERAL REROUTING. PATCH WITH FULL DEPTH STRUCTURAL MORTAR.
- USE BYPASS PUMPING AS NEEDED TO ENSURE THAT SANITARY SERVICE IS NOT INTERRUPTED.
- FOLLOW MANUFACTURERS RECOMMENDATIONS AS WELL AS ALL APPLICABLE AWWA AND ASTM STANDARDS FOR ALL WORK DONE TO LINE EXISTING MANHOLES AND PIPES AS INDICATED.

PROPOSED LEGEND:




**BIDDING SET**  
**RILEY VILLAGE SANITARY SEWER**  
 2243 E MAIN STREET  
 GREENFIELD, IN 46140

#	Revision	Date

Project #: 20-400-286-2  
 Designed By: TAC  
 Drawn By: JLB  
 Checked By: ALC  
 Date: 02/02/2023



*Aaron Crow*



GENERAL NOTES & SYMBOLS

**G001**

PRINT DATE: 3/18/24  
 PLOT SCALE: 1:1  
 EDIT DATE: 2/1/23 - 2:58 PM  
 EDITED BY: MLOYD  
 DRAWING FILE: P:\20-400-286-2 RILEY VILLAGE SANITARY SEWER\5 ACAD\PLAN SHEETS & WORKING DRAWINGS\G001 - GENERAL NOTES & SYMBOLS.DWG




**RILEY VILLAGE SANITARY SEWER**

2243 E MAIN STREET  
GREENFIELD, IN 46140

BIDDING SET


MATCHLINE - STA. 7+50 - SHEET C201



**KEY NOTES**

- A** REPLACE DISTURBED ROAD WITH ASPHALT PAVEMENT. SEE DETAIL ON SHEET C601.
- B** EXISTING STORM SEWER. MAINTAIN SUFFICIENT WATER & SEWER SEPARATION. SEE DETAIL ON SHEET C601.
- C** EXISTING WATER MAIN. MAINTAIN SUFFICIENT WATER & SEWER SEPARATION. SEE DETAIL ON SHEET C601.
- D** EXISTING COMMUNICATIONS UTILITY
- E** EXISTING ELECTRIC UTILITY
- F** PROPOSED 6" SANITARY LATERAL, INSIDE RIGHT-OF-WAY. CONTRACTOR TO CAP FOR FUTURE CONNECTION
- G** REPLACE DEMOLISHED TREES IN KIND
- H** REMOVE TOP 5" OF MANHOLE AND BACKFILL. SEE DETAIL ON SHEET C602.
- I** GROUT AND ABANDON EXISTING SANITARY SEWER.
- J** LINE EXISTING MANHOLE.
- K** LINE EXISTING SANITARY SEWER FROM EX. MANHOLE TO TIE-IN AT SUGAR CREEK WWTP.
- L** CORE IN NEW SANITARY SEWER TO EXISTING MANHOLE. SEE DETAIL ON SHEET C602.
- M** CUT AND CAP EXISTING SANITARY SEWER. USE BYPASS PUMPING TO ALLOW FOR INSTALLATION OF PROPOSED SANITARY SEWER.
- N** USE INTERNAL DROP IN MANHOLE. SEE DETAIL ON SHEET C602.
- O** REPLACE EXISTING PIPE TO REPAIR SAG. MATCH EXISTING VERTICAL AND HORIZONTAL ALIGNMENT.

= GRANULAR BACKFILL




#	Revision	Date

Project #: 20-400-286-2  
Designed By: TAC  
Drawn By: JLB  
Checked By: ALC  
Date: 02/02/2023



*Maron L. Crow*



SANITARY SEWER  
PLAN & PROFILES

**C200**



**RILEY VILLAGE SANITARY SEWER**

2243 E MAIN STREET  
GREENFIELD, IN 46140

BIDDING SET

#	Revision	Date

Project #: 20-400-286-2

Designed By: TAC


Drawn By: JLB

Checked By: ALC

Date: 02/02/2023



*Aaron Crow*




**SANITARY SEWER  
PLAN & PROFILES**

**C201**

MATCHLINE - STA. 7+50 - SHEET C200


MATCHLINE - STA. 15+00 - SHEET C202



**KEY NOTES**

- A** REPLACE DISTURBED ROAD WITH ASPHALT PAVEMENT. SEE DETAIL ON SHEET C601.
- B** EXISTING STORM SEWER. MAINTAIN SUFFICIENT WATER & SEWER SEPARATION. SEE DETAIL ON SHEET C601.
- C** EXISTING WATER MAIN. MAINTAIN SUFFICIENT WATER & SEWER SEPARATION. SEE DETAIL ON SHEET C601.
- D** EXISTING COMMUNICATIONS UTILITY
- E** EXISTING ELECTRIC UTILITY
- F** PROPOSED 6" SANITARY LATERAL, INSIDE RIGHT-OF-WAY. CONTRACTOR TO CAP FOR FUTURE CONNECTION
- G** REPLACE DEMOLISHED TREES IN KIND
- H** REMOVE TOP 5" OF MANHOLE AND BACKFILL. SEE DETAIL ON SHEET C602.
- I** GROUT AND ABANDON EXISTING SANITARY SEWER.
- J** LINE EXISTING MANHOLE.
- K** LINE EXISTING SANITARY SEWER FROM EX. MANHOLE TO TIE-IN AT SUGAR CREEK WWTP.
- L** CORE IN NEW SANITARY SEWER TO EXISTING MANHOLE. SEE DETAIL ON SHEET C602.
- M** CUT AND CAP EXISTING SANITARY SEWER. USE BYPASS PUMPING TO ALLOW FOR INSTALLATION OF PROPOSED SANITARY SEWER.
- N** USE INTERNAL DROP IN MANHOLE. SEE DETAIL ON SHEET C602.
- O** REPLACE EXISTING PIPE TO REPAIR SAG. MATCH EXISTING VERTICAL AND HORIZONTAL ALIGNMENT.

= GRANULAR BACKFILL






**RILEY VILLAGE SANITARY SEWER**

BIDDING SET

2243 E MAIN STREET  
GREENFIELD, IN 46140

MATCHLINE - STA. 15+00 - SHEET C201

MATCHLINE - STA. 22+50 - SHEET C203



**KEY NOTES**

- A** REPLACE DISTURBED ROAD WITH ASPHALT PAVEMENT. SEE DETAIL ON SHEET C601.
- B** EXISTING STORM SEWER. MAINTAIN SUFFICIENT WATER & SEWER SEPARATION. SEE DETAIL ON SHEET C601.
- C** EXISTING WATER MAIN. MAINTAIN SUFFICIENT WATER & SEWER SEPARATION. SEE DETAIL ON SHEET C601.
- D** EXISTING COMMUNICATIONS UTILITY
- E** EXISTING ELECTRIC UTILITY
- F** PROPOSED 6" SANITARY LATERAL, INSIDE RIGHT-OF-WAY. CONTRACTOR TO CAP FOR FUTURE CONNECTION
- G** REPLACE DEMOLISHED TREES IN KIND
- H** REMOVE TOP 5" OF MANHOLE AND BACKFILL. SEE DETAIL ON SHEET C602.
- I** GROUT AND ABANDON EXISTING SANITARY SEWER.
- J** LINE EXISTING MANHOLE.
- K** LINE EXISTING SANITARY SEWER FROM EX. MANHOLE TO TIE-IN AT SUGAR CREEK WWTP.
- L** CORE IN NEW SANITARY SEWER TO EXISTING MANHOLE. SEE DETAIL ON SHEET C602.
- M** CUT AND CAP EXISTING SANITARY SEWER. USE BYPASS PUMPING TO ALLOW FOR INSTALLATION OF PROPOSED SANITARY SEWER.
- N** USE INTERNAL DROP IN MANHOLE. SEE DETAIL ON SHEET C602.
- O** REPLACE EXISTING PIPE TO REPAIR SAG. MATCH EXISTING VERTICAL AND HORIZONTAL ALIGNMENT.

= GRANULAR BACKFILL




#	Revision	Date

Project #: 20-400-286-2  
Designed By: TAC  
Drawn By: JLB  
Checked By: ALC  
Date: 02/02/2023



*Aaron Crow*



**SANITARY SEWER  
PLAN & PROFILES**

**C202**



**RILEY VILLAGE SANITARY SEWER**

2243 E MAIN STREET  
GREENFIELD, IN 46140

BIDDING SET

#	Revision	Date
---	----------	------


Project #: 20-400-286-2

Designed By: TAC


Drawn By: JLB

Checked By: ALC

Date: 02/02/2023




*Aaron Crow*



**SANITARY SEWER  
PLAN & PROFILES**


**C203**



**KEY NOTES**

- A** REPLACE DISTURBED ROAD WITH ASPHALT PAVEMENT. SEE DETAIL ON SHEET C601.
- B** EXISTING STORM SEWER. MAINTAIN SUFFICIENT WATER & SEWER SEPARATION. SEE DETAIL ON SHEET C601.
- C** EXISTING WATER MAIN. MAINTAIN SUFFICIENT WATER & SEWER SEPARATION. SEE DETAIL ON SHEET C601.
- D** EXISTING COMMUNICATIONS UTILITY
- E** EXISTING ELECTRIC UTILITY
- F** PROPOSED 6" SANITARY LATERAL, INSIDE RIGHT-OF-WAY. CONTRACTOR TO CAP FOR FUTURE CONNECTION
- G** REPLACE DEMOLISHED TREES IN KIND
- H** REMOVE TOP 5" OF MANHOLE AND BACKFILL. SEE DETAIL ON SHEET C602.
- I** GROUT AND ABANDON EXISTING SANITARY SEWER.
- J** LINE EXISTING MANHOLE.
- K** LINE EXISTING SANITARY SEWER FROM EX. MANHOLE TO TIE-IN AT SUGAR CREEK WWTP.
- L** CORE IN NEW SANITARY SEWER TO EXISTING MANHOLE. SEE DETAIL ON SHEET C602.
- M** CUT AND CAP EXISTING SANITARY SEWER. USE BYPASS PUMPING TO ALLOW FOR INSTALLATION OF PROPOSED SANITARY SEWER.
- N** USE INTERNAL DROP IN MANHOLE. SEE DETAIL ON SHEET C602.
- O** REPLACE EXISTING PIPE TO REPAIR SAG. MATCH EXISTING VERTICAL AND HORIZONTAL ALIGNMENT.


= GRANULAR BACKFILL






BIDDING SET  
**RILEY VILLAGE SANITARY SEWER**

2243 E MAIN STREET  
GREENFIELD, IN 46140



**KEY NOTES**

- A** REPLACE DISTURBED ROAD WITH ASPHALT PAVEMENT. SEE DETAIL ON SHEET C601.
- B** EXISTING STORM SEWER. MAINTAIN SUFFICIENT WATER & SEWER SEPARATION. SEE DETAIL ON SHEET C601.
- C** EXISTING WATER MAIN. MAINTAIN SUFFICIENT WATER & SEWER SEPARATION. SEE DETAIL ON SHEET C601.
- D** EXISTING COMMUNICATIONS UTILITY
- E** EXISTING ELECTRIC UTILITY
- F** PROPOSED 6" SANITARY LATERAL, INSIDE RIGHT-OF-WAY. CONTRACTOR TO CAP FOR FUTURE CONNECTION
- G** REPLACE DEMOLISHED TREES IN KIND
- H** REMOVE TOP 5" OF MANHOLE AND BACKFILL. SEE DETAIL ON SHEET C602.
- I** GROUT AND ABANDON EXISTING SANITARY SEWER.
- J** LINE EXISTING MANHOLE.
- K** LINE EXISTING SANITARY SEWER FROM EX. MANHOLE TO TIE-IN AT SUGAR CREEK WWTP.
- L** CORE IN NEW SANITARY SEWER TO EXISTING MANHOLE. SEE DETAIL ON SHEET C602.
- M** CUT AND CAP EXISTING SANITARY SEWER. USE BYPASS PUMPING TO ALLOW FOR INSTALLATION OF PROPOSED SANITARY SEWER.
- N** USE INTERNAL DROP IN MANHOLE. SEE DETAIL ON SHEET C602.
- O** REPLACE EXISTING PIPE TO REPAIR SAG. MATCH EXISTING VERTICAL AND HORIZONTAL ALIGNMENT.



= GRANULAR BACKFILL

#	Revision	Date

Project #: 20-400-286-2

Designed By: TAC


Drawn By: JLB

Checked By: ALC

Date: 02/02/2023



*Aron Crow*



SANITARY SEWER  
PLAN & PROFILES

**C204**




**RILEY VILLAGE SANITARY SEWER**

BIDDING SET

2243 E MAIN STREET  
GREENFIELD, IN 46140


MATCHLINE - STA. 37+50 - SHEET C206



**KEY NOTES**

- A** REPLACE DISTURBED ROAD WITH ASPHALT PAVEMENT. SEE DETAIL ON SHEET C601.
- B** EXISTING STORM SEWER. MAINTAIN SUFFICIENT WATER & SEWER SEPARATION. SEE DETAIL ON SHEET C601.
- C** EXISTING WATER MAIN. MAINTAIN SUFFICIENT WATER & SEWER SEPARATION. SEE DETAIL ON SHEET C601.
- D** EXISTING COMMUNICATIONS UTILITY
- E** EXISTING ELECTRIC UTILITY
- F** PROPOSED 6" SANITARY LATERAL, INSIDE RIGHT-OF-WAY. CONTRACTOR TO CAP FOR FUTURE CONNECTION
- G** REPLACE DEMOLISHED TREES IN KIND
- H** REMOVE TOP 5" OF MANHOLE AND BACKFILL. SEE DETAIL ON SHEET C602.
- I** GROUT AND ABANDON EXISTING SANITARY SEWER.
- J** LINE EXISTING MANHOLE.
- K** LINE EXISTING SANITARY SEWER FROM EX. MANHOLE TO TIE-IN AT SUGAR CREEK WWTP.
- L** CORE IN NEW SANITARY SEWER TO EXISTING MANHOLE. SEE DETAIL ON SHEET C602.
- M** CUT AND CAP EXISTING SANITARY SEWER. USE BYPASS PUMPING TO ALLOW FOR INSTALLATION OF PROPOSED SANITARY SEWER.
- N** USE INTERNAL DROP IN MANHOLE. SEE DETAIL ON SHEET C602.
- O** REPLACE EXISTING PIPE TO REPAIR SAG. MATCH EXISTING VERTICAL AND HORIZONTAL ALIGNMENT.

█ GRANULAR BACKFILL




#	Revision	Date

Project #: 20-400-286-2  
Designed By: TAC  
Drawn By: JLB  
Checked By: ALC  
Date: 02/02/2023



*Aaron Crow*





SANITARY SEWER  
PLAN & PROFILES

**C205**



BIDDING SET  
**RILEY VILLAGE SANITARY SEWER**

2243 E MAIN STREET  
GREENFIELD, IN 46140



#	Revision	Date
---	----------	------


Project #: 20-400-286-2

Designed By: TAC


Drawn By: JLB

Checked By: ALC

Date: 02/02/2023



*Maron L. Crow*



**KEY NOTES**

- |   |   |   |  |   |
|---|---|---|--|---|
| <p>(A) REPLACE DISTURBED ROAD WITH ASPHALT PAVEMENT. SEE DETAIL ON SHEET C601.</p> <p>(B) EXISTING STORM SEWER. MAINTAIN SUFFICIENT WATER &amp; SEWER SEPARATION. SEE DETAIL ON SHEET C601.</p> <p>(C) EXISTING WATER MAIN. MAINTAIN SUFFICIENT WATER &amp; SEWER SEPARATION. SEE DETAIL ON SHEET C601.</p> | <p>(D) EXISTING COMMUNICATIONS UTILITY</p> <p>(E) EXISTING ELECTRIC UTILITY</p> <p>(F) PROPOSED 6" SANITARY LATERAL, INSIDE RIGHT-OF-WAY. CONTRACTOR TO CAP FOR FUTURE CONNECTION</p> | <p>(G) REPLACE DEMOLISHED TREES IN KIND</p> <p>(H) REMOVE TOP 5" OF MANHOLE AND BACKFILL. SEE DETAIL ON SHEET C602.</p> <p>(I) GROUT AND ABANDON EXISTING SANITARY SEWER.</p> | <p>(J) LINE EXISTING MANHOLE.</p> <p>(K) LINE EXISTING SANITARY SEWER FROM EX. MANHOLE TO TIE-IN AT SUGAR CREEK WWTP.</p> <p>(L) CORE IN NEW SANITARY SEWER TO EXISTING MANHOLE. SEE DETAIL ON SHEET C602.</p> | <p>(M) CUT AND CAP EXISTING SANITARY SEWER. USE BYPASS PUMPING TO ALLOW FOR INSTALLATION OF PROPOSED SANITARY SEWER.</p> <p>(N) USE INTERNAL DROP IN MANHOLE. SEE DETAIL ON SHEET C602.</p> <p>(O) REPLACE EXISTING PIPE TO REPAIR SAG. MATCH EXISTING VERTICAL AND HORIZONTAL ALIGNMENT.</p> |
|---|---|---|--|---|








**SANITARY SEWER  
PLAN & PROFILES**


**C206**



BIDDING SET  
**RILEY VILLAGE SANITARY SEWER**

2243 E MAIN STREET  
GREENFIELD, IN 46140

LEGEND	
	PROPOSED CONSTRUCTION LIMITS
	SILT FENCE
	TEMPORARY CONSTRUCTION ENTRANCE
	TEMPORARY/PERMANENT SEEDING
	CONCRETE WASHOUT
	DROP BAG INLET PROTECTION
	RIPRAP CHECK DAM PER INDOT STANDARD DRAWING NO. E 205-TECD-06




#	Revision	Date

Project #: 20-400-286-2  
Designed By: TAC  
Drawn By: JLB  
Checked By: ALC  
Date: 02/02/2023



*Maron Cron*



**EROSION CONTROL PLAN**  
**C500**

PRINT DATE: 3/18/24  
PLOT SCALE: 1:1  
EDIT DATE: 2/2/23 10:25 AM  
EDITED BY: MLYDY  
DRAWING FILE: P:\20-400-286-2 RILEY VILLAGE SANITARY SEWERS ACAD\PLAN SHEETS & WORKING DRAWINGS\C500 - EROSION CONTROL PLANS.DWG




- SILT FENCE**
- LOCATION**
- INSTALLED PARALLEL TO THE SLOPE CONTOUR
  - MINIMUM 10 FEET BEYOND THE TOE OF SLOPE TO PROVIDE A BROAD, SHALLOW SEDIMENT POOL.
  - ACCESSIBLE FOR MAINTENANCE (REMOVAL OF SEDIMENT AND SILT FENCE REPAIR)


- INSTALLATION**
1. LAYOUT THE LOCATION OF THE FENCE SO THAT IT IS PARALLEL TO THE CONTOUR OF THE SLOPE AND AT LEAST 10 FEET BEYOND THE TOE OF THE SLOPE TO PROVIDE A SEDIMENT STORAGE AREA. TURN THE ENDS OF THE FENCE UP SLOPE SUCH THAT THE POINT OF CONTACT BETWEEN THE GROUND AND THE BOTTOM OF THE FENCE END TERMINATES AT A HIGHER ELEVATION THAN THE TOP OF THE FENCE AT ITS LOWEST POINT.
  2. EXCAVATE AN EIGHT-INCH DEEP BY FOUR-INCH WIDE TRENCH ALONG THE ENTIRE LENGTH OF THE FENCE LINE. INSTALLATION BY PLOWING IS ALSO ACCEPTABLE.
  3. INSTALL THE SILT FENCE WITH THE FILTER FABRIC LOCATED ON THE UP-SLOPE SIDE OF THE EXCAVATED TRENCH AND THE SUPPORT POSTS ON THE DOWN-SLOPE SIDE OF THE TRENCH.
  4. DRIVE THE SUPPORT POSTS AT LEAST 18 INCHES INTO THE GROUND, TIGHTLY STRETCHING THE FABRIC BETWEEN THE POSTS AS EACH IS DRIVEN INTO THE SOIL. A MINIMUM OF 12 INCHES OF THE FILTER FABRIC SHOULD EXTEND INTO THE TRENCH. (IF IT IS NECESSARY TO JOIN THE ENDS OF THE TWO FENCE, USE THE WRAP JOINT METHOD SHOWN.)
  5. LAY THE LOWER FOUR INCHES OF FILTER FABRIC ON THE BOTTOM OF THE TRENCH AND EXTEND IT TOWARD THE UP-SLOPE SIDE OF THE TRENCH.
  6. BACKFILL THE TRENCH WITH SOIL MATERIAL AND COMPACT IT IN PLACE.

- MAINTENANCE**
- INSPECT WITHIN 24 HOURS OF A RAIN EVENT AND AT LEAST ONCE EVERY SEVEN CALENDAR DAYS.
  - IF FABRIC TEARS, STARTS TO DECOMPOSE, OR IN ANY WAY BECOMES INEFFECTIVE, REPLACE THE AFFECTED PORTION IMMEDIATELY. NOTE: ALL REPAIRS SHOULD MEET SPECIFICATIONS AS OUTLINED WITHIN THIS MEASURE.
  - REMOVE DEPOSITED SEDIMENT WHEN IT IS CAUSING THE FILTER FABRIC TO BULGE OR WHEN IT REACHES ONE-HALF THE HEIGHT OF THE FENCE AT ITS LOWEST POINT. WHEN CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED, REMOVE THE FENCE AND SEDIMENT DEPOSITS, GRADE THE SITE TO BLEND WITH THE SURROUNDING AREA, AND STABILIZE.


- EROSION AND SEDIMENT CONTROL NOTES:**
1. FURNISH AND INSTALL EROSION AND SEDIMENT CONTROL MEASURES IN ACCORDANCE WITH THE INDIANA STORM WATER QUALITY MANUAL.
  2. DURING ALL PHASES OF CONSTRUCTION, THE SITE GENERAL CONTRACTOR AND ALL SUBCONTRACTORS SHALL EXERCISE MEASURES TO PREVENT THE EROSION OF SOILS DUE TO THE ACTION OF WATER AND WIND. ALL STORM WATER POLLUTION PREVENTION MEASURES SHALL BE IMPLEMENTED PRIOR TO ANY LAND DISTURBANCE ACTIVITIES.
  3. THE USE OF ALTERNATIVE MATERIALS/PRODUCTS, SUCH AS FILTER SOCK, ETC., IN LIEU OF SILT FENCE, IS PERMITTED SUBJECT TO APPROVAL BY ENGINEER. ALTERNATIVE MATERIALS/PRODUCTS SHALL MEET OR EXCEED THE PERFORMANCE OF STORMWATER POLLUTION PREVENTION MEASURES SPECIFIED.
  4. OILS, HYDRAULIC FLUIDS, FUEL, GREASE, CONCRETE AND OTHER SPILLS ARE TO BE REMOVED FROM THE SITE AND DISPOSED OF ACCORDING TO ANY AND ALL APPLICABLE REGULATIONS.
  5. IF DETERMINED IS NECESSARY, CONTRACTOR SHALL USE TEMPORARY ROCK CHECK DAMS AND/OR TEMPORARY SEDIMENT TRAPS TO CONTROL STORMWATER POLLUTION AND IS NOT PERMITTED TO DISCHARGE DIRECTLY INTO ANY WATER BODY OR STORM SEWER SYSTEM UNLESS PUMP DISCHARGE BAGS ARE USED.
  6. ALL DISTURBED AREAS SHALL BE SEEDDED AND MULCHED AS SOON AS POSSIBLE WITH TEMPORARY OR PERMANENT SEEDING. NO DISTURBED AREA SHALL BE EXPOSED FOR MORE THAN 14 DAYS.
  7. CONTRACTOR SHALL MONITOR AND MAINTAIN STORMWATER POLLUTION PREVENTION MEASURES AND DEVICES FROM THE BEGINNING OF CONSTRUCTION UNTIL SUCH A TIME THAT SOIL IS STABILIZED IN ACCORDANCE WITH THE SCHEDULE ON THIS SHEET.
  8. CONTRACTOR SHALL REMOVE AND DISPOSE OF TEMPORARY STORMWATER POLLUTION PREVENTION DEVICES ONCE RISK OF ONSITE EROSION AND SITUATION NO LONGER EXIST.
  9. THE OWNER OR ENGINEER HAS THE AUTHORITY TO EITHER REQUEST ADDITIONAL STORMWATER POLLUTION PREVENTION MEASURES OF TO AMEND THE STORMWATER POLLUTION PREVENTION PLANS IN ORDER TO MEET ACTUAL SITE CONDITIONS.



**SILT FENCE DETAIL**  
NOT TO SCALE



**DROP BAG INLET PROTECTION**  
NOT TO SCALE



**TEMPORARY CONSTRUCTION ENTRANCE**  
NOT TO SCALE

**PERMANENT SEEDING**

**Application**

**Site Preparation**

1. GRADE THE SITE TO ACHIEVE POSITIVE DRAINAGE.
2. ADD TOPSOIL OR COMPOST MULCH TO ACHIEVE NEEDED DEPTH FOR ESTABLISHMENT OF VEGETATION. (COMPOST MATERIAL MAY BE ADDED TO IMPROVE SOIL MOISTURE HOLDING CAPACITY, SOIL FRIABILITY, AND NUTRIENT AVAILABILITY.)

**Seedbed Preparation**

1. TEST SOIL TO DETERMINE PH AND NUTRIENT LEVELS.
2. APPLY SOIL AMENDMENTS AS RECOMMENDED BY THE SOIL TEST AND WORK INTO THE UPPER TWO TO FOUR INCHES OF SOIL. IF TESTING IS NOT DONE, APPLY 400 TO 600 POUNDS PER ACRE OF 12-12-12 ANALYSIS FERTILIZER, OR EQUIVALENT.
3. TILL THE SOIL TO OBTAIN A UNIFORM SEEDBED. USE A DISK OR RAKE, OPERATED ACROSS THE SLOPE, TO WORK THE SOIL AMENDMENTS INTO THE UPPER TWO TO FOUR INCHES OF THE SOIL.

**Seeding**

OPTIMUM SEEDING DATES ARE MARCH 1 TO MAY 10 AND AUGUST 10 TO SEPTEMBER 30. PERMANENT SEEDING DONE BETWEEN MAY 10 AND AUGUST 10 MAY NEED TO BE IRRIGATED. SEEDING OUTSIDE OR BEYOND OPTIMUM SEEDING DATES IS STILL POSSIBLE WITH THE UNDERSTANDING THAT RESEEDING OR OVERSEEDING MAY BE REQUIRED IF ADEQUATE SURFACE COVER IS NOT ACHIEVED. RESEEDING OR OVERSEEDING CAN BE EASILY ACCOMPLISHED IF THE SOIL SURFACE REMAINS WELL PROTECTED WITH MULCH.

1. SELECT A SEEDING MIXTURE AND RATE FROM TABLE 1 PERMANENT SEEDING RECOMMENDATIONS. SELECT SEED MIXTURE BASED ON SITE CONDITIONS, SOIL PH, INTENDED LAND USE, AND EXPECTED LEVEL OF MAINTENANCE.
2. APPLY SEED UNIFORMLY WITH A DRILL OR CULTIPACKER SEEDER OR BY BROADCASTING. PLANT OR COVER THE SEED TO A DEPTH OF ONE-FOURTH TO ONE-HALF INCH. IF DRILLING OR BROADCASTING THE SEED, ENSURE GOOD SEED-TO-SOIL CONTACT BY FIRING THE SEEDBED WITH A ROLLER OR CULTIPACKER AFTER COMPLETING SEEDING OPERATIONS. (IF SEEDING IS DONE WITH A HYDROSEEDER FERTILIZER AND MULCH CAN BE APPLIED WITH THE SEED IN A SLURRY MIXTURE.)
3. MULCH ALL SEEDDED AREAS AND USE APPROPRIATE METHODS TO ANCHOR THE MULCH IN PLACE. CONSIDER USING EROSION CONTROL BLANKETS ON SLOPING AREAS AND CONVEYANCE CHANNELS.

**Maintenance**

- INSPECT WITHIN 24 HOURS OF EACH RAIN EVENT AND AT LEAST ONCE EVERY SEVEN CALENDAR DAYS UNTIL THE VEGETATION IS SUCCESSFULLY ESTABLISHED.
- CHARACTERISTICS OF A SUCCESSFUL STAND INCLUDE VIGOROUS DARK GREEN OR BLuishGREEN SEEDLINGS WITH A UNIFORM VEGETATIVE COVER DENSITY OF 90 PERCENT OR MORE.
- CHECK FOR EROSION OR MOVEMENT OF MULCH.
- REPAIR DAMAGED, BARE, GULLIED, OR SPARSELY VEGETATED AREAS AND THEN FERTILIZE, RESEED, AND APPLY AND ANCHOR MULCH.
- IF PLANT COVER IS SPARSE OR PATCHY, EVALUATE THE PLANT MATERIALS CHOSEN, SOIL FERTILITY, MOISTURE CONDITION, AND MULCH APPLICATION; REPAIR AFFECTED AREAS EITHER BY OVERSEEDING OR PREPARING A NEW SEEDBED AND RESEEDING. APPLY AND ANCHOR MULCH ON THE NEWLY SEEDDED AREAS.
- IF VEGETATION FAILS TO GROW, CONSIDER SOIL TESTING TO DETERMINE SOIL PH OR NUTRIENT DEFICIENCY PROBLEMS. (CONTACT YOUR SOIL AND WATER CONSERVATION DISTRICT OR COOPERATIVE EXTENSION OFFICE FOR ASSISTANCE.) IF ADDITIONAL FERTILIZATION IS NEEDED TO GET A SATISFACTORY STAND, DO SO ACCORDING TO SOIL TEST RECOMMENDATIONS.
- ADD FERTILIZER THE FOLLOWING GROWING SEASON. FERTILIZE ACCORDING TO SOIL TEST RECOMMENDATIONS.
- FERTILIZE TURF AREAS ANNUALLY. APPLY FERTILIZER IN A SPLIT APPLICATION. FOR COOL-SEASON GRASSES, APPLY ONE-HALF OF THE FERTILIZER IN LATE SPRING AND ONE-HALF IN EARLY FALL. FOR WARM-SEASON GRASSES, APPLY ONE-THIRD IN EARLY SPRING, ONE-THIRD IN LATE SPRING, AND THE REMAINING ONE-THIRD IN MIDDLE SUMMER.

**Table 1 Permanent Seeding Recommendations**

THIS TABLE PROVIDES SEVERAL SEED MIXTURE OPTIONS. ADDITIONAL SEED MIXTURES ARE AVAILABLE COMMERCIALY. WHEN SELECTING A MIXTURE, CONSIDER INTENDED LAND USE AND SITE CONDITIONS, INCLUDING SOIL PROPERTIES (E.G., SOIL PH AND DRAINAGE), SLOPE ASPECT, AND THE TOLERANCE OF EACH SPECIES TO SHADE AND DROUGHT.


**Open Low-Maintenance Areas (Remaining idle more than six months)**

Seed Mixtures	Rate per Acre Pure Live Seed	Optimum Soil pH
1. Perennial ryegrass - white clover 1	70 lbs. 2 lbs.	5.6 to 7.0
2. Perennial ryegrass - tall fescue 2	70 lbs. 50 lbs.	5.6 to 7.0
3. Tall fescue 2 - white clover 1	70 lbs. 2 lbs.	5.5 to 7.5

**TEMPORARY SEEDING SPECIFICATIONS**


SEED SPECIES	RATE PER ACRE	PLANTING DEPTH	OPTIMUM DATES
WHEAT OR RYE	150 LBS	1 TO 1-1/2 INCHES	SEPT. 15 - OCT. 30
SPRING OATS	100 LBS	1 INCH	MAR. 1 - APR. 15
ANNUAL RYEGRASS	40 LBS	1/4 INCH	MAR. 1 - MAY 1 AUG. 1 - SEPT. 1
GERMAN MILLET	40 LBS	1 TO 2 INCHES	MAY 1 - JUNE 1
SUDANGRASS	35 LBS	1 TO 2 INCHES	MAY 1 - JULY 30
BUCKWHEAT	60 LBS	1 TO 2 INCHES	APR. 15 - JUNE 1
CORN (BROADCAST)	300 LBS	1 TO 2 INCHES	MAY 11 - AUG. 10
SORGHUM	35 LBS	1 TO 2 INCHES	MAY 1 - JULY 15

**GENERAL STAPLE RECOMMENDATIONS**



- NOTE:**
1. CHANNEL LINING UTILIZE STAPLE PATTERN "C" WITH ADDITIONAL STAPLES ON SIDE SLOPES AT PROJECTED WATER LINE.
  2. STAPLE PATTERNS APPLY TO ALL NORTH AMERICAN GREEN EROSION CONTROL BLANKETS. STAPLE PATTERNS MAY VARY DEPENDING UPON SOIL TYPE AND AVERAGE RAINFALL.
  3. AT SLOPE LENGTHS GREATER THAN 300 FEET OR WHERE DRAINAGE OVER LARGE AREAS IS DIRECTED ONTO THE BLANKETS, STAPLE PATTERN "C" SHOULD BE UTILIZED.

**EROSION CONTROL MAT INSTALLATION GUIDE DETAIL**  
NOT TO SCALE



**TEMPORARY DEWATERING**

**EROSION CONTROL DETAILS**

**C501**



*Aaron Crow*

Project #: 20-400-286-2  
Designed By: TAC  
Drawn By: JLB  
Checked By: ALC  
Date: 02/02/2023



#	Revision	Date


Project #: 20-400-286-2

Designed By: TAC

Drawn By: JLB

Checked By: ALC

Date: 02/02/2023



*Aaron Crow*

**STORMWATER POLLUTION PREVENTION PLAN**

**C502**

**CONSTRUCTION/STORMWATER POLLUTION PREVENTION PLAN**

**ASSESSMENT OF CONSTRUCTION PLAN ELEMENTS (SECTION A)**

**A1 PLAN INDEX SHOWING LOCATIONS OF REQUIRED ITEMS:**  
See cover sheet for index of construction plan sheets and this sheet for index of required SWPPP components – Sections A, B, and C.

**A2 18X24 PLAT SHOWING SITE, BUILDINGS, PARKING LOTS, STREETS:**  
See C201 for an overall plot showing existing site, buildings, lots, lot numbers, and streets.

**A3 NARRATIVE DESCRIBING PROJECT NATURE AND PURPOSE:**  
The proposed project includes the installation of approximately 3,600 linear feet of 8" gravity sewer with 48" manholes and 6" laterals.

**A4 VICINITY MAP SHOWING PROJECT LOCATION:**  
See cover sheet.

**A5 LEGAL DESCRIPTION OF THE PROJECT SITE:**  
The project is located in the NW quarter, Section 23, Township 16N, Range 6E in Center Township. The latitude and longitude are 39°49'36.36"N, 85°50'6.99"W

**A6 LOCATION OF ALL LOTS AND PROPOSED SITE IMPROVEMENTS:**  
See sheet(s) C200–C206

**A7 HYDROLOGIC UNIT CODE-14 D10T:**  
05120204060040 – Sugar Creek–Boyd Ditch

**A8 NOTATION OF ANY STATE OR FEDERAL WATER QUALITY PERMITS:**  
IDEM Rule 5 Permit

**A9 SPECIFIC POINTS WHERE STORMWATER DISCHARGE WILL LEAVE THE SITE:**  
Stormwater runoff will discharge to Fountain Lake.

**A10 LOCATION AND NAME OF ALL WETLANDS, LAKES AND WATER COURSES ON AND ADJACENT TO THE SITE:**  
Fountain Lake, a manmade water body, is adjacent to the project site.

**A11 IDENTIFICATION OF ALL RECEIVING WATERS:**  
The stormwater runoff from the site will discharge to Sugar Creek.

**A12 IDENTIFICATION OF POTENTIAL DISCHARGE TO GROUNDWATER:**  
None

**A13 100 YEAR FLOODPLAINS, FLOODWAYS, AND FLOODWAY FRINGES:**  
This project is not located within a floodplain or a floodway.

**A14 PRE-CONSTRUCTION AND POST CONSTRUCTION ESTIMATE OF PEAK DISCHARGES:**  
10YR PRE = 0.11 CFS 100YR PRE = 0.16 CFS  
10YR POST = 0.11 CFS 100YR POST = 0.16 CFS

**A15 ADJACENT LAND USE, INCLUDING UPSTREAM WATERSHED:**  
South–Agricultural  
North–Agricultural  
East–Residential  
West–Agricultural/Industrial

**A16 LOCATIONS AND APPROXIMATE BOUNDARIES OF ALL DISTURBED AREAS:**  
See sheet(s) C501 for construction limits.

**A17 IDENTIFICATION OF EXISTING VEGETATIVE COVER:**  
See sheets C201–C207

**A18 SOILS MAP INCLUDING DESCRIPTIONS AND LIMITATIONS:**  
See this sheet for soils descriptions and limitations.

**A19 LOCATION, SIZE AND DIMENSIONS OF PROPOSED STORMWATER SYSTEMS:**  
See sheet C501

**A20 PLAN FOR ANY OFF-SITE CONSTRUCTION ACTIVITIES ASSOCIATED WITH THIS PROJECT:**  
None

**A21 LOCATIONS OF PROPOSED SOIL STOCKPILES, BORROW AND/OR DISPOSAL AREAS:**  
The Contractor may place proposed soil stockpiles and borrow in the area located to the northeast of the neighborhood entrance. No disposal areas are proposed for this project.


**A22 EXISTING SITE TOPOGRAPHY AT AN INTERVAL APPROPRIATE TO SHOW DETAILED DRAINAGE PATTERNS:**  
See existing topographic survey

**A23 PROPOSED FINAL TOPOGRAPHY AT AN INTERVAL APPROPRIATE TO SHOW DETAILED DRAINAGE PATTERNS:**  
See Sheet(s) C500

**ASSESSMENT OF STORMWATER POLLUTION PREVENTION PLAN-CONSTRUCTION COMPONENT (SECTION B)**

**B1 DESCRIPTION OF POTENTIAL POLLUTANT SOURCES ASSOCIATED WITH CONSTRUCTION ACTIVITIES:**  
The primary pollutant associated with construction activities is sediment. Additional pollutants may be generated by construction vehicle operation and maintenance (e.g. fueling, changing hydraulic fluids and oils); concrete washout; improper storage of construction materials; improper disposal of construction trash and debris; improper application or over application of fertilizers and pesticides; and improper storage, application, and disposal of soluble materials or other materials that may be mobilized by storm water runoff. Equipment and fuel will be stored in a central location and the contractor shall institute methods and procedures to prevent discharge of pollutants.

**SOILS MAP**



**ASSESSMENT OF STORMWATER POLLUTION PREVENTION PLAN-CONSTRUCTION COMPONENT (SECTION B) CONTINUED**

**B2 SEQUENCE DESCRIBING STORMWATER QUALITY MEASURE IMPLEMENTATION RELATIVE TO LAND DISTURBING ACTIVITIES:**  
See erosion and sediment control sequences and implementation on this sheet.

**B3 STABLE CONSTRUCTION ENTRANCE LOCATIONS AND SPECIFICATIONS:**  
The proposed construction entrance can be found on Sheet C500. See Sheet C501 for detail.

**B4 SEDIMENT CONTROL MEASURES FOR SHEET FLOW AREAS:**  
Preliminary grading and stabilization must be completed to ensure adequate drainage to the temporary or permanent runoff conveyance facilities. Silt fencing must also be implemented prior to any construction activity to ensure silt collection. Stabilize disturbed areas directly after earth disturbing activities. Temporary seed areas scheduled to be idle for up to 15 days. Permanently seed all areas that are at final grade, phase projects where each subsequent phase will not begin for 8 months or more, and areas to be idle for more than one year. Erosion control measures to be installed in sheet flow area. See Avon Town Standards for details as well as installation and maintenance procedures. See this sheet for seeding guidelines.

**B5 SEDIMENT CONTROL MEASURES FOR CONCENTRATED FLOW AREAS:**  
Adequate erosion control measures must be installed within these areas prior to opening for runoff acceptance. Stabilize disturbed areas directly after earth disturbing activities. Temporary seed areas scheduled to be idle for up to one year. Ensure that the project is not idle for more than 7 days without temporary seeding. Permanently seed all areas that are at final grade, phase projects where each subsequent phase will not begin for 8 months or more, and areas to be idle for more than one year. See sheet C501 for erosion control measures to be installed in concentrated flow areas.

**B6 SEDIMENT CONTROL MEASURES FOR STORM SEWER INLETS PROTECTION:**  
See sheet C500 and this sheet.

**B7 RUNOFF CONTROL MEASURES:**  
See sheet C500 and this sheet.

**B8 STORMWATER OUTLET PROTECTION SPECIFICATIONS:**  
See sheet C501.

**B9 GRADE STABILIZATION STRUCTURE LOCATIONS AND SPECIFICATIONS:**  
See sheet C500.

**B10 LOCATION, DIMENSIONS, SPECIFICATIONS AND CONSTRUCTION DETAILS FOR EACH STORMWATER QUALITY MEASURE:**  
See sheet(s) C500, this sheet, and associated erosion control details on sheet C502.

**B11 TEMPORARY SURFACE STABILIZATION METHODS APPROPRIATE FOR EACH SEASON:**  
See sheet(s) C501 and "General Seeding & Surface Stabilizing Procedures" on this sheet.

**B12 PERMANENT SURFACE STABILIZATION SPECIFICATIONS:**  
See sheet(s) C501 and "General Seeding & Surface Stabilizing Procedures" on this sheet.

**B13 MATERIAL HANDLING AND SPILL PREVENTION:**  
Expected construction materials on site may include vehicle lubricants, oils, vehicular fuels, concrete wash-out, acids, curing compounds, paints, mulch, pesticides, herbicides, fertilizer, and trash. Any toxic waste materials are to be disposed of according to local and state laws. Small spills and leaks of these materials onto non-paved areas will be shoveled into containers or dumpsters for proper disposal. Fueling trucks will be equipped with spill prevention kits for smaller fuel spills. All vehicular maintenance shall be performed in the same designated area throughout the construction time frame. If possible, vehicular maintenance shall be done off-site at facilities that are designed to handle any material spillage. This shall include fueling of vehicles whenever possible. In case of spill call 911. Call the Indiana Department of Environmental Management, office of emergency response (800)–233–7745. Shall be notified immediately for larger spills or leaks. The National Response Center (800)–424–8802 shall be notified and provided with the following information: time of spill, location of spill, material, source of spill, approximate volume and length of spillage, weather conditions at time of spill, personal present at time of spill, and all action taken for post spill cleanup. Contractor shall contact a waste recovery agency immediately for removal of contaminants and coordination of monitoring the site during cleanup until all of the hazardous material has been removed. Contractor shall cooperate with idem during and after the spill to insure all required cleanup and filing reports are properly submitted. The developer shall be continually informed of any contamination concerns occurring on the site. The construction manager shall keep on site a list of qualified contractors for spill remediation. All site personnel, including maintenance employees, shall be made aware of proper spill prevention and remediation techniques. All materials used to absorb spills shall be properly disposed of in an approved manner with local and state laws. Do not flush spill materials with water unless directed to do so by a governing agency. It is important that all manufacturer's instructions be followed when using or applying all fertilizers, herbicides, and pesticides.

**B14 MONITORING AND MAINTENANCE GUIDELINES FOR EACH PROPOSED STORM WATER QUALITY MEASURE:**  
See sheet(s) C501 for each storm water quality measure.

**B15 EROSION AND SEDIMENT CONTROL SPECIFICATIONS FOR INDIVIDUAL BUILDING LOTS:**  
N/A

**ADDITIONAL EROSION AND SEDIMENT CONTROL INFORMATION (WHERE APPLICABLE)**

**EROSION AND SEDIMENT CONTROL PROVISION FOR STREAM / CHANNEL CROSSINGS:** NONE

**SEDIMENT CONTROL ASSOCIATED WITH DEWATERING AND DIRECTIONAL BORING OPERATION:**  
Sediment laden water shall not be pumped to storm sewer outlets or natural drainage ways. Disposal shall be confined to areas not subject to sheet flow runoff where the effluent can be dried out. This restriction shall apply to areas where lime stabilization has been implemented. Maintenance and inspection are required for proper de-watering procedures.

**HANCOCK COUNTY SOILS CHARACTERISTICS AND LIMITATIONS**

- Br – BROOKSTON SILTY CLAY LOAM, 0 TO 2 % SLOPES
- CrA – CROSBY SILT LOAM, NEW CASTLE TILL PLAIN, 0 TO 2 % SLOPES
- MmB2 – MIAMI SILT LOAM, 2 TO 6 % SLOPES, ERODED
- Or – ORTHENTS
- W – WATER

**EROSION CONTROL SPECIFICATIONS**

**A. SCOPE OF WORK**

1. The work required under this section includes erosion and sediment control measures for construction activities as required by local, state and federal jurisdictions including but not limited to County Soil & Water District, Local MS4, Indiana Department of Environmental Management and the Environmental Protection Agency.

**B. MATERIALS**

1. Materials required for this section are provided under the Stormwater Pollution Prevention Plans, Erosion & Sediment Control Notes, and Details.

**C. GENERAL**

1. This plan is designed as an attempt to prevent any and all sediment from leaving the construction site by way of erosion. If erosion of sediment from the site is taking place, the owner shall take preventative action immediately. The Engineer shall be consulted in the event this happens.
2. This plan is designed to be applied within 7 days if no work is anticipated in an area of disturbed soil within 15 days.
3. Permanent seeding is to be applied immediately to areas that have achieved final and finished grade.
4. Preserve existing vegetation on the site whenever possible to prevent topsoil erosion.
5. All sediment capturing measures are to be implemented prior to the disturbance of the construction area they are intended to serve.
6. All erosion control measures proposed are to be properly maintained to continue their effectiveness.
7. If all grades occur during December, January or February dormant seeding procedures shall be used.
8. During dry weather, keep lawns watered with sprinklers or other approved methods. Reseed any areas not germinating or damaged at intervals as may be required according to seasonal condition and/or construction activity. Water grass and execute necessary weeding until full stand of grass has been obtained.
9. The implementation and maintenance of the erosion control is the sole responsibility of the contractor and/or owner.
10. It shall be the Contractor's and/or Owner's responsibility to minimize sedimentation (from on-site construction activities) from being deposited onto adjacent properties and receiving streams/ditches in strict compliance with the United States Environmental Protection Agency (U.S. EPA) and the Indiana Department of Environmental Management (IDEM) Storm Water Phase II criteria. It shall also be the Contractor's and/or owner's responsibility to obtain approvals required from the local authority having jurisdiction and to submit a complete Notice of Intent form to the Indiana Department of Environmental Management (IDEM) prior to the start of any construction activities.
11. Provide 12" minimum of INDOT #2 crushed stone on filter fabric construction entrance(s) to site from streets/roads. See details for additional information.
12. Contractor shall at all times insure that erosion control measures protecting draining facilities be placed prior to the commencement of any phase of construction or land alteration activity.
13. As soon as areas are brought to finished grade or new drainage facilities are constructed, contractor shall construct the applicable erosion control measure required by and delineated on the approved plan.
14. During site construction activity, the contractor shall:
  - a. Construct all perimeter silt barriers.
  - b. Install and maintain clean crushed stone at all construction entrances/exits to the site and any areas used for parking.
  - c. Prevent construction silts from leaving the site at all times and place excavated materials away from any direct flow runoff from the site.
15. Temporary vegetation shall be installed within 7 days following completion of any phase of grading.
16. Contractor shall inspect all erosion control measures daily and repair as necessary to prevent erosion. Siltation shall be removed from areas where failures have occurred, and corrective action shall be taken within 24 hours to maintain all erosion control.
17. Perimeter siltation barriers shall be maintained at all times.
18. At such time that rough grading of the site is complete and drainage divers to inlets, inlet erosion control measures shall be installed at all inlet structures to keep piping system free of siltation.
19. Erosion control measures, construction entrances and siltation barriers shall remain in place until a good stand of grass has been obtained and/or paving operations are complete. After this has been accomplished, all silt in pipes, detention facilities and swales be removed within 10 days so finished grades are met.
20. Once construction is complete and prior to the contractor handing over the project to the owner, the contractor shall clean all debris, pollutants, and sediment from the detention pond and forebay.

**SPILL PREVENTION PLAN**


All fueling and servicing of vehicles on site will be conducted near the construction entrance/staging area. This area shall be contained with a row of staked strawbales around the perimeter. Secondary containment in the form of drip pans or drop cloths shall be used to contain any spills. The contractor shall maintain a supply of oil-absorbent material to clean up any small spills that may occur. Any spillage will be removed immediately. Used absorbent material shall be removed from the site and disposed of in accordance with the laws of the State of Indiana. Contaminated soils will be placed on heavy plastic and covered or placed into approved containers to prevent contact with storm water. All fuel tanks we be in the containment area. Oils, other vehicle fluids, paints and solvents will be stored in the construction trailer. Any spills in excess of two gallons will be reported to a representative of the contractor.

If a release containing hazardous substance in an amount equal to or in excess of a reporting quantity established under either 40 CFR 117 or 40 CFR 302 occurs during a 24-hour period, the contractor will immediately notify the permittee who shall then do the following: notify National Response Center (NRC) (800-424-8802) and the Indiana State Emergency Management Agency (317-232-3986); as well as Local/County Emergency Management, the Local Fire Department (911), and Hendricks County Engineering Department. Also, the engineer will prepare a revision to this document to identify measures to prevent the recurrence of such releases.

Concrete trucks will wash out at the designated area near the construction entrance. The contractor shall take care to insure that no waste materials are discharged into the waters of the state. Each contractor is responsible to provide litter control for trash generated by his crew. All trash including but not limited to; solid waste, paint cans, oil cans, used oil and filters will be contained and disposed of by the contractor in accordance with the laws and regulations of the State of Indiana and Local/County requirements.

The contractor shall furnish and maintain sanitary facilities for this project. The facilities shall be cleaned as necessary and the waste materials shall be disposed of in accordance with the laws and regulations of the State of Indiana and Local/County requirements.






- NOTES:**
- MANHOLE STEPS SHALL BE POLYPROPYLENE, POLYPROPYLENE COATED STEEL REINFORCING OR APPROVED NON-CORROSIVE FIBERGLASS MATERIAL. COPOLYMER POLYPROPYLENE SHALL MEET ASTM D-4101 REINFORCED WITH DEFORMED 3/8" STEEL MEETING ASTM A-615, GRADE 60.
  - MANHOLE CONFORMS TO ASTM C-478 JOINT CONFORMS TO ASTM C-443

**TYPICAL MANHOLE DETAIL**


NOT TO SCALE



- NOTE:**  
IF THE NEAREST MANHOLE IS NOT AT LEAST ONE (1) FOOT BELOW THE ELEVATION OF THE LOWEST AREA TO BE SERVED, A GRINDER STATION WILL BE REQUIRED.

**GRAVITY CONNECTION DETAIL**

NOT TO SCALE




- NOTES:**
- WATER MAIN AND SEWER MINIMUM SEPARATION: 18" VERTICAL SEPARATION 10'-0" HORIZONTAL SEPARATION.

**SEPARATION REQUIREMENTS FOR WATER & SEWER**

NOT TO SCALE


**TYPICAL CLEANOUT DETAIL**

NOT TO SCALE



**ASPHALT PAVEMENT REPLACEMENT**


NOT TO SCALE



**CONCRETE PAVEMENT REPLACEMENT**

NOT TO SCALE


PIPE SIZE	BELOW 6"	8" TO 15"	18" & OVER
BEDDING BELOW THE PIPE BARREL - X"	O.D./8 4" MIN.	O.D./8 4" MIN.	O.D./8 4" MAX.



- \* TRENCH WIDTHS AND BEDDING REQUIREMENTS TO BE IN CONFORMANCE WITH MANUFACTURER'S RECOMMENDATIONS.**


**TYPICAL SANITARY SEWER TRENCH AND PIPE BEDDING DETAIL**

NOT TO SCALE



- ALL JOINTS SHALL HAVE EXTERIOR JOINT WRAP MEETING THE REQUIREMENTS OF ASTM C-877 (PRIME EXTERIOR OF JOINTS WITH BITUMINOUS PRIMER PRIOR TO WRAPPING)**


- CONCRETE GRADING RINGS MAXIMUM OF TWO RINGS 3", 4", 6", HEIGHTS



- NOTE:**
- MINIMUM CONCRETE STRENGTH: 4500 PSI AT 28 DAYS.
  - PRECAST GRADE RINGS SHALL CONTAIN WATER PROOFING ADDITIVE, XYPEX OR EQUIVLENT.



**STANDARD CASTING ADJUSTMENT & GRADE RINGS**

NOT TO SCALE



**SANITARY SERVICE CONNECTION DETAIL**

NOT TO SCALE



- NOTE:**
- WALLS SHALL BE FLARED OUT AS REQUIRED SO THAT TESTING EQUIPMENT CAN BE SAFELY REMOVED.
  - ALL NON-TYPICAL BENCHES AND CHANNELS WILL REQUIRE A SPECIAL DETAIL ON THE PLANS.

**STANDARD MANHOLE - BENCHES AND CHANNELS**

NOT TO SCALE

#	Revision	Date

Project #: 20-400-286-2

Designed By: TAC


Drawn By: JLB

Checked By: ALC

Date: 02/02/2023



*Marlon Crow*



**CONSTRUCTION DETAILS**

**C600**




#	Revision	Date

Project #: 20-400-286-2  
Designed By: TAC  
Drawn By: JLB  
Checked By: ALC  
Date: 02/02/2023




*Aaron Crow*




- NOTES:
1. PROVIDE CLEARANCE AROUND SIDEWALLS STRUCTURE FOR CONSTRUCTION OPERATIONS.
  2. IF GROUNDWATER IS ENCOUNTERED, PREVENT ACCUMULATION OF WATER IN EXCAVATION.
  3. WHERE POSSIBILITY EXISTS OF STRUCTURE BECOMING BUOYANT IN FLOODED EXCAVATION, ANCHOR STRUCTURE TO AVOID FLOTATION, AS APPROVED BY ENGINEER.

**STANDARD MANHOLE BACKFILL**  
NOT TO SCALE




- NOTES:
1. REMOVE EXISTING INTERIOR BENCH AND RE-POUR BENCHES AND CHANNELS.
  2. VERIFY THE CONDITION OF THE PRECAST BASE AFTER REMOVAL OF THE INTERIOR BENCH TO DETERMINE IF STRUCTURAL INTEGRITY HAS BEEN COMPROMISED DURING REMOVAL. IF REMOVAL IS IMPRACTICAL OR UNSUCCESSFUL, THE ENTIRE BASE SECTION SHALL BE REPLACED.

**NEW PIPE CONNECTION TO EXISTING MANHOLE**  
NOT TO SCALE




**TRACER WIRE INSTALLATION DETAIL**  
SCALE : NOT TO SCALE




- NOTES:
1. ALL MATERIAL, DESIGN, MANUFACTURE, PHYSICAL TEST REQUIREMENTS, FINISH MARKING, INSPECTION, REJECTION AND REPAIRS TO MEET / OR EXCEED "SPECIFICATIONS FOR PRECAST-REINFORCED CONCRETE MANHOLE SECTIONS", PER ASTM C-478 (LATEST REVISION).
  2. RESILIENT CONNECTORS MEET "SPECIFICATIONS FOR RESILIENT CONNECTORS BETWEEN REINFORCED CONCRETE MANHOLE STRUCTURES, PIPES AND LATERALS", PER ASTM C-923 (LATEST REVISION). RESILIENT CONNECTORS SHALL MEET AND/OR EXCEED ASTM C-478 GASKET REQUIREMENTS. 1" MASTIC BUTYL WILL BE ADDED BETWEEN THE JOINTS OF THE PRECAST DROP AND SHALL BE TIED INTO THE BARREL SECTION SEALANT. ALL ANGLES AND FALL SHALL BE ACCORDING TO PLANS.
  3. 33" DROP MINIMUM REQUIRED. DROP IS 8" PIPE ONLY. IF DROP REQUIRES GREATER THAN 8" PIPE, A SPECIAL DETAIL WILL BE REQUIRED FOR APPROVAL.
  4. REQUIRED ON ALL DROPS GREATER THAN 24".

**PRECAST EXTERNAL DROP MANHOLE**  
SCALE : NOT TO SCALE



**INTERNAL DROP MANHOLE**  
NOT TO SCALE



**EXISTING MANHOLE BACKFILL**  
NOT TO SCALE

PRINT DATE: 3/19/24  
PLOT SCALE: 1:1  
DRAWING FILE: P:\20-400-286-2\RILEY VILLAGE SANITARY SEWERS\ACAD\PLAN SHEETS & WORKING DRAWINGS\C600 - STANDARD DETAILS.DWG  
EDITED BY: MLOYD  
DATE: 2/2/23 - 10:18 AM